

RAJA JEJURICHA ELECTRICAL & CONTRACTOR

* Gov. Licensed Electrical Contractor
* All Type HT LT DTC Installation Work
* M.S.E.T.C.L. Registered contractor

* M.S.E.D.C.L Authorised Contractor
* Repair & Maintenance And All Type Work.
* Railway Vender No :- IREPS-1065748

Office:- A/P Waregaon Ta. Phulambri Dist Aurangabad 8530274478/9673150879 Akshaybikalab95@gmail.com

RJE/QTS/2021-22/25 **QUOTATION**

Dtd :- 25/07/2022

To,
Parashra Krishi Farmer Producer company Limited
Phulambri Ta Phulambri Dist. Aurangabad

Item Code No. 1203					
POLE MOUNTED DISTRIBUTION TRANSFORMER SUB-STATION 100KVA, 11/0.433 KV ON 9 mtr RSJ POLE					
S.N.	Description of Material	Unit	QTY	RT/U.Rs.	Amt Rs.
1	Dist. Transformer 100 KVA, 11/0.43 kv	No.	1	210000.00	210000.00
2	RSJ 116x100, 9 m long	No	2	14800.00	29600.00
3	MS Channel 100x50x6 mm	Kg.	200	75.00	15000.00
4	M.S.Channel 75x40x6 mm	kg.	70	75.00	5250.00
5	MS angle 50x50x6 mm	kg.	55	75.00	4125.00
6	M.S.Flat 50 x 6 mm	kg.	40	75.00	3000.00
7	11 kV Pin Insulators with G.I. Pins	NO.	3	240.00	720.00
8	Strain Hardware for Dog0.1 or Equ.AAAC.	No.	3	360.00	1080.00
9	L.T.Dist.Boxes 100 KVA with MCCB	No.	1	18000.00	18000.00
10	L.As. 11 KV (Gapless type) with disconnector	Set.	1	3500.00	3500.00
11	H.T.Stay Set	No	4	1800.00	7200.00
12	G.I.Stay Wire 7/4mm(8 SWG)	kg.	25	85.00	2125.00
13	Earthing Sets H.T	No.	3	342.00	1026.00
14	11KV H.G.Fuses	Set.	1	4000.00	4000.00
	11KV A.B. Switch, 400 A	No.	1	15000.00	15000.00
15	Danger Board in yard.	No.	2	70.00	140.00
16	G.I.Wire 8 SWG/ 6 SWG	Kg.	25	85.00	2125.00
17	G.I.Barbed Wire 'A' type.	kg.	15	85.00	1275.00
18	Concreting ration 1:3:6	CMT.	2	3027.00	6054.00
19	Painting/Hardware & support with numbering of pole	L.S.	1	225.00	225.00
20	Sundries	L.S.	1	810.00	810.00
21	DTC Metring with Box, single core L.T. XLPE cable (70 sq.mm., 120 mtr length) and other allied material.	No.	1	7529.20	7529.20

Cost of material

337784.20

M/s. Raja Jejuricha Electrical & Contractor


Proprietor

RAJA JEJURICHA ELECTRICAL & CONTRACTOR

* Gov. Licensed Electrical Contractor
* All Type HT LT DTC Installation Work
* M.S.E.T.C.L. Registered contractor

* M.S.E.D.C.L Authorised Contractor
* Repair & Maintenance And All Type Work.
* Railway Vender No :- IREPS-1065748

Office:- A/P Waregaon Ta.Phulambri Dist Aurangabad 8530274478/9673150879 [Akshaybakal.ab95@gmail.com](mailto:akshaybakal.ab95@gmail.com)

Item Code No. 0901					
11 KV Pin type line with ACSR weasel Conductor & 200 Kg PSC Poles					
S.N.	Description of Material	Unit	QTY	RT/U.Rs.	Amt Rs.
2	M.S. Flats(50 X 10mm)	Kg.	25	75.00	1875.00
3	11 KV V cross arm with clamp	No.	1	900.00	900.00
4	11 KV Top fitting with clamp	No.	1	250.00	250.00
5	M.S.Channel 75x40x6 mm	Kg.	12	75.00	900.00
7	Disc Insulator 11 KV 70 KN	No.	6	460.00	2760.00
8	11 kv Pin Insulators with G.I. Pins	No.	3	240.00	720.00
9	ACSR Weasel	Rmt	300	20.00	6000.00
10	Strain Hardware for Weasel/Squirrel	Set	6	460.00	2760.00
12	H.T.Stay Set	No.	3	1800.00	5400.00
13	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	30	85.00	2550.00
14	Earthing Sets H.T	No	1	600.00	600.00
15	G.I.Barbed Wire 'A' type.	Kg.	6	85.00	510.00
16	Danger Board in yard.	No.	1	70.00	70.00
18	Red Oxide Paint for 2 coats	Ltr.	3	220.00	660.00
20	G.I.Wire 8 SWG/ 6 SWG	Kg.	5	85.00	425.00
21	Concreting ration 1:3:6	LS	1	3027.00	3027.00
22	Sundries	LS	2	810.00	1620.00
Cost of material 11 kv line					31027.00
Cost of material DTC 100 KVA					337784.20
Labour Charges + Sanction					50000
Licensing Charge					15000
Transportation					10000
Total Amount					443811.20

GST Extra For Bill

M/s. Raja Jejuricha Electrical & Contractor


Proprietor