

A.M. TECHNOLOGY AND ENGINEERING LLP

Office Address: - SR No-135, Mohan nagar, Chinchawad, Pune -19, Maharashtra (India)

Work Address:- 15/1,Gujarwadi Road, Next to Ashvee Company, In Front Of Manish Industries, Katraj, Pune -46

Cell No. 91 7775026727, Email: amtechengg207@gmail.com

Ref. No. AMTE/Sales/Global/2022-23/32-Amended R1

Date: 28.08.2022

To,

Director,

Mahatma Jyotiba Fule Farmer Producer company Limited.

Kathi (Birsola), Gondia.

Kind Attention: **Mr. Mukesh Sir**

Subject : Offer for 1000 kg per hour Dehydration Line Machinery

Reference :

Dear Sir,

Greetings.

This is with respect to the above subject and reference – we are pleased to submit our techno commercial offer for your approval.

We are waiting for your valuable order with advance.

Regards

For A. M. Technology And Engineering LLP,

Director



A.M. TECHNOLOGY AND ENGINEERING LLP

Office Address: - SR No-135, Mohan nagar, Chinchawad, Pune -19, Maharashtra (India)

Work Address:- 15/1,Gujarwadi Road, Next to Ashvee Company, In Front Of Manish Industries, Katraj, Pune -46

Cell No. 91 7775026727, Email: amtechengg207@gmail.com

Offer Details:

| No | Particulars | Specifications | Capacity | Power Reqd per m/c | Reqd Qty in Nos | Price Per Unit in Rs. | Total Price in Rs. | GST Tax Extra |
|---|---|--|------------|--------------------|-----------------|-----------------------|--------------------|---------------|
| Processing Machines | | | | | | | | |
| Onion/Chilly Dehydration Unit 1TPH Input Processing Capacity | | | | | | | | |
| 1 | Material Loading to conveyor dryer Conveyor FBC51 | MOC : Final material Inspection Conveyor, 200 Kg/hr ,with side chutes, Food grade PP Belt , Al extrusion frame with SS 304 chutes Dimension: 5000 x 700 x5000 mm. (L X W X H) Control Panel: Dol Starter provided with conveyor 0.5 to 1 hp 415 Volts 50 Hz. Material Loading : Manual . Material Unloading: Manual. | 1000 kg/hr | 1 hp | 1 | 465000 | 465000 | GST Tax Extra |
| 2 | Raw material Inspection Conveyor FBC31 | MOC : Final material Inspection Conveyor, 200 Kg/hr ,with side chutes, Food grade PP Belt , Al extrusion frame with SS 304 chutes Dimension: 5000 x 700 x5000 mm. (L X W X H) Control Panel: Dol Starter provided with conveyor 0.5 to 1 hp 415 Volts 50 Hz. Material Loading : Manual . Material Unloading: Manual. | 1000 kg/hr | 0.5 hp | 1 | 165000 | 165000 | GST Tax Extra |
| 3 | Dehydration Machine Online Dryer-1000 kg per hr OLD 500 to 1000 | MOC: 1) Main Frame M.S. powder coated outside. 2) All contact Parts SS304, With SS 304. 3) High Temp insulation for the main Cabinet, 4) Control Panel with Automatic temperature controls. Heating load 50 KW, 230/415 Volts, 50 Hz. On Off Switch and safety switch. 5) All ISI and/ or CE marking Accessories. 6) Continuous type operations. 7) Door Locking: Simple Locking system with strong hinges. Easy to operate. 8) Dimension: L10000 x W6000 x H5500 mm. 9) Capacity: 1000 kg onion slices per hour Internal Air Circulation: With Fan - Fan will Circulate the air from heater and pushing through the material. Exhaust and Fresh Air - Vents Provided at Strategic. | 1000 kg/hr | 50 kw | 1 | 3850000 | 3850000 | GST Tax Extra |

A.M. TECHNOLOGY AND ENGINEERING LLP

Office Address: - SR No-135, Mohan nagar, Chinchawad, Pune -19, Maharashtra (India)

Work Address:- 15/1,Gujarwadi Road, Next to Ashvee Company, In Front Of Manish Industries, Katraj, Pune -46

Cell No. 91 7775026727, Email: amtechengg207@gmail.com

| | | | | | | | | | |
|---|--|---|--|------|---|---------|----------------|----------------|---------------|
| 4 | Fine Drying Dehydration Machine- Tray Dryer- (TD 24S) | MOC: 1) Main Frame M.S. powder coated outside. 2) All contact Parts SS304, With SS perforated Tray. 3) High Temp insulation for the main Cabinet, 4) Control Panel with Automatic temperature controls. Total load 6 KW 230 / 415 Volts 50 Hz. On Off Switch and safety switch. 5) All ISI and/ or CE marking Accessories. 6) Batch type operations. 7) Door Locking: Simple Locking system with strong hinges. Easy to operate. 8) Dimension: L 2100 x W1200 x H 1650 mm. 9) Capacity: 3-4 kg beans/ginger slices per tray Internal Air Circulation: With Fan - Fan will Circulate the air from heater and pushing through the material and the trey perforations. Exhaust and Fresh Air -Vents Provided at Strategic Location – manual control. | 100 kg/batch | 6 kw | 1 | 350000 | 350000 | GST Tax Extra | |
| 5 | Boiler-Oil Heating | MOC: 1) Main Frame M.S. powder coated outside 4500 kg/hr- steam with 10kg/cm, oil Heating Boiler with wooden fire system. | 10 kg/cm | | 1 | 2300000 | 2300000 | GST Tax Extra | |
| | Transportation Cost | At customer Scope | | | | 0 | 0 | | |
| | Unloading Cost | At customer Scope | | | | 0 | 0 | | |
| | Loading Cost | At customer Scope | | | | 0 | 0 | | |
| | Installation/ commissioning charges | No installations Charges but Client have pay Actual all Traveling Charges, Lodging & boarding charges to be paid by customer. | | | | 0 | 0 | | |
| | Packing cost | 5% cost will be extra on Basic Price.(customer Scope) | | | | 0 | 0 | | |
| | Warranty | Term & Conditions will be given in separate Charts. | | | | | 0 | | |
| | | | Total Project Basic Cost in Rs. | | | | 7130000 | 7130000 | GST Tax Extra |
| | | | Packing & forwarding cost | | | | 713000 | 713000 | GST Tax Extra |
| | | | | | | | 7843000 | | |
| | | | Total GST Amount in Rs. | | | | 1411740 | | |
| | | | Total Project Basic + Taxes Cost in Rs. | | | | 9254740 | | |

A] Technical Details

| No. | Particulars | Details | Remark |
|-----|--------------------------|--|--|
| 1. | Name of The Equipment | Multiproduct Dehydration 1000 kg Input per Batch / per hr. | Specially designed for mullti commodities – like Ginger, Turmeric, Coriander, Cabbage, Chilly etc. |
| 2. | Project Code | Multiproduct Dehydration 1000 kg Input per Batch/per hr. | SS Harden Blades for vegetable cutting |
| 3. | Material of Constriction | All mfg. Parts – SS 304 ,food grade Aluminum or PVC & IS Standard Brought out material | Food grade SS304 material & IS Standard brought out material |

A.M. TECHNOLOGY AND ENGINEERING LLP

Office Address: - SR No-135, Mohan nagar, Chinchawad, Pune -19, Maharashtra (India)

Work Address:- 15/1,Gujarwadi Road, Next to Ashvee Company, In Front Of Manish Industries, Katraj, Pune -46

Cell No. 91 7775026727, Email: amtechengg207@gmail.com

| | | | |
|----|------------------|---|---|
| 4. | Dimension | Mentioned in quotation sheet | L X W X H mm |
| 5. | Capacity | 1000 kg per hr OR per batch | Batch & Continuous Type. |
| 6. | Control Panel | Control panel or Dol Starter along with machine, On Off Switch and safety switch. | All ISI and/ or CE marking Accessories. |
| 7. | Blades | SS harden Blades | SS material |
| 8. | Material Loading | Manual. | NA |
| 9. | Material Removal | Manual. | NA |

B] Commercial:

| No. | Particulars | Particulars | Remark |
|-----|---|---|---|
| 1. | Total Project Basic Price | Rs. 7130000 + 713000 = 7843000 | Ex Works at Pune. |
| 2. | GST 18% | Rs. 1411740 | As Applicable at the time of Delivery |
| | Total Amount with Taxes | Rs. 9254740 | |
| 3. | Wooden Packing | Inclusive | On Basic Cost |
| 4. | Installation | Inclusive | Basic Training and operation of machines to customer staff. |
| 5. | Transport , Insurance, Material loading and unloading Charges | Inclusive | |
| 6. | Delivery Period | 14-20 weeks | From the date of receipt of P.O and advance. |
| 7. | Quotation Validity | 30 days. Upto 27.08.2022 | From the date of email. |
| 8. | Taxes | These are the current rate of taxes & duties, however those ruling at the time of dispatch will be applicable. | Tax pattern will be at the time of delivery. |
| 9. | Customer Responsibility | <ul style="list-style-type: none"> a. Basic Foundation as per our instruction. b. Electrical Supply – 230V / 415 Volts – 50 Hz. Up to the machine location. c. Material lifting equipment's. d. Two skilled helpers for each machine. e. Water connection up to the machine point. f. Material transport & insurance | Customer must inspect the machine at our end before dispatch. |
| 10. | Payment Term | <ul style="list-style-type: none"> a. 50% Advance along with Purchase Order b. 50% against proforma invoice before dispatch. | Including taxes. |
| 11. | Material to be used | Fresh leafy vegetables to be used, It is not allowed for any out dated, Frozen, blanched, cooked & harden sticked vegetable cutting. | |
| 12. | Warranty | <ul style="list-style-type: none"> 1) Blades & its Sharpness are not covered under warranty 2) All Electrical and Electronics parts warranty covered as per that part manufacturing company's term and conditions. 3) All Plastic, PVC and other standard brought out material are not covered under warranty. 4) One year warranty covered of any material, process or mechanical/technical defect. | |

A.M. TECHNOLOGY AND ENGINEERING LLP

Office Address: - SR No-135, Mohan nagar, Chinchawad, Pune -19, Maharashtra (India)

Work Address:- 15/1,Gujarwadi Road, Next to Ashvee Company, In Front Of Manish Industries, Katraj, Pune -46

Cell No. 91 7775026727, Email: amtechengg207@gmail.com

GENERAL TERMS & CONDITIONS:-

Warranty: The offered equipment's are warranted for mechanical workmanship and material for a period of 12 months from the date of commissioning. The warranty is valid subject to routine proper maintenance of plant by customer.

The standard warranty clause of original manufacturer shall be applicable for all the bought out items like blowers, motor, pumps, instruments etc., The warranty shall not be applicable for consumables, mechanical Seals / rubbers / plastics / glass /electrical / electronic items / rotary equipment etc. The warranty shall preclude any claim direct or indirect consequential or liquidated damages arising out of said contract and our liability shall be limited to repair / replace any of the defective components at our option.

Technical Clause: We reserve the right to make changes in the design of components or material which in our judgment are necessary. Such changes however shall be made only to augment the performance or life of the equipment. The information given in any of our publications, leaflets, drawings etc. is intended to present a general idea of the equipment offered.

Force Majeure: The offer is subject to the Force Majeure. The execution of resultant contract if Affected by causes beyond our control such as accidental fire, war, revolution, flood and any other act of God, change of any government policy or rules, we shall not be held responsible.

Delay in Payment: Any delay in release of payment beyond due date will entitle us to suspend Further supplies without any liability for delay of the completion period and we shall receive interest on the outstanding amounts for the period of delay. We shall also be entitled to claim storage charges.

Risk Cover: The property and the risks shall be passed onto the purchase as soon as the payment is received and the equipment is handed over to the transporter.

Delivery: If the purchaser is not able to take the delivery of the material, the interest on the balance payment will be levied as per the prevailing rate of interest. We will levy necessary charges towards warehousing of equipment in our custody. However the equipment will be stored on as-is-where basis at your risk. The customer will have to arrange necessary insurance for such storage of goods and equipment's at our end.

Consequential Losses: There shall be no liability on us for loss of production, loss of profit, loss of unused / use, loss of contracts, or for any other consequential or indirect loss whatsoever.

Order Cancellation: Customer shall not cancel or returned the order / quantity once placed on us. In the event of order being cancelled by customer with our consent, Client shall be liable to pay us the cancellation charges. The amount given to us as an advance shall be adjusted towards our charges of engineering and bought out items ordered for the said job/and any progress of manufacturing done at our works and in any case shall not be returned as it is in full advance paid to us.

Jurisdiction: Any legal dispute arising out of resultant contract shall be subject to the jurisdiction of Pune Courts in case the same is not settled mutually.

For A.M. Technology & Engineering llp

Director.

