

INDO AMERICAN EQUIPMENT	agrisep®
HO: PLOT NO. D-22, ADDL. M.I.D.C. AREA, AURANGABAD ROAD, JALNA	02482-220422
http://www.indoamericanequipment.com	agrisep@rediffmail.com
GSTN No.- 27AYHPS3777M1ZI	

REF: IAE/YK/07/22-23/143

DATE: 30/07/2022

QUOTATION

TO
Gramadhar Farmers Producer's Company Limited,
Tq. Aurangabad, Dis. Aurangabad (MS)

SUBJECT: OFFER FOR SUPPLY OF 4TPH CAPACITY (BASED ON WHEAT) ONLINE SEEDS PROCESSING PLANT.

S. N.	Particulars	Qty.	Rate (Rs.)	Amount (Rs.)
1	Vertical Bucket Elevator- MODEL: IAE / VBE/ GD6, G I, Geared Drive 1HP, Fiber buckets, attached big hopper. Capacity 6 tones/ hour on wheat basis	1	2,00,000	2,00,000=00
2	Fine Cleaner/ Grader- MODEL: IAE / FIN / J-1507 Three Screen Machine, 4500 CFM Suction Fan of 7.5 HP & Vibrator Sieve-boat on 2 HP. Vibro feeder on 80w single phase, Capacity 4 tones/ hour on wheat basis.	1	7, 60,000	7, 60,000=00
3	Dust Cyclone Fine Cleaner	1	85,000	85,000=00
4	Vertical Bucket Elevator- MODEL: IAE / VBE/ GD6- G I, Geared Drive 1HP, Fiber buckets. Capacity 8 tones/ hour on wheat basis.	1	1,90,000	1,90,000=00
5	Bins & Valves For Gravity Feeding	1	85,000	85,000=00
6	Gravity Separator- MODEL: IAE / GS / J-247 4 Fan Machine. Main Drive on 10 HP, Vibrating Deck Variable speed on 1.5 HP. Aluminium frame Deck. Capacity 3.5 to 4.0 tones/ hour on wheat basis.	1	6, 95,000	6, 95,000=00
7	Vertical Bucket Elevator- MODEL: IAE / VBE/ GD4- For Destoner- G I, Geared Drive 1HP, Fiber buckets. Capacity 4 tones/ hour on wheat basis.	1	1, 48,000	1, 48,000=00
8	De-stoner- MODEL: IAE / DS / J-6147-2 Fan Machine, Main Drive on 5 HP, Vibrating Deck variable speed on 1 HP. Capacity 3 to 4 tones/ hour on wheat basis.	1	4,00,000	4,00,000=00
9	Dual Vertical Bucket Elevator- Model: IAE / VBE- With Maintenance Service Platform, Geared drive of 2 HP, Fiber buckets, Attached hopper.	1	2, 38,000	2, 38,000=00
10	Electrical panel for controlling all machinery	1	1,50,000	1,50,000=00
11	Foundation Bolts, SS Spouting etc.	Set	---	70,000=00
12	Installation & Commissioning Charges For Complete plant	Set	---	70,000=00

	Total Cost of Machinery			30,91,000=00
	Non Negotiable Discount offered-	18%		5,56,380=00
	Final Cost after Discount			25,34,620=00
	GST@18%			4,56,231=60
	ROUND OFF +			00=40
	TOTAL AMOUNT			29,90,852=00

Part B-

1	Civil work charges	-----	1,50,000	1,50,000=00
2	Freight & Hydra Crane charges for machines shifting	-----	80,000	80,000=00
3	Electrical cables & wiring charges from panel to plant (one point earthing)	-----	80,000	80,000=00
	TOTAL AMOUNT			3,10,000=00
	GST@18%			55,800=00
	FINAL AMOUNT			3,65,800=00

TOTAL AMOUNT:- 33,56,652=00

Terms & Conditions-

- 1) Prices : Our Prices are Ex-works, Jalna.
- 2) Freight : .
- 3) Unloading : Safe Unloading of the equipment at the site shall be arranged by the buyer at his Own risk and cost.
- 4) Taxes : **INCLUDED GST @ 18% ON AGRIL. MACHINE AND 18% ON ELECTRICAL PANEL.**
- 5) Validity : Our quotation is valid for 30 days and thereafter subject to our confirmation.
- 6) Payment : 60% payment advance along with your order, 30% against Delivery and Balance 10 % Payment against installation & Commissioning.
- 7) In your scope : Safe Unloading, Civil work, Chain Block to lift the machines during Installation work or Hydra Crane for shifting the machines to their Installation position, Electrical cables & wiring to be done by you.
- 8) Delivery : 8 WEEKS AFTER ADVANCE