

INDO AMERICAN EQUIPMENT	agrisep®
HO: PLOT NO. D-22, ADDL. M.I.D.C. AREA, AURANGABAD ROAD, JALNA	02482-220422
http://www.indoamericanequipment.com	agrisep@rediffmail.com
<u>GSTN No.- 27AYHPS3777M1ZI</u>	

REF: IAE/YK/02/21-22/503

DATE: 22/02/2022

QUOTATION

To,

FARMISSION FARMER PRDUCER COMPANY LTD.

At Gewrai Bajar, Tal Badnapur Dist Jalna

**SUBJECT: OFFER FOR SUPPLY OF 8 TPH CAPACITY (BASED ON PULSES)
COMPLETE ONLINE AGRO PROCESSING PLANT.**

S. N.	Particulars	Qty.	Rate (Rs.)	Amount (Rs.)
1	Dump Hopper	1	48,000	48,000=00
2	Vibro Feeder	1	1,70,000	1,70,000=00
3	Vertical Bucket Elevator- MODEL: IAE / VBE/ AS PER YOUR REQUIREMENT , G I, Geared Drive 1HP, Fiber buckets, attached big hopper. Capacity 10 tones/ hour on wheat basis	1	2,60,000	2,60,000=00
4	Pre Cleaner- MODEL: IAE / PRE / AS PER YOUR REQUIREMENT -(With Stand)-3 Screen Machine, 4500 CFM Suction Fan of 7.5 HP & Vibrator Sieve-boat on 2 HP. Vibro feeder on 80w single phase. Capacity-8 tones/hour on wheat basis.	1	7,95,000	7,95,000=00
5	DUCTING (1 PIPE & 2 BENDS)	1	10,000	10,000=00
6	Dust Cyclone	1	85,000	85,000=00
7	Vertical Bucket Elevator- MODEL: IAE / VBE/ AS PER YOUR REQUIREMENT , G I, Geared Drive 1HP, Fiber buckets. Capacity 10 tones/ hour on wheat basis.	1	1,90,000	1,90,000=00
8	Fine Cleaner/ Grader- MODEL: IAE / FIN AS PER YOUR REQUIREMENT D- 3 & Half Screen Machine, 4500 CFM Suction Fan of 7.5 HP & Vibrator Sieve-boat on 2 HP. Vibro feeder on 80w single phase, Capacity 8 tones/ hour on wheat basis.	1	9,75,000	9,75,000=00
9	DUCTING (1 PIPE & 2 BENDS)	1	10,000	10,000=00
10	Dust Cyclone	1	85,000	85,000=00
11	Vertical Bucket Elevator- MODEL: IAE / VBE/ AS PER YOUR REQUIREMENT - G I, Geared Drive 1HP, Fiber buckets. Capacity 8 tones/ hour on wheat basis.	1	1,90,000	1,90,000=00
12	Bins & Valves For Gravity Feeding	2	85,000	1,70,000=00
13	Gravity Separator- MODEL: IAE /NEW GS /J-247 4 Fan Machine. Main Drive on 10 HP, Vibrating Deck Variable	2	6,95,000	13,90,000=00

	speed on 1.5 HP. Aluminium frame Deck. Capacity 3.5 to4.0 tones/ hour on wheat basis.			
14	Vertical Bucket Elevator- MODEL: IAE / VBE/ AS PER YOUR REQUIREMENT - For Destoner- G I, Geared Drive 1HP, Fiber buckets. Capacity 4 tones/ hour on wheat basis.	1	1,48,000	1,48,000=00
15	De-stoner- MODEL: IAE /NEW DS / AS PER YOUR REQUIREMENT -2 Fan Machine, Main Drive on 5 HP, Vibrating Deck variable speed on 1 HP. Capacity 3 to 4 tones/ hour on wheat basis.	1	4,00,000	4,00,000=00
16	Dual Vertical Bucket Elevator- Model: IAE / VBE- With Maintenance Service Platform, Geared drive of 2 HP, Fiber buckets, Attached hopper.	1	2,38,000	2,38,000=00
17	Vertical Seed Dryer AS PER YOUR REQUIREMENT (Continuous Type 3-4 TPH for superfluous Moisture) Complete with 100kg Capacity Hopper,Air Temp sensor & adjustable Temp Controller, 1500 watt heaters 9 no's(3-zone + 3-zone + 3-zone) 13.5 KW on single phase, 6 HP on three phase Heater Indicators, dynamically balanced blower With 5 HP 2880 rpm 440V AC motor, , Manual discharge Gate, Foundation frame with Blower stand and an electrical panel	2	4,00,000	8,00,000=00
18	Vertical Bucket Elevator- MODEL: IAE / VBE/ AS PER YOUR REQUIREMENT - G I, Geared Drive 1HP, Fiber buckets. Capacity 8 tones/ hour on wheat basis.	2	1,90,000	3,80,000=00
19	STORAGE BIN FOR TREATOR	1	85,000	85,000=00
20	Packing Bin with Supporting Structure-	1	1,60,000	1,60,000=00
21	PIT COVER	2	10,000	20,000=00
22	FEEDING HOPPERS	10	10,000	1,00,000=00
23	Electrical panel for controlling all machinery	1	2,42,000	2,42,000=00
24	Foundation Bolts, SS Spouting etc.	Set	-----	1,80,000=00
25	Installation & Commissioning Charges For Complete plant	Set	-----	1,80,000=00
26	Dust Bag Filter To collect dust from all dust generating points with vacuum blower, Dust Collect Bin and Air Filter with supporting structure	1	2,85,000	2,85,000=00
27	G I Round pipe Ducting for Dust Bag filter	Set	2,20,000	2,20,000=00
28	DUST HOOD (Gravity Separators & feeding point)	3	80,000	2,40,000=00
29	EXTRA ELEVATOR FOR GRAVITY SEPARATOR REMNANT TO BELT CONVEYOR	1	1,48,000	1,48,000=00
30	BELT CONVEYOR FOR REMNANT COLLECTION- Size-320 mm W x 3 mm Thick x 50 ft Length	1	3,40,000	3,40,000=00
31	Vertical Bucket Elevator to lift the Remnant-IAE/VBE	1	1,48,000	1,48,000=00
32	Remnant Collection Bin- Made in GP Sheet with GP Support Structure	1	1,60,000	1,60,000=00
33	COMPLETE PLATFORM JOB WORK WITH MATERIAL	04 MT	1,30,000	5,20,000=00

	Total Cost of Machinery			93,72,000=00
	GST@5%	91,30,000=00		4,56,500=00
	GST@18%	2,42,000=00		43,560=00
	TOTAL AMOUNT			98,72,060=00

Terms & Conditions-

1) **Prices** : Our Prices are Ex-works, Jalna.

2) **Freight** : To pay at actual.

3) **Unloading** : Safe Unloading of the equipment at the site shall be arranged by the buyer at his Own risk and cost.

4) **Taxes** : **INCLUDED GST @ 5% ON AGRIL. MACHINE AND 18% ON ELECTRICAL PANEL.**

5) **Validity** : Our quotation is valid for 30 days and thereafter subject to our confirmation.

6) **Payment** : 60% payment advance along with your order, 30% against Delivery and Balance 10 % Payment against installation & Commissioning.

7) **In your scope** : Safe Unloading, Civil work, Chain Block to lift the machines during Installation work or Hydra Crane for shifting the machines to their Installation position, Electrical cables & wiring to be done by you.

8) **Delivery** : 8 WEEKS AFTER ADVANCE

9) **Installation & Commissioning Charges-** Mentioned in Quotation.

BANK ACCOUNT DETAILS-
INDO AMERICAN EQUIPMENT,
STATE BANK OF INDIA,
SME BRANCH, JALNA.
ACCOUNT NO.- 62095047913
IFSC CODE- SBIN0061561

Please feel free to contact us in case of any query.

Thanking you and looking forward to your confirmed order.

Yours sincerely

For Indo American Equipment.

Authorized signatory.

Electrical Requirement-

- 1) Pre Cleaner – 9.5 hp
- 2) Fine Cleaenr-9.5 hp
- 3) Gravity Separator-2 nos x 11.5 hp = 23
- 4) Destoner with Elevator-7 hp
- 5) Vertical Bucket Elevator- 7 nos. x 1 hp- 7hp
- 6) Dual Bucket Elevator-2 hp
- 7) Dust Bag Filter – 7.5hp
- 8) BELT CONVEYOR - 2hp
- 9) Vertical Seed Dryer – 2 nos X 11hp =22

Total Electrical Load- 89.5 hp