

# Abstract Sheet



  
PRESIDENT / SECRETARY  
BHOOMISPARSH FARMER PRODUCE  
COMPANY LIMITED

## Abstract Sheet

Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details	QTY	UNIT	UNIT RATE	AMOUNT
<b>Excavation (BDA)</b>							
1	BDA1/21.01	718/115	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 3.00 m.) By Manual Means	155.52	CUM	243.40	37864.67
			UNDER GROUND				
2	BDA10/21.36	748/117	Filling in plinth and floors with approved excavated material in 15cm. to 20cm. layers including watering and compacting etc. complete	187.92	CUM	118.65	22296.61
			GROUND FLOOR				
3	BDA10/21.37	749/117	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer in layers of 15 cm to 20 cm including watering and compaction etc. complete.	172.37	CUM	577.50	99542.03
			GROUND FLOOR				
4	As Directed by Engineer	101/24	Providing earth work embankment with approved materials obtained from other sources upto lead of 50m including all lifts laying in layers of 20cm to 30 cm thickness breaking clods dressing to the requirement lines curves grades & sections watering and compaction with vibrator roller with v-sat attachment to achieve not less than 97% of standard proctor density etc complete	1593.00	CUM	573.30	913266.90
			GROUND FLOOR				
5	As Directed by Engineer	102/24	Supplying hard murum /kankar at the road side including conveying and stacking complete	814.20	CUM	417.90	340254.18
			GROUND FLOOR				
6	As Directed by Engineer	103/24	Supplying soft murum at the road side including conveying and stacking complete	814.20	CUM	414.75	337689.45
			GROUND FLOOR				
7	As Directed by Engineer	104/24	Picking the road surface including sectioning etc. complete (WBM surface.)	814.20	SQMT	29.40	23937.48
			GROUND FLOOR				
8	As Directed by Engineer	108/24	Providing dry rubble stone pitching 23cm (9") including all material quarry spalls, labour etc. complete	814.20	SQMT	405.30	329995.26
			GROUND FLOOR				
<b>BD-E : PLAIN CEMENT CONCRETE</b>							
9	BDE2/24.04	826/131	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for plain or molded sills, cornice, jambs, block in course, or architraves of required size and shapes including steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	183.74	CUM	6331.50	1163335.08
			GROUND FLOOR				

  
 PRESIDENT / SECRETARY  
 COMISPARSH FARMER PRODUCER  
 COMPANY LIMITED


Sr. No.	SR_NO & CODE NO	Public Work Region Nagpur	Description & Details	QTY	UNIT	UNIT RATE	AMOUNT
<b>BD - F : REINFORCED CEMENT CONCRETE</b>							
10	BDF3/ 25.11	834/133	Providing and laying In situ /Ready Mix cement concrete M-20 of trap / granite / quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. Including balling out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	27.74	CUM	6444.00	184941.50
<b>BELOW GROUND</b>				27.74	CUM	6444.00	184941.50
11	BDF5/ 25.31	839/134	Providing and laying Cast In situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	47.81	CUM	13636.35	651926.62
<b>GROUND FLOOR</b>				47.81	CUM	13636.35	651926.62
12	BDF6/ 25.50	844/135	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels, parils, copings, fins, arches etc. as per detailed designs, drawings and schedules, including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	157.94	CUM	12057.15	190491.95
<b>GROUND FLOOR</b>				157.94	CUM	12057.15	190491.95
13	BDF9/ 24.05	854/137	Providing and laying Cast In situ/Ready Mix cement concrete M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. chajja as per detailed design and drawings including steel centering, formwork, cover blocks, laying/pumping, compacting and roughening the surface if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	9.12	CUM	13744.55	125499.31
<b>GROUND FLOOR</b>				9.12	CUM	13744.55	125499.31
14	BDF12/24. 23	860/138	Providing and laying Cast In situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C.coping to plinth or parapet and sill of doors and windows moulded as per detailed drawings or chamfered as approved by the Engineer including steel centering, formwork, cover blocks, laying/pumping, compacting, curing, finishing and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)	13.37	CUM	7140.00	95438.95
<b>GROUND FLOOR</b>				13.37	CUM	7140.00	95438.95


  
**PRESIDENT / SECRETARY**  
**EHOOMI SPARSH FARMER PRODUCER**  
**COMPANY LIMITED**


Sr. No.	Sr. NO & CODE NO	Public Work Region Nagpur	Description & Details	QTY	UNIT	UNIT RATE	AMOUNT
15	BDF17/26.33	849/139	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels parils, copings, Bns, arches etc. as per detailed designs, drawings and schedules. Including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete. GROUND FLOOR	42.43	MT	75344.90	4705484.32

  
  
 PRESIDENT / SECRETARY  
 CHOOMISPARSH FARMER PRODUCER  
 COMPANY LIMITED

Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details	QTY	UNIT	UNIT RATE	AMOUNT
<b>BD -G : BRICK WORK</b>							
16	BDG 1/27.01	887/144	Providing second class burnt brick masonry with conventional/LS. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually, striking joints on one exposed faces, raking out joints on exposed faces and watering etc. Complete.				
			GROUND FLOOR	51.24	CUM	7710.15	395043.44
17	BDG 5/27.05	890/144	Providing second class burnt brick masonry with conventional/LS. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete				
			GROUND FLOOR	222.04	CUM	7948.50	1764864.27
<b>BD -L : PLASTERING &amp; POINTING</b>							
18	BDL2/ 32.03	955/153	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:5 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc.				
			GROUND FLOOR	965.38	SQ.MT	249.85	240507.79
19	BDL7/ 32.11	961/153	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound of 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.				
			GROUND FLOOR	965.38	SQ.MT	733.95	708540.65
<b>BD -P: COLOUR/WHITE WASHING, DESTEMPERING</b>							
20	BDP6A/34 .14	1107/147	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.				
			GROUND FLOOR	1930.76	SQ.MT	105.00	202729.80
<b>BD -U: IRON WORK</b>							
21	BDU 1/ 40.1	1289/192	Providing and fixing mild steel grill work for windows, ventilators etc. 20 Kilogram/Square Metre as per drawing including fixtures, necessary welding and painting with one coats of anticorrosive paint and two coats of oil painting complete.				
			GROUND FLOOR	70.20	SQ.MT	1937.25	135994.95
<b>BD -C : STRUCTURAL STEEL WORK</b>							
22	BDC/23.0 7	820/129	Providing, fabricating and erecting at site of work the tubular steel structure (shed) as per standard design and specifications having various spans in between trusses and in multiples of standard length of bays as specified as per standard specifications, inclusive of cost of steel tubular trusses, tubular columns purlins, tie runners, foundation bolts, base plates, nuts and bolts, welding wherever required etc. as per detailed drawing inclusive of one coat of anticorrosive paint and two coats of oil painting of approved quality and shade etc. complete. Spec. Number : As directed by Engineer-in-charge.				
			GROUND FLOOR	12.60	MT	105402.70	1330171.41
<b>BD -R: ROOFING AND CEILING</b>							
23	BDR5/38.0 4	1142/171	Providing and fixing plain zinc sheeting of 0.80 mm thick (22 B.W.G.) over the ridge hip or valley to galvanized iron sheet roofing including all fastening and bolt galvanized iron screws and bolts, lead and bitumen washers etc. complete. (Weight of 6.8 Kilogram/sq.m.).				
			GROUND FLOOR	1709.67	SQMT	1094.10	1870552.14
<b>BD -W: MISCELLANEOUS</b>							

  
 PRESIDENT / SECRETARY  
 BHOOMISPARSH FARMER PRODUCEP  
 COMPANY LIMITED

Sr. No.	Sr. NO & CODE NO	Public Work Region Nappur	Description & Details	QTY	UNIT	UNIT RATE	AMOUNT
24	BDT55/39. 24	1215/181	Providing and fixing rolling shutter fabricated from steel laths of minimum thickness 0.9 mm with lock plate of 3.15 mm thickness reinforced with 35 x 35 x 5 mm angle section fitted with sliding bolts and handles for both sides, deep M.S. channel section of depth and thickness not less than 65 mm and 3.15 mm respectively with hold fast arrangements, M.S. bracket plate 300 x 300 x 3.15 mm minimum size and shape with square bar, suspension shaft of minimum 32 mm diameter, hood cover of M.S. sheet not less than 0.9 mm thickness and of any size at top and safety devices including mechanical gear operation consisting of worm gear wheels and worms of high grade cast iron or mild steel and one coat of red lead primer etc. complete. (LS. 42481979) (With mechanical gear)				
			GROUND FLOOR	43.20	SQMT	4525.50	195501.40
25	IRC 47 2015	307/89	Providing And fixing Informatory sign boards in rectangular shape of size 1.20x0.90 made out of 16 guage aluminium panel bonded with irc specified colour background including M.S angle iron frame of size 35mmx35mmx3mm & 2 m.s angle iron post size 45mmx45m				
			GROUND FLOOR	2.00	NO	11891.25	23782.50
26	As directed by Engineer in charge	1543/399	RWH shallow percolating pit providing constructing 2.0m deep shallow depth percolation pit comprising of 1.0m dia pre cast rcc rings 300mm thk side filling around outside of rcc rings (annular space) with 40mm size boulders including filling of percolatio				
			GROUND FLOOR	1.00	NO	51187.50	51187.50
TOTAL AMOUNT FOR ARCHITECTURAL WORK							277716.5

  
 PRESIDENT / SECRETARY  
 CHOOMISPARSH FARMER PRODUCER  
 COMPANY LIMITED

**ARCHITECTURAL MEASUREMENT SHEET**

  
**PRESIDENT / SECRETARY**  
**PHOOMISPARSH FARMER PRODUCE**  
**COMPANY LIMITED**

**MEASUREMENT SHEET FOR INDIVIDUAL ITEM**

Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details							
1	Excavation (BDA) BDA1/21.01	718/ 115	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 3.00 m.) By Manual Means							
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT	
			1	BUILDING WORK	32.00	1.80	1.80	1.50	155.52	CUM
2	BDA10/ 21.34	748/ 117	Filling in plinth and floors with approved excavated material in 15cm. to 20cm. layers including watering and compacting etc. complete							
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT	
			1	BUILDING WORK	32.00	1.80	1.80	0.15	15.55	CUM
			3	Below Floor	1.00	48.48	21.98	0.15	160.50	CUM
					1.00	3.40	21.98	0.15	11.87	CUM
			<b>TOTAL QTY FOR MURUM FILLING</b>						187.92	CUM
3	BDA10/ 21.37	749/ 117	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer Incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.							
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT	
			1	Below Floor	1.00	48.48	21.98	0.15	160.50	CUM
					1.00	3.40	21.98	0.15	11.87	CUM
			<b>TOTAL QTY FOR MURUM FILLING</b>						178.63	CUM
4	As Directed by Engineer	101/24	Providing earth work embankment with approved materials obtained from other sources upto lead of 50m including all lifts laying in layers of 20cm to 30 cm thickness breaking clods, dressing to the requirement lines curves grades & sections watering and compaction with vibrator roller with v-sat attachment to achieve not less than 97% of standard proctor density etc complete							
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT	
			1	Land Leveling	1.00	40.00	50.00	0.45	1350.00	CUM
			2	Road Leveling	1.00	90.00	6.00	0.45	243.00	CUM
			<b>TOTAL QTY FOR MURUM FILLING</b>						1593.00	CUM
5	As Directed by Engineer	102/24	Supplying hard murum /kankar at the road side including conveying and stacking complete							
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT	
			1	Land Leveling	1.00	40.00	50.00	0.23	690.00	CUM
			2	Road Leveling	1.00	90.00	6.00	0.23	124.20	CUM
			<b>TOTAL QTY FOR MURUM FILLING</b>						814.20	CUM
7	As Directed	103/24	Supplying soft murum at the road side including conveying and stacking complete							
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT	
			1	Land Leveling	1.00	40.00	50.00	0.23	690.00	CUM
			2	Road Leveling	1.00	90.00	6.00	0.23	124.20	CUM

  
**PRESIDENT / SECRETARY**  
**BHOOMISPARSH FARMER PRODUCER**  
**COMPANY LIMITED**


Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details						
			<b>TOTAL OF BOX MURUM FILLING</b>						
7	As Directed	104/24	Pitching the road surface including sectioning etc. complete (WBM surface.)						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			1	1.00	40.00	50.00	0.23	690.00	CUM
			2	1.00	90.00	6.00	0.23	124.20	CUM
			<b>TOTAL OF BOX MURUM FILLING</b>						
8	As Directed	108/24	Providing dry rubble stone pitching 23cm (9") including all material quarry spoils, labour etc. complete						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			1	1.00	60.00	50.00	0.23	690.00	SQMT
			2	1.00	90.00	6.00	0.23	124.20	CUM
			<b>TOTAL OF BOX MURUM FILLING</b>						
<b>BD-E : PLAIN CEMENT CONCRETE</b>									
9	BDE2/ 24.04	826/ 131	Providing and laying Cast In situ/Ready Mix cement concrete in M15 of trap / granite / quartzite / gneiss metal for plain or molded sills, cornice, jambs, block in course, or architraves of required size and shapes including steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			1	32.00	1.50	1.50	0.15	10.80	CUM
			Below Floor	1.00	48.68	21.98	0.15	140.50	CUM
				1.00	3.60	21.98	0.16	12.44	CUM
			<b>TOTAL OF BDECC</b>						
<b>BD -F : REINFORCED CEMENT CONCRETE</b>									
10	BDF3/ 25.11	834/133	Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite / quartzite / gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. Including balling out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			1	32.00	1.70	1.70	0.30	27.74	CUM
			<b>TOTAL</b>						
11	BDF5/ 25.31	839/134	Providing and laying Cast In situ/Ready Mix cement concrete M-20 of trap / granite / quartzite / gneiss metal for R.C.C. columns as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			1	32.00	0.30	0.60	1.80	10.37	CUM
			2	32.00	0.30	0.60	6.50	37.44	CUM

  
**PRESIDENT / SECRETARY**  
**PHOOMISPARSH FARMER PRODUCEP**


Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details						
<b>TOTAL QUANTITY OF PLINTH</b>									
12	BDF4/ 25.50	844/135	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite / quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)						
<b>Building Work</b>									
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			Plinth P81	6.00	48.68	0.30	0.45	39.43	CUM
				13.00	21.98	0.30	0.45	38.57	CUM
				2.00	3.60	0.30	0.45	0.97	CUM
			Lintel Beam	6.00	48.68	0.30	0.45	39.43	CUM
				13.00	21.98	0.30	0.45	38.57	CUM
				2.00	3.60	0.30	0.45	0.97	CUM
<b>Total Qty For Ground Floor</b>									
<b>TOTAL QUANTITY OF PLINTH BEAM AND COPING</b>									
13	BDF9/ 26.05	854/137	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. chajja as per detailed design and drawings including steel centering, formwork, cover blocks, laying/pumping, compacting and roughening the surface if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			Window/Door	26.00	2.75	0.75	0.17	9.12	CUM
<b>Total Qty For Ground Floor</b>									
<b>TOTAL QUANTITY OF CHAJJA</b>									
14	BDF12/26.23	860/138	Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C. coping to plinth or parapet and sill of doors and windows moulded as per detailed drawings or chamfered as approved by the Engineer including steel centering, formwork, cover blocks, laying/pumping, compacting, curing, finishing and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			Long Wall	2.00	48.68	0.30	0.30	8.76	CUM
			short Wall	2.00	21.98	0.30	0.30	3.96	CUM
				2.00	3.60	0.30	0.30	0.65	CUM
<b>Total Qty For Ground Floor</b>									
<b>TOTAL QUANTITY OF COPING</b>									
15	BDF17/ 26.33	869/139	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels, pordis, copings, fins, arches etc. as per detailed designs, drawings and schedules, including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.						
<b>STEEL</b>									
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT

  
**PRESIDENT / SECRETARY**  
**PHOOMISPARSH FARMER PRODUCT**  
**COMPANY LIMITED**


Sr. No.	SLNO & CODE NO	Public Work Region Nagpur	Description & Details				12343.24	62434.34	
			1.00	1149.00	10.74				
<b>BD -G : BRICK WORK</b>									
16	BDG 1/27.01	887/144	Providing second class Burnt brick masonry with conventional/ L.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including balling out water manually, striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			Long Wall	2.00	48.68	0.23	1.50	33.59	CUM
			short Wall	2.00	21.98	0.23	1.50	15.17	CUM
				2.00	3.60	0.23	1.50	2.48	CUM
<b>BD -I: PLASTERING AND POINTING</b>									
17	BDG 5/27.05	890/144	Providing second class Burnt brick masonry with conventional/ L.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			Long Wall	2.00	48.68	0.23	6.50	145.55	CUM
			short Wall	2.00	21.98	0.23	6.50	65.72	CUM
				2.00	3.60	0.23	6.50	10.76	CUM
18	BDL2/ 32.03	955/153	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:5 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc.						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			Internal Plaster	2.00	48.68		6.50	632.84	SQ.MT
				2.00	21.98		6.50	285.74	SQ.MT
				2.00	3.60		6.50	46.80	SQ.MT
19	BDL 7/ 32.11	961/153	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kg/gramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment & to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
			Building Work	2.00	48.68		6.50	632.84	SQ.MT
				2.00	21.98		6.50	285.74	SQ.MT
				2.00	3.60		6.50	46.80	SQ.MT

  
 PRESIDENT / SECRETARY  
 PHOONISPARSH FARMER PRODUCER  
 COMPANY LIMITED


Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details						
<b>BD -P: COLOUR/WHITE WASHING, DESTEMPERING</b>									
20	BDP4A/34.14	1107/147	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT
			TOTAL QUANTITY OF INTERNAL PLASTER					965.38	SQ.MT
			TOTAL QUANTITY OF EXTERNAL PLASTER					965.38	SQ.MT
<b>BD -U: IRON WORK</b>									
21	BDU 1/ 40.1	1289/192	Providing and fixing mild steel grill work for windows, ventilators etc. 20 Kilogram/Square Metre as per drawing including fixtures, necessary welding and painting with one coats of anticorrosive paint and two coats of oil painting complete.						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT
			M.S Grill WT	26.00	1.80		1.50	70.20	SQ.MT
			TOTAL QUANTITY OF M.S GRILL						
<b>BD -C : STRUCTURAL STEEL WORK</b>									
22	BDC/23.07	820/129	Providing, fabricating and erecting at site of work the tubular steel structure (shed) as per standard design and specifications having various spans in between trusses and in multiples of standard length of bays as specified as per standard specifications, inclusive of cost of steel tubular trusses, tubular columns, purlins, tie runners, foundation bolts, base plates, nuts and bolts, welding wherever required etc. as per detailed drawing inclusive of one coat of anticorrosive paint and two coats of oil painting of approved quality and shade etc. complete. Spec. Number : As directed by Engineer-in-charge.						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT
			Building Work	1.00	53.40	23.50	1259.40	12596.00	SQMT
			TOTAL QUANTITY OF STEEL					12.40	MT
<b>BD -R: ROOFING AND CEILING</b>									
23	BDR5/38.04	1142/171	Providing and fixing plain zinc sheeting of 0.80 mm thick (22 B.W.G.) over the ridge hip or valley to galvanized iron sheet roofing including all fastening and bolt galvanized iron screws and bolts, lead and bitumen washers etc. complete. (Weight of 6.8 Kilogram/sq.m.)						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT
			Building Work	1.00	50.00	23.50		1175.00	SQMT
				2.00	48.48	3.60		350.50	SQMT
				2.00	21.98	3.60		158.26	SQMT
				2.00	3.40	3.60		25.92	SQMT
			TOTAL QUANTITY OF SHEET					1709.67	SQMT
<b>BD -W: MISCELLANEOUS</b>									
24	BDT55/39.24	1215/181	Providing and fixing rolling shutter fabricated from steel laths of minimum thickness 0.9 mm with lock plate of 3.15 mm thickness reinforced with 35 x 35 x 5 mm angle section fitted with sliding bolts and handles for both sides, deep M.S. channel section of depth and thickness not less than 45 mm and 3.15 mm respectively with hold fast arrangements, M.S. Bracket plate 300 x 300 x 3.15 mm minimum size and shape with square bar, suspension shaft of minimum 32 mm diameter, hood cover of M.S. sheet not less than 0.9 mm thickness and of any size top and safety devices including mechanical gear operation arrangement consisting of worm gear wheels and worms of high grade cast iron or mild steel and one coat of red lead primer etc. complete. (I.S. 42481977) (With mechanical gear)						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/HT	QUANTITY	UNIT
			Building Work	6.00	2.40	3.00		43.20	SQMT

  
**PRESIDENT / SECRETARY**  
**SHOONISPASH FARMER PRODUCER**  
**COMPANY LIMITED**

Sr. No.	SR NO & CODE NO	Public Work Region Nagpur	Description & Details						
							43.20	SQMT	
25	IRC 67 2015	307/B9	Providing And fixing Informatory sign boards in rectangular shape of size 1.20x0.90 made out of 16 gauge aluminium panel bonded with kc specified colour background including M.S angle iron frame of size 35mmx35mmx3mm & 2 m.s angle iron post size 45mmx45mmx4mm 3.65 long duty pointed with flat oil point fixing the board in m20 concrete block of size 40mmx40mmx75mm including transportation etc						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
		1	Sign Board	2.00				2.00	NO
								2.00	NO
26	As directed by Engineer in charge	1543/377	RWH shallow percolating pit providing constructing 2.0m deep shallow depth percolation pit comprising of 1.0m dia pre cast rcc rings 300mm thick side filling around outside of rcc rings (annular space) with 40mm size boulders including filling of percolation pit upto 0.5m depth (from bottom) with 25-75mm clean washed gravels followed by 0.5m depth of 10-25mm of clean washed stone followed by 0.5m washed of river fine aggregate (natural sand crushed sand VSI grade finely washed etc) media layer including covering with rcc slab manhole frame & cover pvc rungsetc. including arrangement on inlet & outlet pipe excavation & backfilling as shown in the drawing. the rate shall be inclusive of all labour material wastage scaffolding transportation taxes, including all leads, lifts at all levels. All material should be of approved make. All works complete as per the drawing technical specification and direction of the engineer in charge						
			DESCRIPTION	NO.	LENGTH	BREADTH	DPT/MT	QUANTITY	UNIT
		1	Rain Water	1.00				1.00	NO
								1.00	NO

  
 PRESIDENT / SECRETARY  
 PHOONISPARSH FARMER PRODUCT  
 COMPANY LIMITED

# Rate Analysis

  
**PRESIDENT / SECRETARY**  
**CHOOMISPARSII FARMER PRODUCER**  
**COMMISSION**

## Rate Analysis


Sr. No.	SR.NO. & CODE NO	Public Work Region Nagpur	Description & Details																									
Excavation (BDA)																												
1	BDA1/21.0	718/ 115	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 3.00 m.) By Manual Means																									
			<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;">Details</th> <th style="width: 5%;">%</th> <th style="width: 15%;">Amount</th> <th style="width: 10%;">Total</th> <th style="width: 10%;">Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>232.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>11.60</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>243.60</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>243.60</td> <td>Rs./ CUM</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		232.00			Corporation area	5.0%	11.60			Ground Floor		243.60						243.60	Rs./ CUM
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		232.00																										
Corporation area	5.0%	11.60																										
Ground Floor		243.60																										
			243.60	Rs./ CUM																								
2	BDA10/ 21.36	748/ 117	Filling in plinth and floors with approved excavated material in 15cm. to 20cm. layers including watering and compacting etc. complete																									
			<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;">Details</th> <th style="width: 5%;">%</th> <th style="width: 15%;">Amount</th> <th style="width: 10%;">Total</th> <th style="width: 10%;">Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>113.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>5.65</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>118.65</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>118.65</td> <td>Rs./ CUM</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		113.00			Corporation area	5.0%	5.65			Ground Floor		118.65						118.65	Rs./ CUM
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		113.00																										
Corporation area	5.0%	5.65																										
Ground Floor		118.65																										
			118.65	Rs./ CUM																								
3	BDA10/ 21.37	749/ 117	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer																									
			<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;">Details</th> <th style="width: 5%;">%</th> <th style="width: 15%;">Amount</th> <th style="width: 10%;">Total</th> <th style="width: 10%;">Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>550.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>27.50</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>577.50</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>577.50</td> <td>Rs./ CUM</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		550.00			Corporation area	5.0%	27.50			Ground Floor		577.50						577.50	Rs./ CUM
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		550.00																										
Corporation area	5.0%	27.50																										
Ground Floor		577.50																										
			577.50	Rs./ CUM																								
4	As Directed by Engineer	101/24	Providing earth work embankment with approved materials obtained from other sources upto lead of 50m including all lifts laying in layers of 20cm to 30 cm thickness breaking clods, dressing to the requirement lines curves grades A & sections watering and compaction with vibrator roller with v. sat attachment to achieve not less than 97% of standard pactor density etc complete																									
			<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;">Details</th> <th style="width: 5%;">%</th> <th style="width: 15%;">Amount</th> <th style="width: 10%;">Total</th> <th style="width: 10%;">Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>546.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>27.30</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>573.30</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>573.30</td> <td>Rs./ CUM</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		546.00			Corporation area	5.0%	27.30			Ground Floor		573.30						573.30	Rs./ CUM
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		546.00																										
Corporation area	5.0%	27.30																										
Ground Floor		573.30																										
			573.30	Rs./ CUM																								
5	As Directed	102/24	Supplying hard murum /kankar at the road side including conveying and stacking complete																									
			<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;">Details</th> <th style="width: 5%;">%</th> <th style="width: 15%;">Amount</th> <th style="width: 10%;">Total</th> <th style="width: 10%;">Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>398.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>19.90</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>417.90</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>417.90</td> <td>Rs./ CUM</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		398.00			Corporation area	5.0%	19.90			Ground Floor		417.90						417.90	Rs./ CUM
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		398.00																										
Corporation area	5.0%	19.90																										
Ground Floor		417.90																										
			417.90	Rs./ CUM																								
6	As	103/24	Supplying soft murum at the road side including conveying and stacking complete																									
			<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;">Details</th> <th style="width: 5%;">%</th> <th style="width: 15%;">Amount</th> <th style="width: 10%;">Total</th> <th style="width: 10%;">Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>395.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>19.75</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>414.75</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>414.75</td> <td>Rs./ CUM</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		395.00			Corporation area	5.0%	19.75			Ground Floor		414.75						414.75	Rs./ CUM
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		395.00																										
Corporation area	5.0%	19.75																										
Ground Floor		414.75																										
			414.75	Rs./ CUM																								
7	As Directed	104/24	Picking the road surface including sectioning etc. complete (WBM surface.)																									
			<table style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th style="width: 60%;">Details</th> <th style="width: 5%;">%</th> <th style="width: 15%;">Amount</th> <th style="width: 10%;">Total</th> <th style="width: 10%;">Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>28.00</td> <td></td> <td></td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		28.00																	
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		28.00																										

  
**PRESIDENT / SECRETARY**  
**BHOOMISPARSH FARMER PRODUCERS**  
**COMPANY LIMITED**

Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details			
			Corporation area	5.0%	1.40	
					29.40	
						29.40 Rs./ CUM
8	As Directed	108/24	Providing dry rubble stone pitching 23cm (9") including all material quarry spalls, labour etc. complete			
			Details	%	Amount	Total Unit
			Basic Rates for 2021-2022		386.00	
			Corporation area	5.0%	19.30	
			Ground Floor		405.30	
						405.30 Rs./ CUM
<b>BD-E : PLAIN CEMENT CONCRETE</b>						
9	BDE2/ 24.04	826/ 131	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap / granite/quartzite/gneiss metal for plain or molded sills, cornice, jambs, block in course, or architraves of required size and shapes including steel centering, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.) with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)			
			Details	%	Amount	Total Unit
			Basic Rates for 2021-2022		6030.00	
			Corporation area	5.0%	301.50	
			Ground Floor		6331.50	
						6331.50 Rs./ CUM
<b>BD -F : REINFORCED CEMENT CONCRETE</b>						
10	BDF3/ 25.11	834/133	Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including balling out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)			
			Details	%	Amount	Total Unit
			Basic Rates for 2021-2022		6666.00	
			Corporation area	5.0%	333.30	
			Ground Floor		6999.30	
						6999.30 Rs./ CUM
11	BDF5/ 25.31	839/134	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)			
			Details	%	Amount	Total Unit
			Basic Rates for 2021-2022		12987.00	
			Corporation area	5.0%	649.35	
			Ground Floor		13636.35	
						13636.35 Rs./ CUM

  
**PRESIDENT / SECRETARY**  
**BHOOMISPARSH FARMER PRODUCTS**  
**COMPANY LIMITED**


Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details																									
12	BDF6/ 25.50	844/135	<p>Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite / quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)</p> <p>Details</p> <table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>11483.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>574.15</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>12057.15</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>12057.15</td> <td>Rs./ CUM</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		11483.00			Corporation area	5.0%	574.15			Ground Floor		12057.15						12057.15	Rs./ CUM
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		11483.00																										
Corporation area	5.0%	574.15																										
Ground Floor		12057.15																										
			12057.15	Rs./ CUM																								
13	BDF9/ 26.05	854/137	<p>Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite / quartzite/ gneiss metal for R.C.C. chajja as per detailed design and drawings including steel centering, formwork, cover blocks, laying/pumping, compacting and roughening the surface if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)</p> <p>Details</p> <table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>13111.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>655.55</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>13766.55</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>13766.55</td> <td>Rs./ CUM</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		13111.00			Corporation area	5.0%	655.55			Ground Floor		13766.55						13766.55	Rs./ CUM
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		13111.00																										
Corporation area	5.0%	655.55																										
Ground Floor		13766.55																										
			13766.55	Rs./ CUM																								
14	BDF12/26.2 3	860/138	<p>Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap / granite / quartzite/ gneiss metal for R.C.C. coping to plinth or parapet and sill of doors and windows moulded as per detailed drawings or chamfered as approved by the Engineer including steel centering, formwork, cover blocks, laying/pumping, compacting, curing, finishing and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)</p> <p>Details</p> <table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>6800.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>340.00</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>7140.00</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>7140.00</td> <td>Rs./ CUM</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		6800.00			Corporation area	5.0%	340.00			Ground Floor		7140.00						7140.00	Rs./ CUM
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		6800.00																										
Corporation area	5.0%	340.00																										
Ground Floor		7140.00																										
			7140.00	Rs./ CUM																								
15	BDF17/ 26.33	869/139	<p>Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels, purlins, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.</p> <p>Details</p> <table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>71778.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>3588.90</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>75366.90</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>75366.90</td> <td>Rs./M.T.</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		71778.00			Corporation area	5.0%	3588.90			Ground Floor		75366.90						75366.90	Rs./M.T.
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		71778.00																										
Corporation area	5.0%	3588.90																										
Ground Floor		75366.90																										
			75366.90	Rs./M.T.																								
BD - G : BRICK WORK																												
16	BDG 1/27.01	887/144	<p>Providing second class Burnt Brick masonry with conventional/ LS. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually, striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.</p> <p>Details</p> <table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>7343.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>367.15</td> <td></td> <td></td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		7343.00			Corporation area	5.0%	367.15												
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		7343.00																										
Corporation area	5.0%	367.15																										

  
**PRESIDENT / SECRETARY**  
**SHOONISPARSH FARMER PRODUCER**  
**COMPANY LIMITED**


Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details			
					7710.15	7710.15 Rs./ CUM
17	BDG 5/27.05	890/144	Providing second class Burnt Brick masonry with conventional/ L.S. type bricks in cement mortar 1:4 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete			
			Details	%	Amount	Total Unit
			Basic Rates for 2021-2022		7570.00	
			Corporation area	5.0%	378.50	
			Ground Floor		7948.50	7948.50 Rs./ CUM
<b>BD -L: PLASTERING AND POINTING</b>						
18	BDL2/ 32.03	955/153	Providing Internal cement plaster 12mm thick in single coat in cement mortar 1:5 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc.			
			Details	%	Amount	Total Unit
			Basic Rates for 2021-2022		257.00	
			Corporation area	5.0%	12.85	
			Ground Floor		269.85	269.85 Rs./ SQMT
19	BDL 7/ 32.11	961/153	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete.			
			Details	%	Amount	Total Unit
			Basic Rates for 2021-2022		699.00	
			Corporation area	5.0%	34.95	
			Ground Floor		733.95	733.95 Rs./ SQMT
<b>BD -P: COLOUR/WHITE WASHING, DESTEMPERING</b>						
20	BDP&A/36. 14	1107/167	Providing and applying plastic emulsion paint of approved quality, colour and shade to new surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.			
			Details	%	Amount	Total Unit
			Basic Rates for 2021-2022		100.00	
			Corporation area	5.0%	5.00	
			Ground Floor		105.00	105.00 Rs./ SQMT
<b>BD -U: IRON WORK</b>						
21	BDU 1/ 40.1	1289/192	Providing and fixing mild steel grill work for windows, ventilators etc. 20 Kilogram/Square Metre as per drawing including fixtures, necessary welding and painting with one coats of anticorrosive paint and two coats of oil painting complete.			
			Details	%	Amount	Total Unit
			Basic Rates for 2021-2022		1845.00	
			Corporation area	5.0%	92.25	
			Ground Floor		1937.25	1937.25 Rs./ SQMT
<b>BD -C : STRUCTURAL STEEL WORK</b>						

  
 PRESIDENT / SECRETARY  
 SHOOMISPARSH FARMER PRODUCER  
 COMPANY LIMITED

Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details																									
22	BDC/23.07	820/129	<p>Providing, fabricating and erecting at site of work the tubular steel structure (shed) as per standard design and specifications having various spans in between trusses and in multiples of standard length of bays as specified as per standard specifications, inclusive of cost of steel tubular trusses, tubular columns purlins, tie runners, foundation bolts, base plates, nuts and bolts, welding wherever required etc. as per detailed drawing inclusive of one coat of anticorrosive paint and two coats of oil painting of approved quality and shade etc. complete. Spec. Number : As directed by Engineer-in-charge.</p> <table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>100574.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>5028.70</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>105602.70</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>105602.70</td> <td>Rs./M.T.</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		100574.00			Corporation area	5.0%	5028.70			Ground Floor		105602.70						105602.70	Rs./M.T.
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		100574.00																										
Corporation area	5.0%	5028.70																										
Ground Floor		105602.70																										
			105602.70	Rs./M.T.																								
BD -R: ROOFING AND CEILING																												
23	BDR5/38.04	1142/171	<p>Providing and fixing plain zinc sheeting of 0.80 mm thick (22 B.W.G.) over the ridge hip or valley to galvanized iron sheet roofing including all fastening and bolt galvanised iron screws and bolts, lead and bitumen washers etc. complete. (Weight of 6.8 Kilogram/sq.m.).</p> <table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>1042.00</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>52.10</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>1094.10</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>1094.10</td> <td>Rs./SQ.FT</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		1042.00			Corporation area	5.0%	52.10			Ground Floor		1094.10						1094.10	Rs./SQ.FT
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		1042.00																										
Corporation area	5.0%	52.10																										
Ground Floor		1094.10																										
			1094.10	Rs./SQ.FT																								
BD -W: MISCELLANEOUS																												
24	BDT55/39.2 4	1215/181	<p>Providing and fixing rolling shutter fabricated from steel laths of minimum thickness 0.9 mm with lock plate of 3.15 mm thickness reinforced with 35 x 35 x 5 mm angle section fitted with sliding bolts and handles for both sides, deep M.S. channel section of depth and thickness not less than 65 mm and 3.15 mm respectively with hold fast arrangements, M.S. Bracket plate 300 x 300 x 3.15 mm minimum size and shape with square bar, suspension shaft of minimum 32 mm diameter, hood cover of M.S. sheet not less than 0.9 mm thickness and of any size at top and safety devices including mechanical gear operation arrangement consisting of worm gear wheels and worms of high grade cast iron or mild steel and one coat of red lead primer etc. complete. (I.S. 62481979) (With mechanical gear)</p> <table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>4310</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>215.50</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>4525.50</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>4525.50</td> <td>Rs./SQ.FT</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		4310			Corporation area	5.0%	215.50			Ground Floor		4525.50						4525.50	Rs./SQ.FT
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		4310																										
Corporation area	5.0%	215.50																										
Ground Floor		4525.50																										
			4525.50	Rs./SQ.FT																								
25	IRC 67 2015	307/89	<p>Providing And fixing Informatory sign boards in rectangular shape of size 1.20x0.90 made out of 16 guage aluminium panel bonded with lrc specified colour background including M.S angle iron frame of size 35mmx35mmx3mm &amp; 2 m.s angle iron post size 65mmx65mmx6mm 3.65 long duty painted with flat all paint fixing the board in m20 concrete block of size 60mmx60mmx75mm including transportation etc</p> <table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>11325</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>566.25</td> <td></td> <td></td> </tr> <tr> <td>Ground Floor</td> <td></td> <td>11891.25</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>11891.25</td> <td>Rs./SQ.FT</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		11325			Corporation area	5.0%	566.25			Ground Floor		11891.25						11891.25	Rs./SQ.FT
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		11325																										
Corporation area	5.0%	566.25																										
Ground Floor		11891.25																										
			11891.25	Rs./SQ.FT																								

  
 PRESIDENT / SECRETARY  
 PHOOMISPARSH FARMER PRODUCTS  
 COMPANY LIMITED

Sr. No.	SR.NO & CODE NO	Public Work Region Nagpur	Description & Details																									
26	As directed by Engineer in charge	1563/399	RWH shallow percolating pit providing constructing 2.0m deep shallow depth percolation pit comprising of 1.0m dia pre cast rcc rings 300mm thk side filling around outside of rcc rings (annular space) with 40mm size boulders including filling of percolation pit upto 0.5m depth (from bottom) with 25-75mm clean washed gravels followed by 0.5m depth of 10-25mm of clean washed stone followed by 0.5m washed of river fine aggregate (natural sand crushed sand VSI grade finaly washed etc including netlon mesh between each gravel/fine aggregate (natural sand crushed sand VSI grade finaly washed etc) media layer including covering with rcc slab manhole frame & cover pvc rungsetc. Including arrangement on inlet & outlet pipe excavation & backfilling as shown in the drawing . the rate shall be inclusive of all labour material wastage scaffolding transportation taxes , including all leads,lifts at all levels.All material should be of approved make .All works complete as per the drawing technical specification and direction of the engineer in charge																									
			<table border="1"> <thead> <tr> <th>Details</th> <th>%</th> <th>Amount</th> <th>Total</th> <th>Unit</th> </tr> </thead> <tbody> <tr> <td>Basic Rates for 2021-2022</td> <td></td> <td>487.50</td> <td></td> <td></td> </tr> <tr> <td>Corporation area</td> <td>5.0%</td> <td>2437.50</td> <td></td> <td></td> </tr> <tr> <td>Ground Fabr</td> <td></td> <td>51187.50</td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td>51187.50</td> <td>Rs./SQ.FT</td> </tr> </tbody> </table>	Details	%	Amount	Total	Unit	Basic Rates for 2021-2022		487.50			Corporation area	5.0%	2437.50			Ground Fabr		51187.50						51187.50	Rs./SQ.FT
Details	%	Amount	Total	Unit																								
Basic Rates for 2021-2022		487.50																										
Corporation area	5.0%	2437.50																										
Ground Fabr		51187.50																										
			51187.50	Rs./SQ.FT																								

  
 PRESIDENT / SECRETARY  
 MOOMISPARSH FARMER PRODUCE  
 COMPANY LIMITED



130



भारतीय स्टेट बैंक  
State Bank of India

To,  
Bhoomisparsh Farmers Producer Company Limited  
Jamb

Date: 31/01/2022

Dear Sir,

With refer to captioned project which your esteemed company, we are pleased to express our interest in considering providing you an Credit Facility to assist the commercial to Project Sustainable Pad̄dy Farming with Technology.

Please be kindly advised that above terms are our preliminary proposal. They are not legally binding upon us, and are still subject to the internal approval of our bank. State Bank of India is solely responsible for explaining the meaning of this intent and reserves the right to any changes to it whenever we think necessary.

Yours Faithfully

Branch Manager

PRESIDENT / SECRETARY  
BHOOMISPARSH FARMER PRODUCER  
COMPANY LIMITED

# Bhoomisprash Farmer Producer Company Limited

131

REG.OFF :- Near Atkari Petrolium Jamb, Ta-Mohadi, Dist-Bhandara-441914  
CIN No.U01100MH2020PTC341297 Email:-bhoomisparsh.fpojamb@gmail.com

Table A



Name of the Company	Bhoomisparsh Farmer Producer Company Limited
Date Of Allotment	03/07/2020
Type of Share Allotted(Equity or Preference)	Equity Shares
Nominal Amount Per Share Rs.	10
Premium /(Discount) amount per share	100
Total Number of Allotees	259 (Two Hundred Fifty Nine)
Brief particulars in respect of terms and condition voting rihts etc.	New Shares Shall rank part passu in all respects with the existing shares.

// CERTIFIED TRUE COPY //

For, Bhoomisprash Farmer Producer Company Limited

Pankaj P.Lonare  
At-Jamb, Ta-Mohadi,  
Dist-Bhandara-441914

Kiran H.Atkari  
At-Jamb, Ta-Mohadi,  
Dist-Bhandara-441914

  
  
PRESIDENT / SECRETARY  
BHOOMISPARSH FARMER PRODUCER  
COMPANY LIMITED

132

# भुमीस्पर्श फॉर्मर प्रोड्यूसर कंपनी लिमिटेड, जांब, ता.मोहाडी, जि.भंडारा.

CIN No. :- U01100MH2020PTC341297

Mob.No. 9765599009

अध्यक्ष

किरण अतकरी

## ठरावाची सत्यप्रत

आज दिनांक ०३/१०/२०२१ दुपारी १.०० वा.भुमीस्पर्श फॉर्मर प्रोड्यूसर कंपनी लि.जांब ची सभा कंपनीचे कार्यालय येथे श्री.किरण अतकरी यांच्या अध्यक्षतेखाली घेण्यात आली व सभेला सर्व संचालकांची उपस्थिती होती.


विषय क्र.२ :- स्मार्ट प्रकल्प राबविण्याकरीता संचालकांच्या सहमतीबाबद.

ठराव क्र.२ :- सदरहु विषयाच्या अनुसंगाने सभेत चर्चा करण्यात आली कि, स्मार्ट प्रकल्प राबविण्याकरीता स्मार्ट प्रकल्पाच्या सविस्तर आराखड्यात धान पिसाई करीता राईस मिल व धान पिकाची साठवणुक करण्याकरीता अडचन असल्याने धान्य गोडाऊन व धान पिकासाठी लागणारे यंत्रे प्रकल्प आराखड्यात समाविष्ट करण्यात यावे असी चर्चा संचालकांच्या उपस्थितीत करण्यात आली व त्यासाठी लागणारे सर्व कागदपत्रे व अटिशीर्तीचे पालन करुन प्रकल्प पुर्णत्वास नेण्याकडे सुध्दा चर्चा करण्यात आली. सर्व संचालकांनी वरील विषयास मान्यता दिली.

ठराव सर्वानुमते मंजुर

सुचक :- श्री.चंद्रसेन उताने

अनुमोदक :- श्री.अशोक कुये

  
PRESIDENT/SECRETARY  
BHOOMISPARSH FARMER PRODUCER  
COMPANY LIMITED