



10	Providing and casting in situ cement concrete M-20 of trap granite/quartzite/gneiss metal for R.C.C. chajja ) Spec. NO. : Bd.F.9 Page No.18-13(b)	2.70	11199.00	cu.m.	30237.30
11	Providing and casting in situ cement concrete M-20 of trap granite/quartzite/gneiss metal for R.C.C. paradi 150mm thick Spec. NO. : Bd.F.11 Page No.19-15(b)	0.00	12663.00	cu.m.	0.00
12	Providing and casting in situ cement concrete M-20 of trap granite/quartzite/gneiss metal for steps Spec. NO. : Bd.E.2 Page No.13-3(b)	2.92	11827.00	cu.m.	34537.09
13	Providing and fixing in position mild steel bar reinforcement Spec. No. : Bd.F.17 Page No.20-19	5.00	61500.00	M.T.	307500.00
14	Providing and fixing in position HYSD bar reinforcement Tor steel. Spec. No. : Bd.F.17 Page No.21-20	10.00	65600.00	M.T.	656000.00
15	Providing second class Burnt Brick masonry with conventional/I.S. type bricks in cement mortar 1:6 In foundallons Spec No. : Bd.G.1 Page No.25-1	28.56	5820.00	cu.m.	166219.20
16	Providing second class Burnt Brick masonry with conventional/I.S. type bricks in cement mortar 1:6 In superstructure i Spec No. : Bd.G.5 Page No.25.-4	96.57	7004.00	cu.m.	676376.28
17	Providing second class Burnt Brick masonry with conventional/I.S. type bricks in cement mortar 1:4 in half brick thick wall = Spec No. : Bd.G.7 Page No.25-5	0.00	815.00	SQ.M.	0.00
18	Providing & laying water proof treatment on terrace slab with S.B.Coba . Spec. : No.BD.J7 Page No. 35-5	0.00	937.00	SQ.M.	0.00
19	Providing Internal cement plaster 12mm thick Spec. No. : Bd. L.2 Page No.39-3	1237.71	168.00	SQ.M.	207935.28
20	Providing neeru finish Spec. No. : Bd. L.10 Page No.40-14	1237.71	51.00	SQ.M.	63123.21
21	Providing sand faced plaster externally in cement mortar Spec. No. : Bd. L.7 Page No.40-11	729.28	679.00	SQ.M.	495181.12
22	Providing and laying Marbonlle Tiles Flooring Spec. No. : Bd.M.3 Page No. 42-6	629.38	1645.00	SQ.M.	1035330.10
23	Providing and fixing in required position, skirting or dado of Morbonlle Tiles Spec. No. : Bd.M.5 Page No. 42-9	19.91	1645.00	SQ.M.	32751.95

18	Providing and applying Luster Paint Spec No. B.3 P. 5A Page No. 69-10	602.67	160.00	SQ.M.	96471.20
19	Providing and applying two coats of water proof Apex paint o Spec No. B.1. C. 8 Page No. 64-12	502.67	145.00	SQ.M.	72886.43
20	Providing and fixing Flush Door Spec No. B.1. 15 Page 90 - 35	13.55	2333.00	SQ.M.	31612.15
21	Alu Window powder coating with box Spec. No. B.1 Page 102 - 86	27.3	4744.00	SQ.M.	129511.20
22	Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabrication hoisting, erecting fixing in	16.5	66956.00	M.T.	1104774.00
23	Providing and fixing corrugated Galvanised iron sheets of 0.63 mm thickness (24 B.W.G) for roofing without wind tiles including fastening with galvanized iron screw and bolts and lead and bitumen washers as per drawing complete	814.47	1667.00	SQ.M.	1357721.49
<b>TOTAL COST OF CIVIL WORK</b>					<b>6427624.35</b>

GROUND FLOOR CIVIL WORK	7033589.59
FIRST FLOOR CIVIL WORK	6427624.35
TOTAL COST OF GROUND FLOOR CIVIL WORK	13461213.94
ADD ELECTRIFICATION 5.0 %	673060.6971
ADD SANITARY WORK 5.0 %	673060.6971
ADD CONTINGENCIES 7.0 %	942284.9759
ADD ARCHITECT FEE 3.0 %	403836.4182
<b>TOTAL COST</b>	<b>16153456.73</b>

*G. Bhaskar*  
**Gaurav Rajendra Bhaskar**  
 B.E. (Civil) A.M.I.E.  
 Chartered Engineer  
 AM3023322

ABHIRAJ ENGICON PRIVATE LIMITED

*N. Manoj*  
 MANAGING DIRECTOR

**Quotation**

To  
M/s Ishwara Farms Producer Company Ltd.  
Talpe, Tal Phaltan, Dist. Satara,  
Maharashtra 415521

Date : 28.02.2022  
Qtn. No. : KC-GS/2122/41  
Ref.:

Kind Attn.: Mr.Chand

Dear Sir,

Thank you for your valuable enquiry. Please find attached our quotation with all technical specification.


Sl. No.	Description	Quantity	Unit	Unit Rate (Rs.)	GST (18%)	Total (Rs.)	Grand Total (Rs.)
<b>External – 17ft L x 7ft 6in W x 7ft 6in H</b>							
3	Supply, Installation of 17ft Long Insulated Truck body external MS Corrugated with PUF & 4mm Plywood Cladding with Stainless Steel – 0.4mm inside for maintaining minus 25°C.	1	No.	5,50,000/00	99,000.00	6,49,000.00	6,49,000/-
4	Refrigeration Unit / Make – Carrier / Type – Self Powered / Model – Oasis 250	1	No.	6,55,000.00	1,17,900.00	7,72,900.00	7,72,900/-

**Technical Details**

Outer Panel -	MS 1.5mm Corrugated Sheet
Inner Panel -	Stainless Steel 0.4mm Sheet with 4mm Marine Grade Plywood cladding
Corner Profiles -	3mm THK press section with 5mm MS Angle reinforcement inside each pillar.
Cross Member-	100 x 50 x 5mm C Type Channel
Sub Frame -	C Chanel – 150 x 65mm
Flooring Type –	Aluminium T Section, Make – Hindalco 40 mm Height
Insulation -	125 mm PUF for floor & Roof, 115mm PUF insulation for side walls.
Door Hardware -	Galvanised Steel

**Kryo Containers Private Limited**  
Plot No. PAP B 127, Chakan Industrial Area,  
Phase-2, Bhamboli, Khed, Pune 410 501  
CIN : U74999PN2020PTC191267

www.mykryo.i  
Contact : info@mykryo.  
+91 8879923281 / +91 94035974  
GSTIN : 27AAICK1171F12



Lights -	2 Internal LED Lights will be provided, 2 No's marker lamps will be provided on both sides
Door Sealing -	EPDM 5 Leaf Door Sealers.
Paint	2 Coat Epoxy Primer & 2 Coat PU Paint
Drainage -	Proper Drainage System with necessary Valves.
Waterproofing -	Waterproofing on roof & Floor.
Door Curtains	PVC Strip Type
Notcher Door	Yes
UPD	Will be supplied
Steps / Ladder	On container front wall & back side of the vehicle chassis.
Internal Height demarcation will be provided for loading purpose.	

#### Terms & Conditions:

1. GST – 18% for Body.
2. Delivery Schedule – Within 20/25 days from date of advance receipt Along with PO.
3. Payment Terms – 100% Advance for reefer unit. 75% of container along with PO & 25% at the time of delivery.
4. Inspection – Final Inspection will be carried out at our premise in presence of your Team.
5. Transport – To & Fro in Clients scope.
6. Diesel for reefer unit testing to be provided by client

Please feel free to call for any further queries.

Looking for your favorable response. Thank you in advance.

Warm Regards,



**Sairik Saha**  
**MYKRYO Containers Pvt.Ltd.**  
[www.mykryo.in](http://www.mykryo.in)  
 91 887923281

**Kryo Containers Private Limited**  
 Plot No. PAP B 127, Chakan Industrial Area,  
 Phase-2, Bhamboli, Khed, Pune 410 501  
 CIN : U74999PN2020PTC191267

[www.mykryo.in](http://www.mykryo.in)  
 Contact : [info@mykryo.in](mailto:info@mykryo.in)  
 +91 8879923281 / +91 94035974  
 GSTIN : 27AAICK1171F1Z

## Annexure 1 : Technical Details

### 1. Technical Details for Cold Storage (10°C)

Outer Size (Met.) : 8.53 X 12.40 X 2.80 (WXDXH)  
 : 28 X 41 X 9.5' (Feet)

Internal Size : 9550 CFT (40 to 45 Mt)

Room Temperature : +0°C to +4°C

Panel Construction : Prefabricated sandwich panels with Cam lock, so room becomes air tight.

Panel Thickness : 80 mm, density 40 Kg/m<sup>3</sup>, Both side PPGI sheet with PVC film.

Floor Insulation : 80 mm PUF Panels Aluminum Chq. Plate.

Door : Flush type Swing Door with Closer, Heavy duty S. S. Hinges. Door frame made in Heavy duty PVC profile & Push type Gasket. Opening size 34" X 78" (860mm X 1980mm), Aluminum Checkered Plate on both side of Door bottom to reduce damage.

### 2. Technical Detail for Refrigeration Unit for Cold Storage

Daikin make outdoor condensing Unit with Emerson Scroll Compressor. & Top hanging type Indoor Unit cooler with axial Fan. Powder coated aluminum casing with stainless steel hardware. Drain Pipeline with Heater.

Refrigeration Unit Model : LRMS-0600-AXY1 / BLC-440-2  
 Refrigeration Unit Type : Air Cooled Split Type  
 Compressor : Emerson Scroll (Cooling Cap. 12.5 kW @ 0 Evaporating)  
 Refrigerant : R-407c  
 Connected Load : 6.5 HP / 4.88 kW (380-415 V, 3 Ph)

### 3. Electrical Control Panel

User friendly control panels with On / Off Switch & Digital Controller.

- Voltage imbalance & Single phasing Protection
- Standard electric parts from Schneider (Telemecanique / Siemens)
- Overload & Low Pressure protections with Fault Indicator

**Annexure 2 : Price Schedule**

Sr. No.	Items	Qty.	Rate	Amount
1	Cold Room Panels 80mm & Installation	1	9,30,000.00	9,30,000.00
2	Ref. System (12.5kW Daikin) & Control Panel	2	2,60,000.00	5,20,000.00
		Sub Total		14,50,000.00
		G.S.T.	18%	2,61,000.00
		TOTAL		17,11,000.00

Piping length is estimated at 5 Met, for piping length longer than 5 Met, price will be charged extra.

**EXCLUSIONS:**

- Unloading & Safe storage of the panels, equipment's & erection material.
- Any civil & structural works, secondary roofing etc.
- Weather protection for the condensing units.
- Cable from main supply board to control panel
- Single phase 230V, 50 Hz 32 A power supply for installation activity.
- Provision of lights for inside the rooms.
- Any other item not specified in our offer.

**Annexure 3 : Commercial Terms and Conditions**

**DELIVERY TIME** : 3 - 4 weeks from the receipt of the payment. (To be reconfirmed with Purchase Order with all Technical Specification needed to manufacture the machine.)

**PAYMENT TERMS** : 70% advance with your PO. 30% against Pro. Invoice before Dispatch.

**TAXES** : GST Extra on Basic Price as applicable (Our GST No: - 27AGZPG6837E1ZV)

**INSPECTION** : Finished Products can be inspected by you or your representative at factory prior to dispatch day & date mutually decided, at your cost.

**CONNECTIONS** : All Electrical / Water Connections up to the machines to be done before the arrival of our technician by the buyer as per drawing which shall be provided after order Confirmation.

**TRANSPORTATION** : Extra

**WARRANTY** : One year against Manufacturing Defects. We shall repair / replace such parts which may prove defective and which do not fall from neglect or misuse or faulty operation. No warranty for electrical parts. Parts subject to normal wear & tear are void warranty. Warranty starts from the date of receipt of Goods at site.

**VALIDITY** : This offer is valid for 15 days from the date of issue.

**CANCELLATION** : Once order confirmed, would not be cancelled. However, If any order or part of order is cancelled, the cancellation charges will be levied as compensation for cost and expenses incurred by Scanvision up to the date of cancellation. Such cancellation charge would be minimum 25% of the order.

**NOTE - Our offer does not include any Octrol / Cess / Entry or similar Tax. The same will be Payable by you directly to the Authorities.**

For Scanvision Invensys

Mahendra Gawand

+91 9321 101199 / +91 9341 101199  
 (Computerized transmission, hence no signature)