


**NAME OF WORK-Construction of Warehouse FOR Agro produsing work with Compound wall
and R.C.C.C.staff cabin**

**Agency Name - SITAMAI AGRO PRODUSAR COMPANY LIMITED, A/P- SHIRATE ,TAL-WALWA (SANGLI)
Abstract sheet**



sr.no	Discription	Qty	Unit	Rate	Amount(rs)
1	Providing and laying cast in situ / Ready Mix Cement Concrete M-20 for double rim bored pile of 450 mm dia. each of load capacity as per design and of specified diameter of pile and bulb as directed, sunk to therequired depth through all strata except rock,excluding provision of reinforcement including placing with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) by tremie arrangement compaction of concrete including chipping and dressing etc. complete. (Excluding steel reinforcement)	105.11	Running mtr	2575	270658.25
2	Excavation for foundation in earth, soils of all types, sand,gravel and soft murum, including removing the excavated material upto a distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, rramming, watering including shoring and strutting etc. complete. (Lift from 1.5m to 3.0m) By Manual Means	144.3	cubic mtr	306	44155.8

Gopichand V. Patil

GOPICHAND V. PATIL
B.E (CIVIL)
Engr. & Govt. Regd. Contractor