

||SHREE||

POONAM ENGINEERING WORKS

Specialize in: -

Fully Automatic Dall Mill, Grain Cleaning Plant, Grain Dryer, Besan Plant, Atta Chakki Plant, Vibro Separator (MTRA), Di-stoner, Gravity Separator, Hammer, etc.

PLOT NO N-243, MIDC PHASE IV, AKOLA - 444104 (MS)

Mo. +918080485406, +91 9371007484

Web:-www.poonamengworks.in

Email:poonamengworks4@gmail.com

{SEND BY - POOJA PATIL}

QUOTATION

To,


Date: - 10/09/2022

DHARMABAD

Agro Producer Company Ltd. Dhanora.

REF: "TOOR DALL MILL 1TPH"

Sr.No.	Description	Qty	Rate	Amount
1.	Grader (Chalna). *4 Sheet dai 21''X30'' inside Φ 1.5''m/s shafting, pulley, Bering, the structure of machines made in a m/s Angel and 16-18-gauge m/s sheet, with mesh, with motor 1 HP IE2.	02	85000/-	170000/-
2.	Grader (Chalna). *3 Sheet dai 21''X30'' inside Φ 1.5''m/s shafting, pulley, Bering, the structure of machines made in a m/s Angel and 16-18-gauge m/s sheet, with mesh, with motor 1 HP IE2.	04	75000/-	300000/-
3.	Di-stoner Double (Plot) 5HP.	01	145000/-	145000/-
4.	Bucket Elevators. *Inside Φ 1.25'' m/s shafting, pulley, UC Bering, cotton nylon belt 4'', M/S Bucket- 4'', height 16', m/s box 18-gauge, m/s top bottom 16 gauge, with motor 2 HP IE2.	10	51000/-	510000/-
5.	Roll petty. *Emery roll Φ 10''x27'' with Motor 10HP, in side Φ 2''m/s shafting, Bering 3pc, the- foundation of this machine is made 4''c-channels.	03	71500/-	214500/-
6.	Petti Fan. *m/s 14-gauge fan body, In side Φ 1.5'' m/s shafting, UC Bering, with motor 1 HP IE2.	07	35200/-	246400/-
7.	M/s Warm. * Φ 8'' length 12 feet U- m/s 16 Gauge, In side Φ 1.5'' m/s shafting, with motor 1 HP IE2.	03	35000/-	105000/-
8.	Machinery Structure, Pipe, Pulley, Belt.	00	280000/-	280000/-
9.	Stock Hopper. *Capacity 12 TON. *Dryer hopper.	06 02	175000/- 95000/-	1050000/- 190000/-
10.	Dall Stock Hopper *Capacity 10 TON. *Capacity 03 TON.	02 02	145000/- 45000/-	290000/- 90000/-
11.	Grain Dryer 1.5TPH complete set. *M/S Trolley (1.5TPH)2pc, panels in starter, Sensor, with motor.	02	280000/-	560000/-



[[NITRE]]

ISO 9001:2015
GST NO. 27AJFPV537BN128

POONAM ENGINEERING WORKS

Specialize in:-

Fully Automatic Dall Mill, Grain Cleaning Plant, Grain Dryer, Besan Plant, Atta Chakki Plant, Vibro Separator (MTRA), Di-stoner, Gravity Separator, Hammer, etc.

PLOT NO N-243, MIDC PHASE IV, AKOLA - 444104 (MS)

Mo. +918080485406, +91 9371007484

Web:-www.poonamengworks.in

Email:poonamengworks4@gmail.com

[SEND BY - POOJA PATIL]

POLISHER

12.	M/s Warm. *Φ 8" length 12 feet U- m/s 16 Gauge, In side Φ 1.5" m/s shafting, with motor 1 HP IE2.	03	38500/-	115500/-
13.	Buff Polisher. *Φ 12"x30" with Motor stand in side Φ 2" m/s shafting, Bering 3pc, the foundation of this machine is made 4" c-channels, with motor 15HP.	01	165000/-	165000/-
14.	Bucket Elevators. *Inside Φ 1.25" m/s shafting, pulley, UC Bering, cotton nylon belt 4", M/S Bucket- 4", height 16', m/s box 18-gauge, m/s top bottom 16 gauge, with motor 2 HP IE2.	01	51000/-	51000/-
15.	Machinery Structure, Pipe.	00	244200/-	244200/-
16.	Transportation charges.	--	218316/-	218316/-
17.	Machinery Fitting Charges.	--	250000/-	250000/-
Total				5194916/-
GST @18%				935084/-
Total Amount				6130000/-

SPECIFICATION

MODEL	PEWDMT-01
CAPACITY	1 TPH
POWER	108 HP
MACHINE TYPE	AUTOMATIC

Terms & Condition

- Prices Net - All Price are Ex- Factory Akola.
- Transportation Charges as applicable.
- Packing and Forwarding Charges Extra at Actual.
- Delivery Period - In 2 months from the date of Receipt you confirm order.
- Payment - 70% Advance at the time of confirmation of order.
- Balance 30% Payment before Dispatch.
- Quotation Valid for 15 days, otherwise Subject to our Confirmation.
- Electric panel, electric fitting & civil work party will provide.
- Motors & Gear Motors mfg. difficulties for near service centre provide.
- Total Electric load 108 HP

I Agree Terms & Condition
For Purchaser

Signature

2

For Poonam Engineering Works

