

ABSTRACT


OF THE WORK :- Propose Construction Of Factory's head For
HORTIGROW FARMER'S PRODUCER COMPANY LTD.

NO. U01100MH2020PTC351994

134/1(Part) Mouje - Tondgaon, G.P. Tondgaon
Bazar. Dist. Amravati

On
TQ.Chandur

Details of Item	Quantity	Rate	Per	Amount
CIVIL-WORK				
Excavation For Foundation in silt with 1.5 left M. lead etc. Complet	270.95	130.00	M ³	35224.00
Binding & Construction of P.C.C. Concrete 1:4:8 include compaction & curing comp	23.22	2410.00	M ³	55960.00
Binding & Construction of R.C.C. Concrete for Coloumn Beam include centering complet	85.72	4800.00	M ³	411456.00
Binding & Pleacing of Reinforcement as Desgings include bent up, binding etc plet	134.58	5100.00	Qt.	686358.00
Binding & Construction second class Masonry in C.M. 1:6 include curing Complet	25.74	4700.00	Qt.	120978.00
Binding & filling With Boulder & murrum de Watering & compaction etc. Complet	416.42	900.00	M ³	374778.00
Binding & filling 80mm Aggregate	249.84	1100.00	M ³	274824.00
Binding & Construction of P.C.C. Concrete 1:4:8 include compaction & curing comp	124.92	2410.00	M ³	301057.00
Binding & filling Trimix Concerte	83.28	2900.00	M ³	241512.00
Binding & Construction second class Masonry in C.M. 1:6 include curing Complet	106.94	4700.00	M ³	502618.00
Binding & Construction of R.C.C. Concrete for Coloumn Beam include centering complet	50.92	4800.00	M ³	244416.00
Binding & Pleacing of Reinforcement as Desgings include bent up, binding etc plet	79.94	5100.00	Qt.	407694.00



Rajesh B. Tadas
B.E., D.C.E., Civil
Paratwada

121

ing T.W. Pannel Door including hold etc. Complet	4.20	3700.00	M ²	15540.00
ing M.S. Frame fully glazed window complet	10.80	3963.00	M ²	42800.00
Frame lourved type Ventilator etc. et	9.00	2540.00	M ²	22860.00
Rolling Shutter	20.22	2000.00	M ²	40440.00
Total-A				3778515.00

Roof And Roof Covering Works

ctural Steel members for the Building, ndary Members, Sheeting & Trims etc.	870.96	4500.00	M ²	3919320.00
ght Polycarbonate Panel on Roof Only-	17.00	1200.00	M ²	20400.00
vents-24" with Polycarbonate Base	10.00	7000.00	No.	70000.00
ion Charges For P.E.B.				350000.00
Total - B				4359720.00
Total A+B				8138235.00
5% Electricfication charges				406911
3% Water Supply & Sanitary fitting				244147
3% Eingeiner supervision charges				244147
Grand Total				9033440.00


Rajesh B. Tadas
 B.E.,D.C.E.,Civil .
 Paratwada

MEASUREMENT SHEET

DESCRIPTION OF THE WORK :- Prapose Construction Of Factoryshead For

HORTIGROW FARMER'S PRODUCER COMPANY LTD.

CIN NO. U01100MH2020PTC351994

No.134/1(Part) Mouje - Tondgaon, G.P. Tondgaon
Dist. Amravati

On
TQ.Chandur Bazar.


Detail of Item	No.	Length	Width	Height	Quantity	Total
Excavation for foundation	42	1.92	1.92	1.75	270.95	270.95M³
C.C. Bed Concrete	42	1.92	1.92	0.15	23.22	23.22 M³
C.C. Work						
Coloumn footing	42	1.92	1.92	0.15	23.22	
	42	1.20	1.20	0.3	18.14	
coloumn	28	0.60	0.45	2.20	16.63	
	14	0.45	0.23	2.20	3.19	
Plinth beam	2	22.86	0.23	0.30	3.15	
	9	22.86	0.23	0.30	14.20	
	2	37.64	0.23	0.30	5.19	
	2	3.66	0.23	0.30	0.51	
	4	2.10	0.23	0.30	0.57	
	2	3.87	0.23	0.30	0.53	
						85.72 M³
Reinforcement (2% R.C.C.)	<u>2X85.72X78.5</u>					134.58QL
	100					
Masonry						
Wall	2	22.86	0.23	0.75	7.89	
	2	37.68	0.23	0.75	13.00	
	2	3.87	0.23	0.65	1.16	
	4	2.10	0.23	0.65	1.26	
	2	3.66	0.23	0.75	1.26	
	2	3.61	0.23	0.75	1.25	
						25.74 M³
um & Boulder Filling						

123



Factory Shead	1	22.40	37.18	0.50	416.42	
40mm Aggregate						416.42 M ³
Factory Shead	1	22.40	37.18	0.30	249.85	
C.C. Bed Concrete						249.84 M ³
Factory Shead	1	22.40	37.18	0.15	124.92	
Concrete						124.92 M ³
Factory Shead	1	22.40	37.18	0.10	83.28	
Concrete						83.28 M ³
Brick Masonry (In SuperStructure)						
Wall	2	19.71	0.23	4.56	41.34	
	1	33.50	0.23	3.30	25.43	
	1	33.50	0.23	4.30	33.13	
	2	3.66	0.23	2.70	4.55	
	2	3.61	0.23	2.70	4.48	
						106.94 M ³
C. C. Work						
Coloumn	9	0.60	0.45	3.60	8.75	
Coloumn	9	0.60	0.45	4.60	11.18	
	10	0.60	0.45	6.40	17.28	
	14	0.30	0.23	4.56	4.40	
Lintel Béam	2	22.86	0.23	0.30	3.15	
	2	37.64	0.23	0.30	5.19	
	2	3.66	0.23	0.30	0.51	
	2	3.61	0.23	0.30	0.50	
						50.92 M ³
Reinforcement (2% R:C.C.)	2X50.92X78.5					79.94 Qt
	100					
D	2	1.00	-	2.10	4.20	
						4.20M ²

Window	6	1.20	-	1.50	10.80	
						10.80 M ²
Ventilator V	20	1.00	-	0.45	9.00	
						9.00 M ²
Rolling Shutter	2	3.37	-	3.00	20.22	
						20.22 M ²
Structural Steel members for the Building, Secondary Members, Sheeting & Trims etc.						
Factory Shead	1				870.96	
						870.96 M ³
Skylight Polycarbonate Panel on Roof Only- Qty						
Factory Shead	1				17.00	
						17.00M ³
Turbovents-24" with Polycarbonate Base						
	10				10.00	
						10.00 No


Rajesh B. Tadas
 B.E.,D.C.E.,Civil
 Paratwada