



SINCE 1971

GOYUM TECHNICAL HOLDINGS PVT. LTD.

► Extraction ► Refining ► Recycling

(A Govt. of India Recognized Export House)

324, INDUSTRIAL AREA - A, LUDHIANA-141003. (PUNJAB) INDIA.

PH: +91-161-4603180 Mobile: +91-98140-33180,+91-99150-43180

Email: jain@oilmillmachinery.com, gs@oilmillmachinery.com

Website: www.oilexpeller.com and www.goyumgroup.com

► AN ISO 9001:2008 CERTIFIED COMPANY

To,

M/s I Watch Farmer Producer Company Ltd.
Registration No.: U01110MH2019PTC322152.
Maharashtra
Email- iwathfpc@gmail.com

P.I. No.: GTH /4465

DATED: 12.09.2022

18-20 Ton Per Day Soya Oil Extraction Plant with Extruder

S. NO.	DESCRIPTION	QTY.	PRICE IN INR PER UNIT	AMOUNT IN INR
1.	OIL PRESS GOYUM -150 (Capacity 18-20 Tons per day) Double reduction gearbox having steel casted helical gears in oil bath, steel casted chamber, complete with Motor, V-Belts and Foundation Bolts etc. With Electrical. Power Required: 40 HP.	1 Unit.	1850000.00	1850000.00
2.	GOYUM HEAVY DUTY SOYA EXTRUDER Complete with all accessories and all electrical. High Capacity 18-20 Tones in 24 Hrs. Power Required: 120 HP Inlet chamber-2, compression chamber-2, Nose cap-1, feeding motor 2 H.P. and Stainless Steel Feeder.	1 Unit.	1300000.00	1300000.00
3.	GOYUM' SOYA CRACKER with electrical. Capacity 30 Tones in 24 Hrs.	1 Unit.	525000.00	525000.00
4.	GOYUM' SEED CLEANER with electrical. Capacity 30 Tones in 24 Hrs.	1 Unit.	450000.00	450000.00
5.	GOYUM' VACCUM DESTONER with electrical. Capacity: 30 Tones in 24 Hrs.	1 Unit.	395000.00	395000.00
6.	GOYUM' MAGNETIC SEPARATOR with electrical. Capacity: 30 Tones in 24 Hrs. (static)	1 Unit.	380000.00	380000.00
7.	GOYUM' FILTER PRESS complete with oil trough, pet cocks, pressure gauge, plunger pump complete with all accessories. Size: 24" x 24" + 24 Plates. With Electrical. Power Required: 3HP	1 Unit.	410000.00	410000.00
8.	GOYUM' HAMMER MILL with electrical. Capacity: 20 Tones in 24 Hrs.	1 No.	350000.00	350000.00
9.	BUCKET ELEVATOR with Chain, Buckets and all accessories. With Electrical.	6 No.	135000.00	810000.00
10.	TAPER SCREW CONVEYOR for soya extruder to oil press feeding. With electrical (Stainless Steel)	1 No.	175000.00	175000.00
11.	SCREW CONVEYOR with accessories. With Electrical.	1 Lot.	450000.00	450000.00
12.	SPARE PART KIT .	1 Lot.	257000.00	275000.00
14.	ELECTRICAL CONTROL PANEL.	1 No.	475000.00	475000.00
15.	MEAL COOLER	1 Unit.	950000.00	950000.00
16.	INSTALLATION CHARGES			525000.00
			Ex-Works Prices :	9320000.00
			Transportation :	180000.00
			G.S.T 18%:	1710000.00
			Grand Total:	11210000.00

(In Words Rupees: One Crore Twelve Lac Ten Thousand Only.)

For Goyum Technical Holdings Pvt. Ltd.

Mg Director

1. PACKAGING AND SHIPPING

As Required.

2. VALIDITY OF THE QUOTATION

This offer is valid for acceptance for **10 Days** from the Proforma Invoice Date.

3. DELIVERY

The ideal delivery time of the equipment as mentioned above is between **60 and 90 Calendar Days**.

Firm delivery time shall be given after the clarification of all commercial details and receipt of advance payment as per "Terms of Payment".

THE DELIVERY IS ESTIMATED ON PRESENT CONDITIONS. WE CANNOT BE HELD RESPONSIBLE FOR DELAYS BY FORCE MAJEURE, LABOUR, STRIKE, LOCKOUT, BREAKDOWNS, BY TRANSPORTER, ACT OF LEGISLATURE, ACT OF GOD, AND STRIKE AT THE PORTS OR ANY EVENTS WHATSOEVER BEYOND OUR CONTROL. ANY DISPUTES ARISING OUT OF THE CONTRACT WILL BE SETTLED IN LUDHIANA (INDIA) COURTS JURISDICTION.

4. TERMS OF PAYMENT

The Terms of payment are:

- (I) **40%** advance payment at the time of confirmation of order.
- (II) **Balance** at the time of dispatch.

BANK DETAILS:

PUNJAB NATIONAL BANK,
Account No.0298001800000118 of
M/s. GOYUM TECHNICAL HOLDINGS PVT. LTD.
LUDHIANA
with **PUNJAB NATIONAL BANK,**
MILLER GANJ, LUDHIANA
RTGS No: PUNB0029800
PNB BANK CODE-024

5. INSURANCE AND INSPECTION

To be taken care by the Buyer.

6. CHARGES FOR EXPERT / ENGINEER

We shall depute our Expert / Engineer for Supervision of Installation and Commissioning and for providing Training at a charge of **INR 2000 (Rupees Two Thousand Only)** Per Day per Engineer.

Further the client shall provide at **NO COST** to us the following for our Engineer.

- To and Fro Air Tickets from Ludhiana – Site – Ludhiana.
- Boarding and Lodging facility.
- Medical and Local Conveyances.
- Use of Communications Facilities like Fax, Telephone, Internet, etc.

PART II: PERFORMANCE DETAILS

1. CAPACITY

The equipment will process approx. 18-20 Tons Soybeans & Sunflower in 24 Hrs.

2. RAW MATERIALS

Soybeans entering the mill building is to be of prime quality. Assuming the raw material specifications defined as under:

Oil content	16% - 18%
Moisture	7% - 8% maximum
Temperature	20°C minimum
Impurities content	2 % maximum – but free of stones
Foots Generation	3 – 5 %

3. QUALITY OF THE FINISHED PRODUCTS

Oil Cake with:

Residual oil content	5% - 6 % Approx.
Temperature	40°C – 50°C

REMARKS:

All the above figures apply simultaneously, with the relevant tolerances of +/- 5% to the plant running in normal operating conditions at its guaranteed capacity on a homogeneous lot of material to be treated.

Dry saturated steam, electricity and lubricants being supplied to the plant at constant rate and quality and without interruption.

Any over and under consumption of utilities will be offset against each other in Value.

PART III: UTILITY CONSUMPTION

1. ELECTRICITY

Power Requirement (For Quoted Equipment)	170 kW Approx.
--	----------------

2. MANPOWER (Approx.)

Designation	No. off	Duties
Manager	1	Official Work, Billing, Stock Register, Maintenance etc.
Engineer cum Supervisor	1	To guide semiskilled & unskilled person in Machine fitting during maintenance. To check quality of incoming seed. To Supervise Loading & unloading of Trucks, Cake Bag counting, Checking Quality of Extracted Oil per shift, To supervise in Milling Section.
Electrician	1	For all Electrical Maintenance.
Semi - Skilled	1 / 8Hrs. Shift	To check machines are working in perfect condition, starting & stopping of Machine.
Unskilled	2 / 8Hrs. Shift	Miscellaneous Jobs
Unskilled	2 / 8Hrs. Shift	Cake Bagging & Stitching
Unskilled	2 / 8Hrs. Shift	Seed Bag Emptying Section

Manpower required for Loading and Unloading for Cake and Seed resp. is not included in the above list.

PART II: EXCLUSIONS

(PLEASE READ THOROUGHLY)

- I. All site civil works: excavations, foundations, concrete works, masonry, anchorage, perforation, bedding, etc.
- II. Buildings, including siding and roofing.
- III. Scaffolding, tools, gas, electricity, etc. required for installation Purpose.
- IV. Loading, Unloading and shifting the equipment's to erection points.
- V. All lubricants.
- VI. Electric power generation, transformation and distribution outside battery limit.
- VII. Weigh Bridge for weighing incoming and outgoing material by trucks, etc.
- VIII. Pipes, Pipe Fittings and valves required for handling extracted Oil, Steam, Condensate.
- IX. All Chutes and Hoppers wherever required
- X. Insulation Material
- XI. All Electric Cables and supporting material for Cables.
- XII. Fabricating Equipment's Welding Rods.
- XIII. Lab Equipment's.
- XIV. Crude Oil Tank and Filtered Oil Tank
- XV. Any other item which is not specified or included in our prices.