


Kumar Metal Industries Pvt. Ltd.

Head Office #101, Kakad Bhavan, 30th Road, Opp, Gaiety Galaxy Cinema,
Bandra W, Mumbai 400050. India
+91 22 2644 1673 | 2644 1667 (t) | +91 22 2642 8136 (f)
info@kumarmetal.com | www.kumarmetal.com
linkedin.com/company/kumarmetal | CIN No. U17291MH2007PTC168776

Turnkey solutions: Oil mills | Edible oil refineries | Solvent extraction plants



Vande Bharat Agro Producers Co. Ltd.

Karanja Lad, Washim- 444105- Maharashtra.

Proforma Invoice No. KMIPL/P21D01011

Date : 06.07.2022

S.N	Item Description	Qty	Rate (Rs.)	Total (Rs.)
I	Design, Engineering, Manufacture & Supply of 90 TPD Oil Mill Machinery for Soybean with Extruder system	1 Unit		
1	Material Handling Equipments	1 Set	2,271,000	2,271,000
a	Screw Conveyors with drive and accessories	1 Set		
b	Bucket Elevators with drive and accessories	1 Set		
2	Seed Preparatory Section	1 Set	1,855,000	1,855,000
a	Seed cleaner with Aspiration System, Motor and accessories for removing impurities from feed material (Capacity 90 TPD)	1 Unit		
b	Destoner with Aspiration System, Motor and accessories for removing stones (Capacity 90 TPD)	1 Unit		
c	Hammer Mill complete with beaters, vibro mounts, 50 HP Electric Motor and accessories (Capacity 90 TPD)	1 Unit		
3	Seed Crushing Section	1 Set	13,482,000	13,482,000
a	Soya Extruder Capacity 800-1000 kg/Hr along with Electric Motor 125 HP/1440 RPM, Control Panel, Spares and Tools (Bronto Make)	3 Units		
b	Kumar's New Super Press Series NSP IIICLD Oil Expellers Having triple stage helical reduction gear box, M.S. hard faced worm assembly, cage bars, knife bars and main shaft of alloy steel. Complete with oil and foots discharge conveyor with all necessary accessories and 150 HP Electric motor	1 Unit		
4	Meal Section	1 Set	2,010,000	2,010,000
a	Hammer Mill complete with beaters, vibro mounts, 40 HP Electric Motor and accessories (Capacity 90 TPD)	1 Unit		
b	Cake cooler : To cool the cake before bagging Capacity 100 TPD	1 Unit		
5	Filtration Section	1 Set	661,500	661,500
a	Vibro Separator 36"	1 Unit		
b	Kumar Filter Press 25" x 25" x 25 Plates Plate Type Centre feed, Complete with Screw tightening arrangement, filter cloth set, Cocks, Pressure Gauge, Safety valve and pump with motor	1 Unit		

6	Intermediate Tanks (C.K.D.Condition) and Pumps	1 Set	610,500	610,500
i	Oil-N-Foots Tank with Agitator - 1 Set			
ii	Pre Cleaned Oil Tank - 1 No.			
iii	Filtered Oil Tank - 1 No.			
iv	Pumps with Motors, base frame and accessories	3 Sets		
7	Electrical Accessories and Panel	1 Set	3,150,000	3,150,000
i	Pipes, Valves and fittings	1 Lot		
ii	Control Panel with soft starter, Cables and accessories	1 Unit		
IV	Supervision charges for Erection and Commissioning activities consists of - 1 Site Engineer for 3 months for Oil Mill 1 Commissioning Engineer for 15 days for Oil Mill 1 Electrician for 1 months			560,000
Total Ex-Works Rs.				24,600,000

Terms & Conditions

Delivery:

Within 150-180 Days From Receipt of Down Payment and Cleared PO.

Validity:

Offer is valid for 30 days and thereafter subject to our re-confirmation

Confidentiality and Restrictions:

This Proforma Invoice is property of Kumar Metal Industries Pvt Ltd. and is a confidential presentation to Buyer for its exclusive use in considering the Equipment of Seller and shall not be disclosed to third parties without prior written consent from the Seller.

Payment terms:

40% advance along with the Cleared PO and Balance 60% on readiness of the material before

GST : 18% EXTRA

Packing/Forwarding : 3% Extra

TCS : Extra 0.075% on the Final value

Freight/Insurance - Extra at Your Cost

Bank Details :

A/c. Name : Kumar Metal Industries P. Ltd

Bank : Canara Bank

Branch : Bandra (w),Mumbai-400 050.

A/c. no : 0103201008568

RTGS CODE : CNRB0000103

List of Exclusion

- 1 All civil work & foundation of equipments and Bolts
- 2 Painting materials
- 3 Insulation and Painting materials
- 4 Laboratory equipment
- 5 Steel structure for equipment support, railing, ladder. platform etc
- 6 Roofing sheet and claddings
- 7 Bulk oil storage tanks with pumps, pipe line etc
- 8 Main power receiving station and power distribution system
- 9 Skilled / un skilled labours, Tools, tackles and consumables like welding rods, cutting gas etc for installation of the plant
- 10 Unloading of the equipments at site
- 11 Generator set
- 12 Workshop equipments
- 13 Cake Bagging and stitching unit
- 14 Fire extinguishers, fire hydrants etc
- 15 Return air fare tickets from Mumbai to site and local transport from house to site for our supervisor
- 16 Boarding and lodging
- 17 All other utilities not specifically mentioned in the offer

Notes

- a) Our supervisor will arrive at site once the civil work and foundations is completed as per our drawings. Our commissioning engineer will come once the plant is completely installed and ready for commissioning
- b) All goods will be guaranteed against manufacturing defects for one year from date of despatch
- c) All layout/foundation drawings etc. will be provided after confirmation of the order and receipt of down payment.
- d) All goods supplied as per Packing list shall be construed as received in total content, quantity or number of packages & condition at your delivery site, unless discrepancy, if any, is notified by an email on "info@kumarmetal.com" within 15 days of clearance of the goods from the Port of Discharge or 30 days of date of arrival at destination port whichever is earlier.
- e) Any subsequent loss, damage or shortage of material on site would be on your account if the goods are unpacked in absence of our Company representative.

For Kumar Metal Industries Pvt Ltd

Director