

VAASTU ENGINEERS & ARCHITECTS, TAHARABAD

Er. Amit S. Hire (B.E. CIVIL, A.I.C.T.E.)

Cell No.9881884542

OFFICE ADD. : MAIN ROAD, NEW BUS STAND, TAHARABAD.

NAME Of WORK Detailed Estimate for installation of "WEIGHBRIDGE"
Capacity Of 100 MT.
in Gat No. 548/2/2/A , Kaavthe,
Tal. Sakri, Dist. Dhule.

CLIENT NAME : PANZRAKAAN FARMERS PRODUCER Co. Ltd. BHADNE

ABSTRACT SHEET

Item No.	Particulars	Qty.	Rate	Unit	Amount
1)	End to end Assembly of weighing bridge	01	12,00,000.00	01	12,00,000.00
a)	Weighing bridge plateform of wileded structure, minimum 10 mm thickness having size of 9x3 sq.mt area double coated with zinc chromate base red oxide and painted by black colour with yellow strips, it should have free				




A.S.H.



	floating mounting assembly.				
b)	Double ended sheer beam type of IP 68 standards compatible with capable of calibrating same weight at all corners.				
c)	Intelligent terminal indicators having additional facility of email and SMS reports with extra jumbo display 2x3 inch.				

d)	Civil work (Foundations, cabin 10x10 sqft bricks cement plastered with coated galvanized iron sheet on the top), earthing pits, ramps and piping as per the drawing)	100.0 SQFT		LUMPSUM	3,00,000.00
e)	Crane for unloading the platform and erecting the same on the foundations				





f)	Printer (80 column dot matrix or similar configurations)				
g)	Transportations				
f)	Government stamping/Calibration Certificate				
				Say	1500000.00
					1500000.00

In words :- Fifteen Lakhs Rupees Only.....

Authorised & Estimated By

Er. Amit S. Hire (B.E. Civil)



1. Mr. Snashikant Hire
B.E. CIVIL



AA
1000000000