

Durwa Projects Pvt. Ltd.



Ref: DPPL/23
Date: 23.08.2022

Jijaau Cultivator Producer Company Ltd.
At Post : Chausala,
Ta : Anjangaon Surji
Dist.: Amravati

Shri. Akshay Surendra Kalmegh (Director)
Mobile : 83080 65414

Sub: Offer for the Supply and installation of Cold Storage Capacity 30MT .

Dear Sir,

This has reference to the above subject, we are pleased to offer you for the supply, and installation, testing and commissioning of Cold Storage of capacity 30 MT.

Our offer comprises of the following Annexures:

- Annexure - I : Basis of Design for Cold Rooms Capacity 30 MT - 1 Nos.
- Annexure - II : Price Schedule & bill of quantity
- Annexure - III : Exclusion of Contract
- Annexure - IV : Terms & Conditions of Contract

We hope that our offer will meet with your requirement and we now look forward to the pleasure of receiving your valued order.

Thanking you and assuring you of our best services at all times.

Very Truly Yours,
For Durwa Projects Pvt. Ltd.

Nitin Rewatkar
Mobile : 98222 03259

Encl : Annexure - I, II, III & IV

ANNEXURE-3

Details of equipment: Cold Storage Capacity 40 MT. - 3 Nos.

Sr. No	Description	Specs/Remarks
1	Dimensions all materials in mm Length / breadth / height	15000 / 5000 / 3200 (mm) 22000 / 10000 / 10000 (mm)
2	Total pressure carrying capacity	10000
3	Size of floor	5000
4	Ambient Temperature	45°C
5	Room Temperature	10°C to 15°C
7	Insulation to be used	Polystyrene & high density polyurethane
8	Size of floor	5000 x 5000
9	Pressure measuring temperature	10°C
10	Door openings per floor	2 Nos.
11	Insulation	Insulation material to be specified. Make Blue Star
12	Thickness of insulation	50 mm to be specified accordingly
13	Lamination of panels	2000 inside and outside.
14	Floor insulation	2000 thick 50 mm
15	Floor Finish	P.S. & tiles in Commercial & Garage
16	Door Details	Flush Type self-closing swing Door. 50 mm thick. Size 40' x 70' Door opening Hinged Type
17	Refrigeration systems	R404A Split type & Air Cooled Make Blue Star
18	No. of refrigeration systems	1 Nos. 40 MT Split Unit. 10.72kw
20	Compressor Type	Scroll
21	Power Supply Requirement	415 Volts 3 Ph / 50 Hz
22	Internal Lighting	Provide
23	Temperature Indicator	Digital temperature indicator cum controller

Annexure – II

Price Schedule : Cold Storage Capacity 30 MT - 1 Nos

S.No	Description	U/M	QTY	Price
1	Supply of 60MM thick Puff Panels with 1 Nos Door and 1 Nos refrigeration units for 1 Nos. Cold Room of 30MT Capacity Chamber as per Annexure I	1	lot	10,50,000.00
2	Copper piping & electrical cable of required capacity			
3	Installation, Testing and Commissioning charges	1	Lot	2,21,186.00
	Sub Total			12,71,186.00
	GST 18%			2,28,814.00
	Grand Total Supply & Installation			15,00,000.00

Total Amount for Cold Storage including GST and Transportation Rs.15,00,000.00

Terms:-

1. Taxes : GST 18%. Included
2. Transportation : Included
3. Payment Terms
 - 3a. Supply of Machines 50% advance along with the order, balance 50 % against intimation/prior dispatch
 - 3b. Installation 50% advance , 25% after installation before commissioning, 25% after testing and trail run.
4. Piping length is estimated at 20 feet, for piping length longer than 30 feet, price will be charged extra @ Rs.1100/- per running foot per machine.
5. Delivery Time: 4 weeks on received of advance.
6. Installation : 2 Week
7. Offer Validity : 30 Days
8. MS stand for ODU will be in Customer scope.
9. Electrical work in your Scope. Supply upto the outdoor condensing unit.

For, Durwa Projects Pvt. Ltd