



Choudhari Light House & Generators

Lighting Decoration

चौधरी लाईट हाऊस अँड जनरेटर्स

Bohra Masjid, Sarafa Bazar, Amravati .(R) 2570753, (Mob.) 9370653953, 9422156611

GST NO-27ADCPC1988N2Z6

Ref:30082022

Date: 30/08/2022

To,
Krishipreneurs Farmer Producer Company Limited,


Kind Attn:

Re: Offer for Greaves 62.5 kva DG set with AMF Panel.

Sir,
As per the discussion we are submitting the offer as follows:

Sno	Description	Qty	Rate
01	Greaves GPWII-PII-62.5 KVA Powered by Greaves Engine Model 3G11TAG25. KW/BHP 80.1 @ 1500rpm ISO 3046 / BS 5514 Coupled with Alternator: Meccalte / (Optional - Stamford/ Crompton Greaves/equivalent) -brushless alternator - Self-excited, self-regulated - Class 'H' insulation limited to temperature rise of class H - Salient pole revolving field - Single bearing - Automatic voltage regulator Branded Alternator Acoustic enclosure – Engine alternator assembly mounted on AVM with Silencer and S.S exhaust bellow suitably optimized to meet stringent sound emission standards as laid down by MOEF / CPCB - Base rail with draw-out type fuel tank is provided with a drain plug, air Vent, inlet and outlet connections, level indicator, manhole etc. - Sub-base fuel tank with 13 hours capacity at 75% load.	01set	7,95,886.00





Choudhari Light House & Generators

Lighting Decoration

चौधरी लाईट हाऊस अँड जनरेटर्स


Bohra Masjid, Sarafa Bazar, Amravati .(R) 2570753, (Mob.) 9370653953, 9422156611

GST NO-27ADCPC1988N2Z6

	<ul style="list-style-type: none">- 12V dry, batteries with connecting leads and terminals-90% gloss RAL9003 white pure polyester powder coated, base in black colour.Control panel: RAL 9003 White Powder coated control panel manufactured with CRCA sheet , Control Panel is having following features:-Water and lube oil drain outlets located on the outer surface- Leading to ease of maintenance and cleanliness.- MCCB of suitable rating with short circuit protection- Controller which displays voltage, current, KW, PF, Frequency, KWh.- Indicating lamps for "Load On" and "Set Running"- Current transformers of suitable ratings.- Copper Cables of suitable capacity with incoming and Outgoing terminations- Control fuses duly wired and ferruled panel inside the canopy.		

Terms & Conditions

1. Prices: The prices quoted are FOR Site.
2. Taxes: The above rates INCLUSIVE of GST @ 18 %.
3. Unloading additional to customer account
4. PAYMENT: 100% ADVANCE ALONG WITH ORDER
5. DELIVERY: WITHIN 4-6 WEEKS FROM DATE OF RECEIPT OF FIRM ORDER AND PAYMENT
5. WARRANTY: As per the OEM Norms 5000hrs or 02 years whichever is earlier.
6. VALIDITY: 30 DAY



Thanking You
Yours Faithfully For
Choudhari Light
House & Generators
Authorised Signatory

