

5

INTERNAL BITUMINOUS ROAD**SHREE AGRO INDUSTRIES (PROP.MR.SAGAR UTTAM GHORPADE)**

SHREE AGRO KRUSHI FARMERS PRODUCER COMPANY LTD.

GAT NO 216/B/1,DAHIWADI,TAL-MAN,DIST-SATARA 415508

Sr. No.	Description	Quantity	Unit	Rate	Amount
1	Providing, laying, spreading & compacting stone aggregate of specific sizes to WBM specification with intelligent compactor - by mechanical Means - Grading II - using screening type B	153.000	cu.m	1953.60	298900.80
2	providing & constructing 50mm thick M.P.M Road surface Including picking of existing WBM surface.	1500.000	Sq.m	152.75	229125.00
3	P/L/R of O.G.C 20 mm th. including seal coat & tack coat @ 3 kg/10 sqm - bulk asphalt 60/70 . With SCADA, Paver & vibratory roller.	1500.000	sq.m	141.05	211575.00
4	supplying Hard murum/ kankar at the road site , including conveying and stacking etc . complete.	200	cu.m	489.20	97840.00

5	Spreading H.M at road site , including conveying & stacking, etc.complete.	200	Cu.m	50.90	10180.00
6	Compaction HM side widths layers with power roller	730.00	Sq.m	10.40	7592.00
7	Laboratory testing charges for various materials required fot items of work.	2.000	one job	23400.00	46800.00
8	Royalty charges For various materials. 1.Qnty of metal 40mm&above. 2.Qnty of Hard murum .	205.240	Cu.m	141.34	29008.62
9	P/L C.C pipe I.S.N.P -2 Class of 600 mm dia.	10.000	R.M	2200.00	22000.00
Total Amount Rs					953021.42
Say					9,53,000/-

In Words- Rupees Nine Lakh Fifty Three Thousands Only

SHREE AGRO INDUSTRIES
(PROP.MR.SAGAR UTTAM GHORPADE)

SIGN OF
ENGINEER

Vishal
15/03/23
for Bank purpose
Er.VISHAL S.GHORPADE
Civil Engineer & Govt.Contractors
A/p.Dahiwadi Tal.Man,Dist.Satara
PWD.Reg.No.69/2017/2018
Mo.9421144411/943144411