

DHOPESHWAR & SONS

ISO 9001-2015 Company

A-16, Cooperative Industrial Estate, Balanagar, Hyderabad 500 037, INDIA

 TEL :+ 91 40 2377 1579, FAX :+91-40 2377 2450, Email : sales@dhopeshwar.in, Web : www.dhopeshwar.in

GSTN : 36AETPD7840L1ZX / IEC No. 0908011237

NARDUS Aromatics Oil Producer Co. Ltd

Kranja Lad, Washim, Maharastra 444 105

[Email : ceonardus@gmail.com](mailto:ceonardus@gmail.com)

Mobile : Mr. Kuldip Khadse 8010654109

OFFER

12.11.2021

10 MT
with IBR Boiler
Essential oil Distillation plant - 10 MT
**Stainless
steel Model**

For Distillation of GERANIUM, Other grasses

per batch

Bio-Mass Capacity in 1 Vessel = 1 Batch. Time 4 hrs

10 MT

Bio-Mass Capacity in 2 Vessels = Plant cap.= 2 T / shift

Basic Set 1-8, Auxilliaries 9-12.

1	Distillation Vessels in SS 304 - DV -All in SS 304, Shell 2.5mm/ bottom 3 mm + re-inforcement/	2	With 2" Insulation for 2 DV Shells only	In SS304
2	Conical Top Cover in SS 304 in 1.2 mm	1		In SS304
3	Vapour pipe/ Goose neck in SS 304 in 1.2 mm+Jacket	1		In SS304
4	Stainless Steel Tubes Condenser with SS 304 Tubes -All contact parts - 1" OD tubes, Tube plate & ends in SS304	1		In SS304
5	Oil & Water Separator in SS 304	1		In SS304
6	Pipe lines & Valves - set- In CI or Brass	1		GI, MS
7	Perforated Cages for loading raw material - SS	4		In SS304
8	Water Boiler - IBR -ALL MS, Furnace shell 8 mm, Outer 6 mm, Tubes 40 mm C Class	1	Insulation for MAIN - BODY	In MS
Total Lumpsum Price for Basic set		1-8		6,210,000
9	Channel Base frame + Lifting Structure - 1 Set in MS	1		430,000
10	Trolley + Chain block for Cages - 1 Set	1		160,000
11	Cooling Tower (in FRP With Pump & GI Piping)	1		200,000
P	Lumpsum BASIC Price for above			7,000,000

Forwarding+ Rockwool 2" Insu.+ Aluminium cover sheet for 2 DV

140,000

Erection & Commissioning : Additional

70,000

P1 Lumpsum BASIC Price with Erection & Commissioning
7,200,000

GST 18%

1,296,000

Transport - Lumpsum

LS

104,000

P2 TOTAL LUMP SUM PRICE - ALL INCLUSIVE
Each Unit 8,600,000
Terms & Condition of Supply : See ANNEX 1 attached
TOTAL UNITS 8,600,000

Delivery : 8 to 12 Weeks for 1 Unit. 4 -5 Months for 5

For DHOPESHWAR & SONS

Payment : 1. Advance - 50%, Balance at time of delivery

Essential oil Distillation plant - 10 MT batch with NON-IBR wood fired Boiler



Un-loading structure with moving trolley and Chain block

General Arrangement- 250 kg



**2 + 2
4 Vessel system Arrangement**



Essential oil Distillation plant - 1 T / batch - Some more photos



Photos from
KHOT AROMATICS
1 Ton per batch Plant
Pusesavali, Satara
Maharashtra



- Best Yield of Oil**
- Best quality of Oil**
- Low wood consumption**
- Low batch time**
- Best performance**
- Best service support**
- Quality Engineering**
- backed by 5 decades**
- engineering experience**



Shot on vivo S1
AI Triple Camera

2021.10.31 00:45