



माहेला अर्थिक विकास महामंडळ

(महाराष्ट्र शासन अंगीकृत) जि. ठाणे

तेजस्विनी महाराष्ट्र ग्रामिण महिला सक्षमीकरण कार्यक्रम
अंतर्गत

समृद्धी लोकसंचलित साधन केंद्र, शहापूर



एकजुटीतून अवतरेल
समृद्धीची नवप्रभा
माविम

रजि. नं. महा/1091/11/ ठाणे

o/c

पत्ता: रुम नं. ११, ए-विंग, साई प्रेरणा अपार्टमेंट, ग्रा.पं.कळभेच्या बाजुला कळभे ता. शहापूर, जि.ठाणे.

जा. क्र. प्रती, स।लो।सा।के।जा.क्र. ५३५

दिनांक - १/१२/२०२१

श्री. राकेश विष्णू शिर्के

राकेश कन्स्ट्रक्शन, मु. नारायणगाव

पो. मलेगाव, तालुका शहापूर जिल्हा- ठाणे

महोदय,

आपणास कळविण्यात येते की, उपरोक्त आदेशानुसार सोबत दिलेल्या अटी व शर्तीनुसार कार्यारंभ करावे.

प्रत- मा.नोडल अधिकारी, प्रकल्प अंमलबजावणी कक्ष माविम मुंबई यांना माहितीस्तव सविनय सादर.

पुरवठा आदेशाच्या अटी व शर्ती :-

- 1) बंधपत्रात दिलेल्या नियम व अटीचे अधीन राहून कामकाज करणे बंधनकारक असेल.
- 2) देयक:- विहित टप्प्यात कामकाज केल्यानंतर 2 प्रतीत देयके सादर करावी. तसेच देयक सादर केल्यानंतर 30 दिवसामध्ये देय रक्कम अदा केली जाईल.
- 3) देयकातून नियमानुसार TDS कपात करण्यात येईल.
- 4) निविदा मागणी पत्रकातील सर्व अटी व शर्ती लागू राहतील.
- 5) निविदा प्रक्रियेत नमूद मानकाचे कामानुसारच कामकाज अपेक्षित असून MB रिपोर्ट नंतरच खात्री करून देयक अदा केले जाईल. MB रिपोर्ट शिवाय देयक स्वीकारले अथवा अदा केले जाणार नाही

५२२५६३९१११

Rakesh Vishnu Shirke

PROPRIETOR

Proprietor

कविता यशवंत धामणे

अध्यक्ष सचिव व्यवस्थापक
समृद्धी लोकसंचलित साधन केंद्र (स्मार्ट)
ता. शहापूर, जि.ठाणे.

स्वाक्षरी

कविता यशवंत धामणे
अध्यक्ष

संपादन समती

महिला अर्थिक विकास महामंडळ

(महाराष्ट्र शासन अंगीकृत) जि. ठाणे

तेजस्विनी महाराष्ट्र ग्रामिण महिला सक्षमीकरण कार्यक्रम
अंतर्गत

समृद्धी लोकसंचलित साधन केंद्र, शहापूर



रजि. नं. महा/1091/11/ ठाणे

पत्ता: रुम नं. ११, ए-विंग, साई प्रेरणा अपार्टमेंट, ग्रा.पं.कळभेच्या बाजुला कळभे ता. शहापूर, जि.ठाणे.

जा. क्र. स/लो/सा/कें/जा.क्र. 434

दिनांक - १ / 12 / 2021

वाचा:

- नोडल अधिकारी प्रकल्प अंमलबजावणी कक्ष यांचे उपप्रकल्प मंजूरी आदेश जा.क्रं स्मार्ट/माविम/पीआययु/वर्ष/०९ दि.२७/०५/२०२०
- समुदाय आधारित संस्थेचा बांधकाम निविदा प्रसिद्ध करणेबाबतचा ठराव क्रं १ व दि ६/७/२०२१
- या संस्थेचे निविदा दैनिक पुढारी ठाणे आवृत्ती वर्तमानपत्र प्रसिद्धी दि १५/१०/२०२१
- आपण सादर केलेले दरपत्रक दिनांक २८/१०/२०२१
- समुदाय आधारित संस्थेचा पुरवठा आदेश निर्गमित करणेबाबतचा ठराव क्रं २ व दि २१/११/२०२१-

कार्यारंभ आदेश

संदर्भ क्रं १ अन्वये मा. नोडल अधिकारी, प्रकल्प अंमलबजावणी कक्ष माविम, मुंबई यांनी उपप्रकल्प अंमलबजावणीसाठी मंजूरी दिलेली आहे. सदर उपप्रकल्पाच्या यशस्वी अंमलबजावणीसाठी आवश्यक बांधकाम करण्याबाबत **Proposed Construction work for collection centre** साठी संदर्भ क्रं २ नुसार ठराव मंजूर करण्यात आलेला आहे. त्यानुसार संदर्भ क्रं ३ अन्वये वर्तमान पत्रात जाहिरात देऊन स्पर्धात्मक निविदा मागविण्यात आल्या होत्या. संदर्भ क्रं ४ नुसार आपण सादर केलेल्या निविडे मधील दर हे न्यूनतम असल्याची खरेदी समितीची खात्री झाली आहे आहेत. सदर खरेदी प्रक्रिया रु. 50,000 पेक्षा जास्त असल्याने संपादन समितीने संदर्भ क्रं ५ च्या ठरावानुसार कार्यारंभ आदेश देण्यास मान्यता दिलेली आहे.

संदर्भ क्रं १ ते ५ च्या अधीन राहून आपणास खालील प्रमाणे आपण सादर केलेल्या दरपत्रकानुसार कार्याआदेश देण्यात येत आहे.




अ क्र.	वस्तूचे नाव	वस्तूचे मापदंड /विवरण (specification)	एकूण नग	दर प्रति नग	एकूण रक्कम	अक्षरी
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means....(INo21-02, PgNo 197) (STATE SSR) Item Spec: (Bd.A.1 Page No. 259)	cum	90.00	191.00	17190.00	सतरा हजार एकशे नव्वद
2	Excavation for foundation in hard murum including removing the excavated material upto distance of 50 metres beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.50 m) By Mechanical Mean.(INo 21-06, PgNo 197) (STATE SSR) Item Spec: (Bd.A.2 Page No. 259)	Cum	42.00	241.00	10122.00	दहा हजार एकशे बावीस
3	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granitel quartzitel gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)....(INo24-01, PgNo 226) (STATE SSR) Item Spec: (Bd. E. 1 Page No. 287)	CUM	89.00	6650.00	591850	पाच लाख एकव्याण्णव हजार आठशे पन्नास
4	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering, formwork ,cover blocks, laying/pumping, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc	CUM	10.37	7600.00	78812.00	आठ्यातर हजार आठशे बारा
5	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks compacting and roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	CUM	15.00	14500.00	217500.00	दोन लाख सतरा हजार पाचशे

6	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap/ granite /quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc).... (INo25-50, PgNo 234) (STATE SSR) Item Spec: (Bd.F.6 Page No. 300 and B.7, Page No.38)	CUM	20.00	13600.00	272000.00	दोन लाख बहात्तर हजार
7	Providing and casting in situ cement concrete M20 of trap/Granite / quartzite/ gneiss metal for R.C.C. slabs and landings canopy as per detailed designs and drawings including centering, formwork, cover blocks compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete,(Excluding reinforcement and structural steel).With fully automatic micro processor based PLC with SCADA enabled reversible drum type concrete mixer With natural sand.Bd.F.8 Page No.302 and B.7,Page No.38	CUM	1.00	15590.00	15590.00	पंधरा हजार पाचशे नव्वद
8	Providing and laying in situ cement concrete M-20 with tremix treatment for 100 mm thickness for flooring with groove cutting of 4 mm wide and 20 mm deep with necessary refilling with bitumen etc. complete.SSR 2019-20 Item No. 33.30.	SQM	173.84	1150.00	199916.00	एक लाख नव्यानव हजार नाउशेसोळा
9	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels, parapets, copings, fins, arches etc. as per detailed designs, drawings and schedules, including cutting, bending, hooking the bass, binding with wires or tack welding and supporting as required complete (INo26-33, PgNo 245) (STATE SSR) Item Spec: (Bd.F.17, Page No. 306)	MT	5.53	87000.00	481110.00	चार लाख एक्याऐशी एकशे दहा
10	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.	CUM	13.00	8400.00	109200.00	एक लाख नऊहजार दोनशे
11	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. CompleteBd.G.5 Page No.315	CUM	70.00	8380.00	586600.00	पाच लाख श्याऐशी हजार सहाशे
12	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15cm, to 20cm, including watering and compaction etc. complete.....(INo21-37, PgNo 201) (STATE SSR) Item Spec. (Bd. A.11 Page No. 283)	CUM	61.00	610.00	37210.00	सदोतीस हजार दोनशे दहा
13	Providing soling using 80 mm size trap metal in 15 cm. layer including filling voids with Crushed sand/grit, ramming, watering etc. Complete	CUM	91.00	1400.00	127400.00	एक लाख सत्तावीस हजार चारशे
14	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete....(INo32-04. PgNo 268) (STATE SSR) Item Spec: (Bd. L.2 Page No. 368)	SQM	252.00	280.00	70560.00	सत्तर हजार पाचशे साठ




15	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.....(INo32-11, PgNo 269) (STATE SSR) Item Spec: (Bd.L.7 Page No. 369)	SQM	339.00	625.00	211875.00	दोन लाख आकरा हजार आठशे पंच्याहत्तर
16	Providing & applying washable oil-bound distemper of approved colour and shade to old & new surfaces in two coats including scaffolding, preparing the surfaces. (excluding the primer coat.) etc. complete.....(INo36-11, PgNo 291) (STATE SSR) Item Spec: (Bd.P.5 Page No. 413)	SQM	252.00	45.00	11340.00	आकरा हजार तीनशे चाळीस
17	Providing and applying three coats of water proof cement point of approved manufacture and of approved colour to oldplastered surfaces including scaffolding if necessary, cleaning and preparing the surface, watering for two days etc. complete.Spec.No.: Bd.O.8/Page No.406	SQM	339.00	107.00	36273.00	छत्तीस हजार दोनशे त्र्याहत्तर
18	Providing and fabricating structural steel work in rolled sections like joists, channels, angles, tees etc. as per detailed design and drawings or as directed including cutting, fabricating, hoisting, erecting, fixing in position making riveted / bolted /welded connections without connecting plates, braces etc. and including one coat of anticorrosive paint and over it two coats of oil painting of approved quality andshade etc. complete.	MT	4.10	94000.00	385400.00	तीन लाख पंच्याऐशी हजार चारशे
19	Providing and fixing colour coated Zinalume (R) AZ150 (min 150 gms/sq.mt. Total on each side) profiled sheets for roofing. The feed material is manufactured out of nominal 0.45 mm Base Metal Thickness (BMT) (0.5 mm TCT), Hi-strength steel with min.550 Mpa yield strength, metallic hot dip coated with Aluminium-Zinc alloy (55% aluminium 43.4% zinc 1.6% silicon) vath COLORBOND (R) steel quality with thickness of nominal 35 um, comprising of nominal 25 um exterior coat on top surface and nominal 10 coat on back surface. Profile sheet shall have nom. 950-1050 mm width and nominal 25-30 mm deep ribs with subtle square fluting in shall be designed for anti-capillary groove. & return leg. The feed material should have coil manufacturers product details marked a regular interval. Including fasteners with min. Fastened with min. 25 um Zinc-Tin alloy coated, Hex head, self-drilling screw etc. Complete. (weight of profile 4.52 kg/sqm)....(INo38-34 , PgNo 302) (STATE SSR) Item Spec: (As directed by Engineer in charge.)	SQM	197.00	1506.00	296682.00	दोन लाख श्याणव हजार सहाशे ब्याऐशी
20	Providing and fixing of colour coated Zinaluminium R) AZ150 (min 150 gms/sq.mt. Total on each side) profiled sheets for roofing. The feed material is manufactured out of nominal 0.45 mm Base Metal Thickness (BMT) (0.5 mm TCT), Hi-strength steel with min.550 Mpa yield strength, metallic hot dip coated with Aluminium-Zinc alloy (55% aluminium 43.4% zinc 1.6% silicon) with COLORBOND (R) steel quality super durable polyster paint coat (with inorganic pigment). The paint shall have a total coating thickness of nominal 35 mm, comprising of nominal 25mm exterior coat on top surface and nominal 10 um reverse coat on back surface. Profile sheet shall have nom. 950-1050 mm effective cover width and nominal 25-30 mm deep ribs with sublet square fluting in the five pan at nominal 180-250 mmcenter-to-center. The end rib shall be designed for anti-capacity groove. & return leg. The feed material should have coil manufacturers product details marked a regular interval. Including fasteners with min. Fastened with min. 25 um Zinc-Tin alloy coated, Hex head, self-drilling screw etc. Complete. (weight of profile 4.52 kg/sqm) 301 mm to 600 mm girth (Surface Width)....(INo38-35 PgNo 303) (STATE SSR	SQM	7.00	1100.00	7700.00	सात हजार सातशे



21	<p>Providing and fixing rolling shutter fabricated from steel laths of minimum thickness 0.9 mm with lock plate of 3.15 mm thickness reinforced with 35 x 35 x 5 mm angle section fitted with Sliding bolts and handles for both sides, deep M. S. channel section of respectively with hold fast arrangements, M.S. Bracket plate 300 x 300 x 3.15 mm minimum size and shape with square bar, suspension shaft of minimum 32 mm diameter, hood cover of M.S. sheet not less than 0.9 mm thickness and of any size at top and safety devices including mechanical gear operation arrangement consisting of worm gear wheels and worms of high grade cast iron or mild steel and one coat of red lead primer etc. complete. (I.S. 6248-1979) (Without mechanical gear)...(INo39-24 , PgNo 318) (STATE SSR) Item Spec: (Bd.T.55, Page No. 510)</p>	SQM	24.00	5100.00	122400.00	एक लाख बावीस हजार चारशे
22	<p>Providing and fixing steel ventilator fully glazed partly fixed as per detailed drawing without hot dip zinc coating including fabricating glazing with plain / obscured glass panes and approved type and quality and iron oxidized fixtures and fastening oil paint 2 coats etc. complete. Bd. T. 53, Page No. 509 & As directed by Engineer in charge.</p>	SQM	11.00	3200.00	35200.00	पस्तीस हजार दोनशे
23	<p>Supplying & erecting mains with 2x1.5 sq.mm. and earth wire 1.5 sq.mm FRLSH PVC copper wire, in HMS PVC conduit min. 20mm dia .CSR 2019-20 Item No 1-6-2 Additional specification No: WG-MA/PC.</p>	Each	15.00	110.00	1650.00	एक हजार सहाशे पन्नास
24	<p>Supplying & erecting mains with 2x2.5 sq.mm. and earth wire 1.5 sq.mm FRLSH PVC copper wire in HMS PVC conduit min. 20mm dia. CSR 2019-20 Item No 1-6-4 Additional specification No: WG-MA/PC.</p>	Rmt	20.00	128.00	2560.00	दोन हजार पाचशे साठ
25	<p>Supplying & erecting mains with 2x4 sq.mm. and earth wire 2.5 sq.mm FRLSH PVC copper wire in HMS PVC conduit min. 20mm dia, CSR 2019-20 Item No 1-6-6 Additional specification No: WG-MA/PC.</p>	Rmt	7.00	155.00	1085.00	एक हजार पंच्याऐशी
26	<p>Supplying and erecting Ceiling rose / Batten holder / Slanting holder / hanging cord switch / hanging bell push / pendent holder bakelite base 6A. erected on filled polypropylene board or polished double wooden block/ PVC junction box. CSR2019-20 Item No 1-7-7</p>	Each	5.00	32.00	160.00	एकशे साठ
27	<p>Supplying and erecting triple pole and neutral distribution board (TPNDB) surface/ flush mounted suitable for SPMCB of 12 ways on iron / GI frame (horizontal busbar type) CSR2019-20 Item No 5-4-1 Additional specification no. SW-SWR/MCBDB</p>	Each	2.00	1660.00	3320.00	तीन हजार तीनशे वीस
28	<p>Supplying, erecting & marking FPMCB 40A to 63A in provided distribution board. CSR 2019-20 Item No 5-3-17 Additional specification No. SW-SWR/MCB</p>	Each	2.00	1232.00	2464.00	दोन हजार चारशे चौसष्ट
29	<p>Supplying, erecting & marking DPMCB 6 A to 32 A B- series (for lighting) in provided distribution board. CSR 2019-20 Item No 5-3-7 Additional specification No. SWSWR/ MCB</p>	Each	4.00	434.00	1736.00	एक हजार सातशे छत्तीस
30	<p>Supplying & erecting conventional spike Providing earthing with galvanized iron earth plate size 60 x 60 x 0.6 cm with funnel with a wire mesh for watering and brick masonry block C.I. cover complete with all materials, testing & recording the results. CSR 2019-20 Item No 9-1-3 Additional specification No. EA-EP</p>	Each	3.00	5110.00	15330.00	पंधरा हजार तीनशे तीस

31	Supplying, erecting & terminating XLPE armoured cable 4 core 25 sq. mm. aluminium conductor with continuous 5.48 sq. mm. (12 SWG) G.I. earth wire complete erected with glands & lugs, on wall/ trusses/pole or laid in provided trench/ pipe. CSR 2019-20 Item NO 7-1-30 Additional specification No CB-LT/AL	Rmt	7.00	222.00	1554.00	एक हजार पाचशे चौपन्न
32	Supplying and laying (including excavation of suitable width & depth up to 90 cm) 75 mm outside dia. double wall corrugated pipes(DWC) of HDPE for enclosing cable below ground/road surface, to required depth complete.CSR 2019-20 Item No 7-6-10	Rmt	5.00	205.00	1025.00	एक हजार पंचवीस
33	Supplying & erecting Siemens type brass cable glands for 4 core 35 sq. mm./3 core 50 sq. mm. for XLPE armoured cable. CSR 2019-20 Item No 7-7-4 Additional specification No. CB-GL	Each	3.00	79.00	237.00	दोनशे सदोतीस
34	Supplying & erecting crimping type copper lugs for cable 25 sq. mm. complete. CSR 2019-20 Item No 7-9-2 Additional specification No. CB-CL/CU	Each	3.00	23.00	69.00	एकोणसत्तर
35	Supplying and erecting single pole and neutral distribution board (SPNDB) surface/flush mounted with 2 ways for incoming and 2 ways for outgoing SPMCBs on iron/ GI frame. CSR 2019-20 Item No 5-4-14 Additional specification No. SW-SWR/MCBDB	Each	3.00	126.00	378.00	तीनशे आठहत्तर
36	Supplying and erecting LED Street light fitting suitable for above 40W to 48W lamp, including lamp, with PF > 0.95 class IP 65 and above housing of pressure die cast aluminium alloy and heat sink extruded aluminium complete .CSR 2019-20 Item No 2-5-4 Additional specification No . FGODF/ FLS2.	Each	5.00	3457.00	17285.00	सतरा हजार दोनशे पंच्याऐशी
37	Supplying and erecting Street light bracket made from 40 mm. dia 'B' class G.I. Pipe, 0.6m. in length along with pole cap of 300 mm length and 80 mm dia duly welded with provided leads. CSR 2019-20 Item No 2-9-2 Additional specification No. FG-BKT/BPC	Each	2.00	591.00	1182.00	एक हजार एकशे ब्याऐशी
38	Providing and fixing lioghtening conductor system comprising of erecting Air-Termination consisting of tubular copper rod of 25mm dia. 1.2 mm thick with multiple points head 1.2 mt. long (Heavy Duty) welded or clamped to G.I. pipe pole B grade 50 mm diaof required length with M.S. round bnase plate 25 Cm diam and 10mm thick at bottom embeded in cement concrete 1:3:6 dfoundation of size 45 cm diam x 45 cm Height and providing earthing with copper earth plate of size 60 x 60 x 0.3 cms with cadmium plated nut bolts to fix earthing strip burried in specially prepared earth pits 1.5 metre below ground level with 40 kg charcoal and salt with alternate layers of charcoal and salt and G.I.pipe 40mm dia 2 meter length burried in earthe upto earthing plate remining portion above ground level for watering and refilling compete Note- Copper strip from lightning conductor is not considered in this item. CSR 2020-21 Item No 44.18 Additional Spec No:BDW 1 pAGE No 581	Nos	1.00	22186.00	22186.00	बावीस हजार एकशे श्याऐशी



39	Providing and fixing copper strip 25mm wide and 3mm thick for lightning conductor including fixing with screws required scaffolding etc. complete Note- Lightning conductor and earthing pits is not considered in this item. CSR 2019-20 Item No 44.19 Additional Spec No :BDW 1 Page No 581 & As directed by Engineer in Charge	Rmt	2.00	265.00	530.00	पाचशे तीस
40	Cement -Fineness, Standard Consistency, Setting Time (Initial & Final), Compressive strength, Soundness	No	1.00	3770.00	3770.00	तीन हजार
41	Concrete M-10 grade-i)Concrete cube compressive strength (Set of 3 Cubes)	No	6.00	690.00	4140.00	सातशे सत्तर
42	Concrete M-20 gradei)Mix Design with all tests on basic materials	No	1.00	13755.00	13755.00	चार हजार एकशे चाळीस
43	ii)Concrete cube compressive strength (Set of 3 Cubes)	No	7.	690.00	4830	तेरा हजार सातशे
44	Crushed metal for concrete-i)Water absorption, Specific gravity,Impact value,Crushing value	No	1.00.	1380.00	1380.00	पंचावन्न
45	Bricks-Crushing value, Water absorbaton, & Specific Gravity	No	2.00	2175.00	4350.00	चार हजार आठशे तीस
46	TMT steel bars-Tensile strength ,Yield stress, ultimate tensile stress, %elongation, weight per running meter,Bend/Rebend test.(Set of 3 Bars)	No	1.00	3875.00	3875.00	एक हजार तीनशे ऐशी
47	Sand-Fineness Modulus, silt & clay content.	No	1.00	1380.00	1380.00	चार हजार तीनशे पन्नास
48	Murum in plinth-i)Plasticity Index	No	1.00	1170.00	1170.00	तीन हजार आठशे
49	ii) Field Density of compacted layer	No	1.00	1860.00	1860.00	पंचाहत्तर
50	Royalty Charges	CUM	366.26			एक हजार तीनशे ऐशी
51	Management Strategies and Implementation Plan (MSIP) to manage the Environmental, Social, Health and Safety (ESHS) risks and ESHS Code of Conduct	Lum Sum		60000.00	60000.00	एक हजार एकशे सत्तर
					एकूण रक्कम (GST तथा सर्व कर सहित)	4095191.00
अक्षरी - चाळीस लाख पंचाण्णव हजार एकशे एक्याण्णव हजार मात्र						

उपरोक्त कार्यारंभ आदेश सोबत जोडलेल्या अटी व शर्तीच्या आधीन राहून करावा.

सोबत:- अटी व शर्ती प्रपत्र

का.ता. शिवाळे

अध्यक्ष सचिव व्यवस्थापक
समृद्धी लोकसंचलित साधन केंद्र(स्मार्ट)
तां. शहापूर, जि.ठाणे.

स्वाक्षरी

का.वि.ता. चशवंत-थानगे
अध्यक्ष

संपादन समती