

# SHRI KRISHNA SALES

Uti Solar System ,Jantre Complex,Dhoki Road kalamb-  
413507 Mo.9881630001

REFNO:

DATE : 20-12-2022

To,  
Ganrajya Agro Producer Company Ltd.Khamgaon  
Ta.& Dist. Osmanabad.

## SUBJECT : QUOTATION FOR ON-GRID SOLARPV SYSTEM -(60 KW)

Respected Sir,

Referring to the said subject and all previous discussions on your requirement we here with submitting our proposal for the required system of 10KW 180VDC off grid solar.

### 1. BOQ (BILL OFFQUANTIITES)

Sr. No.	Description	Qty	Units	Amount	GST	Total
A	Supply of New Material					
1	335 Wp Polycrystalline Solar PV Panel	180	Nos			
	Make-UTL,Waaree,Vikram					
2	60 KW 1-1 MPPT Solar Inverter	1	Nos	3420000	410400	3830400
	Make-UTL				@12%	
3	12 V 150 Ah C-10 Tubular Battery	-	Nos			
	Make-UTL Warranty (36+24) Months					
B	Control and Structure					
1	Array Junction Box With DC DB.	1	Nos			
2	Input/Out Put Control DB	1	Nos			
4	Solar Structure					
	MS+ GI Structure	1	Nos			
5	Lighting Arrester With Earthing					
	10 Mtr Radius Solid LA	1	Nos			
6	AC Earthing	1				
7	DC Earthing	1				
8	Delivery and Installation	1	Nos			
					Total	3830400

### 2. Earthing:

- I. AC Earthing: 17.2 MM 1 MTR COPPER BANDED CHEMICAL EARTHING, With 1.5 Sq. MM Single Core Multistand Copper Wire for AC Earthing.
- II. DC Earthing: 17.2 MM 1 MTR COPPER BANDED CHEMICAL EARTHING, With 2.5 Sq. MM Single Core Multistand Copper Wire for DC Earthing.
- III. LA Earthing: 17.2 MM 1 MTR COPPER BANDED CHEMICAL EARTHING, with 4 Sq. MM Single Core Multistand Copper Wire for LA Earthing.

### 3. CABLING:

- I. DC CABLING: for interconnection of panels single Core 4 Sq. MM Tinned Copper Cable (DC Cable)

- II. **SYSTEM CABLING:** for interconnection of Protection devices like AC DB, DC DB etc Single Core 6 Sq. MM Copper Multi stand Cable
- III. **AC CABLING:** From AC DB to Load BUS BAR 6 Sq MM 4 Core Aluminum cable.

4. **SCOPE OF WORK:**

The project is complete turn-key basis, the scope includes-

- Supply of Material as per BOQ.
- Delivery onsite
- Installation and Commissioning.

5. **Warranty:**

- For UPS 24 Months from the date of Supply.
- For battery 36+24 Months from the date of Supply.
- For Panel- 25 Years from the date of supply as per OEM terms.
- For Remaining Systems from BOQ- 5 Years from the date of Supply.
- Note: Warranty as per standard terms of OEM.

6. **Payment:**

- Advance With P.O. 80%
- After installation- 20%

7. **Warranty:**

The entire Project has fully 5 Year {60 Months} Warranty against all defects in components, material and workmanship supplied by us. We will undertake all repairs / replacement of the goods / parts as required during the warranty period at free of cost to Client. The warranty will be subjected to Manufacturer's terms and conditions.

Industry accepted standard warranty for 5 years shall be provided for Inverter. Manufacturer warranty for performance of solar panels 90% Power efficiency for 10 years, 80% Power efficiency for next 15 years

These warranty provisions will be null & void, if the goods are opened in the absence of four engineers / authorized persons or without our prior written consent and also for mishandling / modification of plant post its commissioning and handing over to the Client.

8. **Force Majeure:**

The following clauses which substantially affect the performance of the Contract shall only be considered as Force Majeure conditions.

✓ Natural phenomena, including but not limited to floods, droughts, and earthquakes, heavy rains, cyclones and epidemics.

Bank Details :-

Shri Krishna sales, Kalamb

BANK ICICI

Account no. 281905500021

Ifsc code. ICIC0002819

Thank u

श्री कृष्णा सिलस  
Mr. K.V. Thakur  
श्री कृष्णा सिलस, लोका रोड, कलंब  
For: 92219938009