

223



# UJJWAL

AGRO FOOD INDUSTRIES

Fully Automatic Flour Mill Plant Manufacturer

An ISO 9001 - 2015  
Certified Company

Quote

GST No.: 24AIXPG9815G2ZT

PAN No.: AIXPG9815G

Date: 16-Jan-2022

Valid Until: 16-Feb-2022

Quote: Quo/2021-22/570

Customer ID: N/A

**FULLY AUTOMATIC FLOUR MILL PLANT , 800  
KG/HOUR CLEANING AND 400 KG/HOUR FLOUR**

Customer:

**SURMAI FARMERS PRODUCER CO. LTD.**  
AT POST. DASWEL , TALUKA. SHINDKHEDA  
DISTRIC - DHULE, PIN. 425407

Project Description/Condition

Delivery time = 35 days, Transportation charge extra.  
One Year Warranty On Machine, Panel board & wiring charge extra.  
35% Payment Advance At The Time Of Order, Balance At Delivery Time.  
Installation Facility And Machine Trial Provide By Us.

S R No	DESCRIPTION	SIZE ( L / W / H )	QTY	H.P. ( RPM )	Line Total
1	MULTY GRAIN CLEAING MACHINE ( 4 SCREEN ROUND GRADER) CAPACITY = 800 KG/HOUR ( AS PER WHEAT) With extra different types of 6 screen Destoner machine for removing stone Grv. pestoner machine for weight grading Precleaner system with blower , cyclone , cleaner system Lifting bucket elevator = 18 feet x 1800 rate , (4/3.75/3" bucket)	( 9/ 5/ 10) feet	1.00	1 (960)	185,000.00
2	WHEAT CRUSHER MACHINE FOR REMOVING BRAIN LAYER with high carbon steel net and 20 cutter arms	( 4/ 2/ 4 ) feet	1.00	2 (960)	28,000.00
3	EXTRA LIFTING BUCKET ELEVATOR , ( 4/ 3.75/ 3 INCH BUCKET) Total 2 extra elevators = 33 feet x 1800 rate = 59400 with high grade p.v.c bucket and 6 mm cotton belt	( 5/ 1/ 15 ) feet	2.00	0.5 (960)	59,400.00
4	SCREW CONVEYOR = 10 FEET x 2000 RATE 6 inch inner worm diameter	( 10/1/1 ) feet	1.00	0.5 ( 960 )	20,000.00
5	STORAGE TANK FOR WHEAT STORAGE 2000 kg each tank capacity with high strength c - chanel structure	( 4/4/7 ) feet	2.00	0.00	70,000.00
6	Heavy duty Flourmill , 24" emery stone = 2 nos x 42000 with pully , v - belts , v - belt cover with 2 pair red emery stone , 4 nos.	( 5/ 3/ 5 ) feet	2.00	15 (1440)	84,000.00
7	CENTRIFUGAL MACHINE FOR FLOUR SEPARATE with 54 gg naylone germon net with box engle structure	( 12/ 4/ 15 )feet	1.00	3 ( 960 )	170,000.00
8	PNEUMATIC SYSTEM FOR CENTRIFUGAL MACHINE with 7.5 hp high presure blower with airlock , cyclone , exhaust, piping system		1.00	7.5 ( 2800 )	150,000.00
9	Motor = 1+3+0.5+0.5+2+0.5+0.5+0.5+15+15+3+7.5			<b>TOTAL = 49 H.P</b>	192,555.00

Crompton/Havels Brand Use For Induction Motor

Our Bank Detail

ICICI BANK

A/c. No. 261405500498

RTGS / NEFT -IFSC CODE :- ICIC0002614

Veraval (Shapar) Branch, Dist.Rajkot, Gujarat.

**TOTAL 958,955.00**

**GST 5 % 47,947.75**

**INSTALATION CHARGE 15000**

**TOTAL AMOUNT 1,021,902.75**