



TUSKER MATERIALS HANDLING PVT. LTD.

(formerly known as Jaldoot Materials Handling Pvt. Ltd)

ISO 9001:2015 Certified

EL-39/2,MIDC,Bhosari,Pune-411026,Phone:020-40776666,40776611 Fax No. 020-40776622

E-mail : mktg@jaldoot.com website : www.jaldoot.com

GSTN No : 27AAACJ4190K1ZD

Quotation

Our Ref.No. QTN/SALES/22-23/00349

Date :23/07/2022

Revision No. 01

Revision Date :25/07/2022

To,

Shreeagro Krushi Farmers Producer Company Ltd.

Sno 116/4, Office No 308 Wall Street -24 Near Cipla Foundation, Warje,
Pune - 411058,
MAHARASHTRA,
India.

GSTN No :

Kind Attn. : Mr. Sunil T

Contact No. : 7385985060

Sub : Your Requirement For : Hand Pallet Truck & Dock Leveler

Ref : As per your enquiry mail received dated on 22 July 2022

Dear Sir,

With reference to above ,we are pleased to submit our offer for the subject item required by you as follow:-

HPT
Dock Leveler

Sr. No.	Product Description	Model/Item Code	HSN CODE	HSN Rate	Quantity	Rate/Each Rs.	Amount
1	Hand Pallet Truck -THPT- 25 Capacity-2500-Kgs. Fork Lift Height-201-MM. Width Over Forks-560/685-MM. Fork Length-1220-MM. Fork Width-160-MM. Fork Lowered Height-86-MM. Load Wheel Material-Nylon- Load Wheel Type-Tandem- Load Wheel Size-83 X 70-MM. Steering Wheel Material-Nylon- Steering Wheel Size-200 X 50-MM. Finish Colour-Blue- Material of Construction-M.S.-	THPT- 25	842710	18 %	4	18000	72000.00
2	Dock Leveler TDL-90 Capacity-9000-Kgs. Platform Type-Chequered- Platform Length-2700-MM. Platform Width-2100-MM. Lip Type-Hydraulic-MM. Lip Length-350-MM. Working Range - Above-300-MM. Working Range - Below-250-MM. Parking Height-480-MM. Buffers-Yes- Finish Colour-Yellow- Material of Construction-M.S.- Special Instructions 1.-Side Flap for safety along length side-	TDL-90	842810	18 %	2	235000	470000.00

COMMERCIAL TERMS AND CONDITIONS



05) CGST(CGST 9) -:9.00%

06) SGST(SGST 9) -:9.00%

All duties and taxes will be payable by you extra as applicable at the time of supply. Rates in force currently are Indicated above,

Price Basis : Price quoted above is Ex-works Bhosari,Pune. Unpacked

Freight : Extra at Actual

Delivery Period : Within 4-5 Weeks

Payment Term : 60% advance , Balance against PI prior to despatch

Delivery Term : Door Delivery - Freight Extra

Transit Insurance : Borne By Customer

Validity : 15 Days

Inspection : The Equipment can be inspected at our works prior to dispatch at the following Address :
TUSKER MATERIALS HANDLING PVT. LTD.
EL-39/2.M.I.D.C.,Bhosari,Pune:411026

Warranty : **1. For Battery Operated Equipments**
These equipments are covered against faulty components and workmanship by our standard warranty for a period of 12 months from the date of commissioning or 2,000 working hrs. whichever is earlier.

2. For AC Mains/Power Operated Equipments

These equipments are covered against faulty components and workmanship by our standard warranty for a period of 15 months from the date of supply OR 12 months from the date of commissioning, whichever is earlier.


3. For Manual Operated Equipments

These equipments are covered against faulty components and workmanship by our standard warranty for a period of 12 months from the date of supply.

Force Majeure : Neither party shall be liable in damages or have the right to terminate this contract for any delay or default in performing hereunder If such delay or default is caused by conditions beyond its control including, but not limited to Acts of God, natural disasters, pandemics, Government restrictions, wars, riots, strike, lockouts, insurrections and/or any other cause beyond the reasonable control of the party whose performance is affected.

We trust this meets with your approval and look forward to receiving your valued order at as early date.

Yours faithfully
FOR TUSKER MATERIALS HANDLING PVT. LTD.

Authorised Signatory


Enclosed :