

553
Er. Parmanand S. Patel

B.E. (Civil)

Engineer & Govt. Contractor

45, Nandurbar Tal. Nandurbar Dist. Nandurbar

Date:

Ref: PSP/QTN/29/2021-22

13 JAN. 2022

M/S Vanashree Farmers Producer Co. Ltd. Shahada

Plant Address: 52/1,52/2 Nandarkheda Tal. Shahada

Dist. Nandurbar-425422

Kind Attn: Mr. Yogesh D. Nandre

Sub: Our Offer for All Civil & Engineering Works for your Warehouse construction (1000 MT)

With reference to our last discussion after increasing our work scope, our offer for complete turnkey based construction of your Warehouse consisting of

Capacity & Details:

- 1) Capacity : 1000 MT
- 2) Area: Main Building: 617.10 SQ. MTR

Total B/UP: 655.69 SQ. MTR

Enclosed:

- A- Covering Letter
- B- Project Cost Sheet
- C- Estimate


Dear Sir,

We thank you very much for the opportunity to offer turnkey based construction for our Warehouse Project.

We understand that our offer is in line with your requirements. We would be anxiously awaiting your reply. We would be keen to discuss our proposal with you.

Thanking You & Assuring you of our best services all times.

With warmest regards.



Amपाल
CHAIRMAN
Vanashree Farmers Producer Company Limited
Shahada, Tal. Shahada Dist. Nandurbar

Tour Sincerely

Prptil
Er. PARMANAND SHARAD PATEL
B. E. (Civil)
Engineer & Govt. Contractor
Mb.No.: 9970343710

Date DATE: 13 JAN. 2022

**PROPOSED CONSTRUCTION OF WAREHOUSE BUILDING (1000 MT)
VANASHREE FARMERS PRODUCER CO. LTD. SHAHADA
52/1,52/2 AT NANDERKHEDA, TAL-SHAHADA, DIS-NANDURBAR, M.S.
425409**

ABSTRACTS (SSR 2021-22)

Sr. No.	Description Of Item	Quantity	Unit	Rate In Rs.	Amount In Rs.
1	Excavation - Excavation for foundation in earth, soils of all types, sand, gravel and soft murum, including removing the excavated material upto a distance of 50 metres eyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift from 1.5m to 3.0m) By Manual Means (SSR/Item No-21.03)	497.664	CuM	306	152285.184
2	Rubble Soling In Footing - Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete. (SSR/Item No-21.38)	41.472	CuM	1294	53664.768
3	RCC Footing, Column and Beam - Providing and laying Cast in situ/Ready Mix cement concrete M-30 of trap / granite/quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. columns as per detailed designs and drawing or as directed including Steel centering formwork, cover blocks laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). with fully automatic	290.862	CuM	7006	2037779.172




Am Patel
CHAIRMAN
Vanashree Farmers Producer Company Limited
Shahada, Tal. Shahada Dist. Nandurbar

	microprocessor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) (SSR/Item No. 25.15)				
4	PCC - Providing and laying Cast in situ Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) (SSR Item No.24.01)	20.736	CuM	5538	114835.968
5	Reinforcement - Providing, cutting, bending, hooking, tying and laying in position TMT FE 500 steel bars for reinforcement for all RCC works as per detailed drawings etc. complete. (SSR/Item No.14.01)	18.84	CuM	69888	1316689.92
6	Sand Filling in Foundation - Providing and filling in the foundation with sand of approved quality including watering, compacting etc. complete. (To be executed with prior approval of Superintending Engineer) (SSR/Item No.21.39)	414.72	CuM	2172	900771.84
7	Rubble Soling In Plinth - Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.(SSR/Item No-21.38)	277.2	CuM	1294	358696.8
8	Brick Masonry In Plinth - Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete (SSR/Item No.27.05)	48.68	CuM	7570	368507.6
9	Plastering - Providing sand faced plaster externally and internally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete. (SSR/Item No.32.11)	232.96	SqM	599	139543.04




CHAIRMAN
 Vanashree Farmers Producer Company Limited
 Shahada, Tal. Shahada Dist. Nandurbar

10	<p>Bed Concrete - Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel cantering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic microprocessor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) (SSR/Item No.25.11)</p>	92.4	CuM	6666	615938.4
11	<p>Brick Masonry In Superstructure - Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete (SSR/Item No.27.05)</p>	237.958	CuM	7570	1801342.06
12	<p>Plastering In Super structure - Providing sand faced plaster externally and internally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete. (SSR/Item No.32.11)</p>	1433.6	SqM	599	858726.4
13	<p>GI Sheet - Providing and fixing corrugated galvanised iron sheets of 0.63mm thick (24 B.W.G.) for roofing and side without wind tiles including fastening with galvanised iron screws and bolts, lead and bitumen washers as per drawing etc. complete.(Weight of 5.5 Kilogram/sq.m.) (SSR/Item No.38.04)</p>	1050	SqM	816	856800
14	<p>Truss - Providing structural steel work in trusses, other similar trussed purlins and members with all bracing, gusset plates etc. as per detailed designs and drawings or as directed including cutting, fabricating, hoisting, erecting fixing in position, Making riveted/ bolted/ welded connection and one coat of anticorrosive paint and over it 2 coats of oil painting approved quality and shade etc. complete. (SSR/Item No.23.04)</p>	17.514	MT	105909	1854890.226



Am Patel

CHAIRMAN
 Vanashree Farmers Producer Company Limited
 Shahada, Tal. Shahada Dist. Nandurbar

15	Rolling Shutter - Providing and fixing rolling shutter fabricated from steel laths of minimum thickness 0.9 mm with lock plate of 3.15 mm thickness reinforced with 35 x 35 x 5 mm angle section fitted with sliding bolts and handles for both sides, deep M.S. channel section of depth and thickness not less than 65 mm and 3.15 mm respectively with hold fast arrangements, M.S. Bracket plate 300 x 300 x 3.15 mm minimum size and shape with square bar, suspension shaft of minimum 32 mm diameter, hood cover of M.S. sheet not less than 0.9 mm thickness and of any size at top and safety devices including mechanical gear operation arrangement consisting of worm gear wheels and worms of high grade cast iron or mild steel and one coat of red lead primer etc. complete. (I.S.62481979) (With mechanical gear) (SSR/Item No.39.25)	21	SqM	4730	99330
14	Steel Ventilators - Providing and fixing steel ventilator fully glazed partly fixed as per detailed drawing with hot dip zinc coating including fabricating glazing with plain / obscured glass pans 5 mm thick and approved type quality and iron oxidized fixtures and fastening with guard square bars 12 mm 10 cm c/c and oil painting 2 coats etc. complete. (SSR/Item No.39.30)	34.56	SqM	4449	153757.44
TOTAL					11683558.82
Add 10% for Electrification Charges					1168355.882
GRAND TOTAL					12851914.7

Note:

All prices include sales tax, labour charges, transportation, Electrification charges at the appropriate rate.

This estimate is an approximation and is not guaranteed.

The estimate is based on information provided from the client regarding project requirements. Actual cost may change once all project elements are finalized or negotiated.

Prior to any changes of cost, the client will be notified.

This Quotation is valid for 30 Days of quotation date.



Amptil
CHAIRMAN
 Vanashree Farmers Producer Company Limited
 Shahada, Tal. Shahada Dist. Nandurbar

Amptil
Er. PARMANAND SHARAD PATEL
 B. E. (Civil)
 Engineer & Govt. Contractor
 Mb.No.: 9970343710