"GENERAL REPORT"

Name of work : Yeshwanti Agro Producer Company Limited, Aitwade Khurd. construction of godown 500MT (16.50m x 30.50m)

Estimated cost : **6309,314.00 (Sixty Three Lakh Nine Thousand Three Hundred Fourteen) (Excluding GST & royalty charges)**

Authority : **Project Director DEPARTMENT OF AGRICULTURE SANGLI**

Necessity : For Provide all soybean information (soybean seeds, fertilizers, storage, sales,) farmers/growers, processed for the marketing purpose & supply to the farmers.

Provision : **Godown**

Foundation: - Frame structure r.c.c. footing & columns in M-20 grade cement concrete. Beams, lintels, ratrack, chajjas provided in r.c.c. M-20 grade concrete.

Plinth: Plinth height considered 1.15 M. above general ground level filling hard murum, 80 mm metal solling 20 cm. Angular brocken glasspieces to restrict the entry of rodent, Sand 15 cm, PCC 1:4:8 bed concrete 10cm.

Flooring: - Trimex flooring in M-151 (1:2:4) cement concrete 100 mmf thick with floor with groove cutting @ 4.0 M. Both way,

Superstructure: - Brick masonary in cement mortar 1:6 with ptasterl innerside-12mm thick in 1:5 with neeru & outerside-2Qmm thick plaster in 1:5

Roof: - Trussless roof with PPGL sheet 1.00mm thick

Doors: - M. S. Rolling shutters 2"0m x 2.50m (3 Nos)

Ventilator: - Z type ventilator with 6 mm thick wired glass at sill level and below tie beam level 2"0m x 0.75m (33Nos)

Colouri`ng: - Waterproof cement paint externally & White wash internally

Site of Building : Yeshwanti Agro Producer Company Limited, Aitwade Khurd.
Gat No. 607, Tal:Walwa, Dist: Sangli, Maharashtra, Pin: 415 409.
Emai.:- hanmantpatil55534@gmail.com
Mob: +91 9146649038.

Rates : As per D.S.R. 2021- 22 excluding lead charges of materials.

Specifications : The work will be executed as per standard specifications of P. W. D. Govt. of Maharashtra.

वासुदेव आर. पाटील