

Mr. Dipak Chandra Chakravarti (B.E. Civil) Member of Institution of Engineers (India) No. 101174284  
 Mr. Sankar Chakravarti (B.E. Civil) Member of Institution of Engineers (India) No. 101174285  
 Mr. Ananta Chakravarti (B.E. Civil) Member of Institution of Engineers (India) No. 101174286  
 Mr. Ananta Chakravarti (B.E. Civil) Member of Institution of Engineers (India) No. 101174287  
 Mr. Ananta Chakravarti (B.E. Civil) Member of Institution of Engineers (India) No. 101174288

Client: Kisan Development Agri-Industrial Company Limited, Sangamachwar  
 Address: 63/2, 7th Main Road, Sangamachwar, Tal. Sangamachwar, Dist. Raichur

**Estimate For Coconut Storage & Coir Production Industrial Shed**  
(Connected To Main Building)

Sl. No.	Length	Breadth	Depth	Number	Quantity	Unit	Rate	Amount
<b>Excavation</b>								
Excavation for foundation in laterite rock (soft or hard) including trimming and levelling the bed for the foundation, removing the excavated material up to a distance of 50 metres beyond the building area, stacking as directed, dewatering and back filling with available murum, watering, ramming etc. complete. (Lift upto 1.5								
Wall 5	10	0.5	1.5	2	15.00	M3		
Wall 11	46	0.5	1.5	1	34.50	M3		
					<b>49.50</b>	<b>M3</b>	1,507	74,597
<b>Plinth Level</b>								
<b>RC</b>								
Providing and laying Cast in situ/Ready Mix cement concrete in M20 of trap/granite/quartzite/gneiss metal for steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.), with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)								
Wall 5	10	0.55	0.05	2	0.55	M3		
Wall 11	46	0.55	0.05	1	1.27	M3		
					<b>1.82</b>	<b>M3</b>	7,002	12,709
<b>Course Outside Masonry</b>								
Providing coursed outside masonry second sort of trap / granite / quartzite / gneiss stones in cement mortar 1:6 on external walls of plinth including bailing out water manually, striking joints inside and raking out joints from outside and watering etc. complete								
Wall 5	10	0.45	0.4	2	3.60	M3		
Wall 11	46	0.45	0.4	1	8.28	M3		
					<b>11.88</b>	<b>M3</b>	11,780	1,39,946
<b>Brickwork</b>								
Providing second class Burnt Brick masonry with conventional / I.S. type bricks in cement mortar 1:6 in foundations and plinth of outer walls/ in plinth external walls including bailing out water manually, striking joints in compressed bases, raking out joints on exposed faces and watering etc. Complete.								
Wall 5	10	0.25	1.5	2	5.29	M3		
Wall 11	46	0.25	1.5	1	15.87	M3		
					<b>21.16</b>	<b>M3</b>	8,077	1,70,909





