



SANKALP

ER. RAJ SHIVBA SURVE.

ENGINEER & CONTRACTORS
BE civil

DATE – 15- SEP- 2022


Contact NO. : 9284397578
rsurve333@gmail.com

Planning, Estimation, Valuation, Consultants

PROPOSED CONSTRUCTION OF **CASHEW FACTORY UDDYOG** OF **UNNATI MAHILA PRABHAG SANGHA, HATKHAMBA, TAL. DIST. RATNAGIRI MAHARASTRA 416701**

Sr. NO.	ITEM DISCRPTION	QUENTITIOY	RATE	AMOUNT
1	EXCAVATION FOR FOUNDATION	39.5M3	615	24292.00
2	PROVIDING & LAYING PCC IN FOOTING AND PLINTH	34.58M3	6000	207480.00
3	FILLING IN PLINTH WITH MURRUM	140 M3	350	49000.00
4	LATERITE STONE MASSONRY IN FOOTING & PLINTH	30.27 M3	7000	211890.00
5	LATERITE STONE MASSONRY IN SUPAESTRUCTURE	82 M3	7000	574000.00
6	PROVIDING AND CASTING LINTEL BEAM	7.5 M3	25000	187500.00
7	PROVING INTERNAL CEMENT PLASTER	484 M2	400	193600.00
8	PROVING EXTERNAL CEMENT PLASTER	283 M2	500	141500.00
9	PROVING CIRAMIC TILES	308 M2	1100	338800.00
10	PROVING ALUMINIUM WINDOW	27 M2	3500	94500.00
11	PROVING STEEL GRILES	27 M2	2250	60750.00
12	PROVING DOOR PANELS WITH DOOR FRAME	8 NO.S	9500	76000.00
13	PROVING STEEL COLOR COATING ROOFING SHEET	322 M2	1500	483000.00
14	PROVING ELCTRIC WIRING AND FETTING	LUMSUM	--	150000.00
15	PROVING PLUMBING AND FETTING	LUMSUM	--	50000.00
TWENTY EIGHT LACKS FORTY TWO THOUSANDS THREE HUNDRED TWELVE ONLY.			TOTAL	2842312.00

NOTE – THIS ESTIMATE IS CALCULATED IN 15/09/22 ON THE BASIS OF RATE IN RATNAGIRI. THERATE MAY VARY AS PER MARKET AND TIME.


Raj Shivba Surve
BE CIVIL
Engineer and Contractor
Mob. 9284397578

