

Ref. No.

Date :

Date :- 31.12.2021

To,

SHIVKHANDI FARMERS PRODUCER COMPANY LIMITED
AT-SHIRADHON TQ. KANDHAR DIST-NANDED .

Sub:- Quotation .

R/ Sir ,

Pls. find below prices for your kind reference.

S/n	Description	Price/Unit	Qty.	Total
01.	Dell Laptop Intel core i5 11 th Gen. / 8 GB RAM / 256 GB SSD + 1 TB HDD / 2 GB GRAPHICS / WINDOWS 10 + MS OFFICE	66,000.00	01	66,000.00
02.	EPSON L 3250 AIO PRINT / SCAN / COPY / WI-FI	14,800.00	01	14,800.00
03.	EPSON LX-310 DOT MATRIX PRINTER	10,500.00	01	10,500.00
04.	5 KVA SINE WAVE INVERTOR	55,000.00	01	55,000.00
05.	EXIDE TUBULAR 150 AH BATTERY	14,500.00	04	58,000.00
06	Lenovo AIO Desktop Intel Core i5-10 th Gen. / 8 GB RAM / 1 TB HDD / 21.5 " Monitor / Windows 10 / Ms Office	80,000.00	03	2,40,000.00
07	CCTV System 32 Channel DVR , 20 Camera , 2 Power Supply . 4 TB HDD , 32 " LED TV , Cable , Connector	1,80,000.00	01	1,80,000.00
08	Biometric Attendance Machine	10,500.00	01	10,500.00
09	EPBX SYSTEM 8 PORT With Installation and Instruments	22,000.00	01	22,000.00
10	Fire Alarm System	38,500.00	01	38,500.00
			Grand Total	6,95,300.00

Terms & conditions :-

1. Prices are inclusive of all taxes and duties.
2. Validity till 15 days .
3. Delivery within 15 Days.
4. Payment 100 % advance .

Thanking You.



For PACIFIC INCORPORATION
GST NO. :- 27ADWPS7912E1ZY



VENKAYANNI
FURNITURE WORKS

VENKAYANNI FURNITURE WORKS

Shop - Near Veerabhadra Mah College, Main Road, CHITTOOR, New MARKET (100000)

Factory - Plot No. P-29, Backside Ruby Hotel, M.D.C. CHITTOOR, New MARKET (100000) E. Road, Chittoor, Andhra Pradesh

Quotation

Date: 27/12/2022

TO,
Shivkandi Farmers Producers Co Ltd,
Shiradhan, Ta, Kandhali.

Plywood Office Table	03 No. X 20000/-	= 60000/-
Shelf Rack Plywood	04 No. X 25000/-	= 100000/-
1 Visitor Chairs	20 No. X 1000/-	= 20000/-
1 Revolving Chair	06 No. X 5000/-	= 30000/-
1 Steel Cupboard	03 No. X 10000/-	= 30000/-
Aluminium Partition Size - 20' X 20'	400 sq.ft X 400/-	= 160000/-
Visitor Sofa Set	03 No. X 35000/-	= 105000/-
Computer Table	05 No. X 10000/-	= 50000/-
		<u>555000/-</u>
	+ GST 18%	96422/-

651422/-

Arjun

Mob: 9959331456
9429826471

No. AE / OSMANNAGAR / TECH / ESTT / 203

Date:- 29.12.2021


To,
DY.E. Engineer
M.S.E.D.C.L.
O & M Sub-Dn. Loha

Sub :- Submission of Technical Estimate for Shivkhandi Farmer Producer Company Ltd at
Shiradhon Gut No 968 Under 1.3% DDF Scheme Tq Kandhar Dist Nanded.

In Connection to the above, Please find enclosed herewith
Submission of Technical Estimate for Shivkhandi Farmer Producer Company Ltd at Shiradhon Gut
No 968 Under 1.3% DDF Scheme Tq Kandhar Dist Nanded.

The estimate sanction vide EE/NANDED RURAL/TECH/2020-21 /Estt/1.3 % DDF / Dt.
For an amounting Rs. 439109 /- The Estimate is proposed under
DPDC SCHEME

Scheme for the Year 2020-21.


Assistant Engineer
M.S.E.D.C.L.
Osmanagar Unit, कं. न.
उस्मानगर, शाखा

Maharashtra State Electricity Distribution Company Limited
O. & M. Division, Nanded Rural,


Name of Estimate:- Submission of Technical Estimate for Shivkhandi Farmer Producer Company Ltd at Shiradhon Gut No 968 Under 1.3% DDF Scheme Tq Kandhar Dist Nanded.

Provision :- 11 kV Line 0.18 km

Sr.No.	Particular	Unit	Qty	Rate	Amount
1	RSJ 116x100, 9 m long	No.	0	9254.00	0
2	PSC Pole 9 Mtr (200 KG)	No.	0	2260	0
3	RSJ 116x100, 10 m long	No.	0	10283.00	0
4	RSJ 116x100, 11 m long	No.	3	11311	33933
5	11 kv guarding channel MS 75x40	Kg.	90	51.8	4662
6	M.S.Channel 75x40x6 mm	Kg.	90	51.8	4662
7	MS angle 50x50x6 mm	Kg.	100	51.8	5180
8	11 KV V cross arm with clamp	No.	3	639	1917
9	11 KV Top fitting with clamp	No.	3	91	273
10	11 kV Pin Insulators with G.I. Pins	No.	10	135	1350
11	Disc Insulator 11 KV 70 KN.	No.	6	344	2064
12	Strain Hardware for 55 Sq.mm AAAC	Set	3	140	420
13	AAAC 55 mm ²	Rmt	600	28.56	17136
14	H.T.Stay Set	Set	2	598	1196
15	G.I.Stay Wire 7/4mm(8 SWG)	Kg.	30	57.45	1723.5
16	Earthing Sets H.T	Set	3	342	1026
17	G.I.Barbed Wire 'A' type.	Kg.	5	64.27	321.35
18	Danger Board	No.	3	50	150
19	Concreting ration 1:3:6	Cmt.	3	3027	9081
20	Red Oxide Paint for 2 coats	Ltr.	2	85	170
21	Aluminium Paint for 1 coat	Ltr.	2	113	226
22	G.I.Wire 8 SWG/ 6 SWG	Kg.	5	57.4	287
23	Sundries such as N/B, Washers, Welding etc.	LS	3	810	2430
				Sub-Total	88207.85
a) T.&P 1.5%,Contingencles 3%, Transportation 4%, & Labour Charges @ 10%-----				10.00%	8820.79
				Sub Total	97028.64
b) G. E. C. &H.O.Supervision Charges @ -----				1.30%	1261.372255
				Total	98290.01

SAY RS/-

98290


Assistant Engineer
M.S.E.D.C.L.
Osmannagar Unit
उस्माननगर, शाखा

DY.E.Engineer
M.S.E.D.C.L.
Loha S/Dn.

Executive Engineer,
M.S.E.D.C.L.
O & M Div.Nanded Rural.

Name of Estimate:-


Submission of Technical Estimate for Shivkhandi Farmer Producer Company Ltd at Shiradhon Gut No 968 Under 1.3% DDF Scheme Tq Kandhar Dist Nanded.

Provision :- Erection of 200 KVA :- 1 no.

Sr.No.	Particular	Unit	Qty	Rate	Amount
1	Dist T/F 200 KVA 11/0.433 KV	No.	1	195137.00	195137.00
2	RSJ 116x100, 9 m long	No	2	9254	18508.00
3	MS Flat 50mm x 6mm (2.4 kg/meter)	Kg.	100	48.5	4850.00
4	MS Channel 100mm x 50mm x 6mm (9.2	Kg.	150	51.8	7770.00
5	MS Channel 75mm x 40mm x 6mm (9.2	Kg.	150	51.8	7770.00
6	MS angle 50mm x 50mm x 6mm (4.1 Kg /	Kg.	120	51.8	6216.00
7	11 Kv Pin Insulator with GI pins	No.	12	135	1620.00
8	Strain Hardware for 55 Sq.mm AAAC	No.	6	140	840.00
9	L.T. Dist. Boxes 100 KVA with MCCB	No.	1	12822	12822.00
10	L.As. 9 KV (Gapless type) with disconnector	Set	5	1268	6340.00
11	Stay set HT	Set	7	598	4186.00
12	stay wire 7/4 mm 8 SWG	Kg.	5	57.45	287.25
13	Earthing set HT	Set	10	342	3420.00
14	H.G. Fuse 11 Kv	Set	5	1964	9820.00
15	Dangour boards	No.	10	50	500.00
16	G.I. Wire 8 SWG/ 6 SWG	Kg.	20	57.4	1148.00
17	G.I. Barbed Wire 'A' type.	Kg.	20	64.27	1285.40
18	DTC Metring with Box, single core L.T. XLPE cable (70 sq.mm., 120 mtr length) and other allied material.	No.	1	7529.2	7529.20
19	Concreting ratio 1:3:6	CMT	5	3027	15135.00
20	Painting/Hardware & support with numbering of pole	ls	3	225	675.00
21	Sundries	ls	3	810	2430.00
				Sub-Total	305858.85
a) T.&P 1.5%, Contingencies 3%, Transportation 4%, & Labour Charges @ 10%-----				10%	30585.885
				Sub Total	336444.74
b) G. E. C. & H.O. Supervision Charges @ -----				1.30%	4373.781555
				Total	340818.52

Say Rs/-

340819


Assistant Engineer
M.S.E.D.C.L.
Osman Nagar, Nanded.
उस्माननगर, शाखा


DY.E.Engineer
M.S.E.D.C.L.
Loha S/Dn.

Executive Engineer,
M.S.E.D.C.L.
O & M Div. Nanded Rural.

ESTIMATE REPORT

Name of Estimate:- Submission of Technical Estimate for Shivkhandi Farmer Producer Company Ltd at Shiradhon Gut No 968 Under 1.3% DDF Scheme Tq Kandhar Dist Nanded.

- | | | |
|----|--------------------------|--|
| 1] | Provision:- | 1] 3Ph 4W LT line : - 0.0 km |
| | | 2] 11 kV Line 0.18 km |
| | | 3] Erection of 200 KVA :- 1 no. |
| 2] | Amount Of Estimate :-Rs. | 439109 |
| 3] | Supply of System:- | 440V/11000 Volts A.C. 50 Hz |
| 4] | Rough length | as above |
| 5] | Size of cond. | 11 kv ACSR Dog
L.T. :- AAC Ant & Gnat |
| 6] | % Voltage Regulation :- | Within Limit |
| 7] | % Anticipated R. R.:- | N.A. |
| 8] | T/F Capacity :- | Existing T/F
Propose T/F |
| 9] | Budget Head | 1.3 % DDF |


Assistant Engineer
M.S.E.D.C.L.
Osmanhgir Unit
उस्मानगिर, सावना

DY.E.Engineer
M.S.E.D.C.L.
Loha S/Dn.

Executive Engineer,
M.S.E.D.C.L.
O & M Div.Nanded Rural.