

# Samarth Ripening

Sr No 165, Malwadi, Hadapsar, Pune 411028.  
Mob No: 09822526468, 09673637878  
Email- Samarthripening@gmail.com

Ref.: SR/2021-22/14  
Date: 27/01/2022

## Quotation

To,  
Sonhira Agro Farmer Producer Company Ltd.  
Mohityanche Vadgaon,  
Tal – Kadegaon, Dist – sangli  
GST No. – 27ABCCS7381N1ZN

### SUBJECT: PROPOSAL FOR COLD ROOM.

Dear Sir,

We take this opportunity to inform you that, we have successfully implemented several projects for **Fruit Ripening Cum Cold Rooms**

We are pleased to submit our final and competitive detailed offer comprising of;

- Product Summary & Commercial terms and conditions
- Technical Specifications
- Scope of supply

We hope the above details are in line with your requirement and we now look forward to receive your valued order at the earliest.

Should you require further clarifications / Information, Please feel free to contact us.

Assuring our Best of services always.

Thanking You,  
Yours truly,

॥ श्री सद्गुरु ॥

# Samarth Ripening

Sr No 165, Malwadi, Hadapsar, Pune 411028.  
Mob No: 09822526468, 09673637878  
Email- Samarthripening@gmail.com

Ref.: SR/2021-22/14  
Date: 27/01/2022

1. Supply of PUF sandwich panel's floor puf Slabs, Hinged doors, Puf density 40 Kg/m<sup>3</sup> PPGI 0.5mm for Wall and Ceiling Panel with Prefab Puf. Including Installation accessories like angle flasher, rivets and Sealants etc. For Floor Insulation Loose Puf slabs, Vapor Barrier Polythene Sheets etc. will be supplied by us for laying prior to Flooring work (**Kota stone**) which to be carried out by customer at own expenses. (Customer's Scope)

## 2. COLD ROOM SIZE (External Dimension)

Length	Width	Height	Qty.
15 Ft	15 Ft	10 Ft	2 Nos.

Wall & Ceiling Panel Area      **140 Square Meter.**  
Floor Panel Area                      **42 Square Meter.**  
Ceiling & Roof Panel thickness   **60 mm**  
Floor    **60 mm**

## 3. Hinge Door

Width	Height	Thickness	Qty.
1200 mm	2100 mm	60 mm	2 Nos.

# Samarth Ripening

Sr No 165, Malwadi, Hadapsar, Pune 411028.  
Mob No: 09822526468, 09673637878  
Email- Samarthripening@gmail.com

Ref.: SR/2021-22/14  
Date: 27/01/2022

1. **Puf Panel and Doors**

2. **Condensing Unit & Evaporating Unit (3TR 2Nos.)**

Air cooled condensing of with suitable hermetically sealed  
Compressor to achieve the above temperature with  
**EMERSON** Make comp. complete

With receiver, Service valves, Driers, Liquid Solenoid valves.

**Temperature Control Panel**

Under/Over Voltage Protection Single Phase and Phase reversal safety  
Minilec/Subzero Make High Pressure & Low Pressure Protection Inbuilt  
In condensing unit. Cold Room Controller Fitted in Control Panel Box  
With MCB, Indicating Lamps, Contactors, Overload Relay Etc.

3. Ethylene Gasing System (SS 2 Stage Regulators /  
Gas Manifold with Shutoff Valves)

---

**Total Material Supply Cost**

**11,70,424/-**

GST Extra @ 18%

**Installation & Commissioning charges Inclusive**

**Transportation Cost Extra**

Ex. Delhi  
Ex. Indore  
Ex. Pune

# Samarth Ripening

Sr No 165, Malwadi, Hadapsar, Pune 411028.

Mob No: 09822526468, 09673637878

Email- Samarthripening@gmail.com

Ref.: SR/2021-22/14

Date: 27/01/2022

<b>MODEL</b>	ARB-304 Nos. Two for each chamber
Room Dimensions to be maintained	15 x 15 x 10 feet 2 rooms
Design Room Temperature	+ 2°C (Product Resins)
<b>Indoor cooling unit</b>	Fan Motors <b>300 mm Dia. x 3 Nos.</b> Air flow <b>3000 Cu.Mtr/Hr</b> Type <b>Ceiling Suspended with Air Defrost</b>
<b>COMPRESSOR DATA</b>	
Type	Hermetic compressor Emerson make <b>3.0TR</b>
Refrigerant ( First Charge )	R-22
Brake Horse Power (BHP) (Approx) and Cooling Capacity	<b>4.060000 BTU/Hr at +7 Deg Evap.</b> <b>+ 45 Deg Condensing Temp.</b>
<b>CONDENSER DATA</b>	
Mode Of Cooling	<b>AIR COOLED Horizontal Discharge Of Air With Service Valve and Filter Dryer, Receiver, Solenoid valve, HP LP switches</b>
Type	TUBE AND FINNED COIL
<b>CONTROL PANEL</b>	
Single Phase and phase reversal safety	Selec Make
High Pressure & Low Pressure Protection	Inbuilt in condensing unit
Cold Room Controller	Fitted in Control Panel Box with MCB, Indicating Lamps, Contactors, Overload Relay Etc.
Electrical Cable & Copper Tubing	Upto 10 Meters Only In Our Scope

# Samarth Ripening

Sr No 165, Malwadi, Hadapsar, Pune 411028.  
Mob No: 09822526468, 09673637878  
Email- Samarthripening@gmail.com

Ref.: SR/2021-22/14

Date: 27/01/2022

## TERMS & CONDITIONS

### **Validity: -**

Our offer is open for acceptance for a period of 15 days from the date of this offer and thereafter it shall be subject to our written confirmation.

### **Specifications: -**

In line with our policy of continual improvement we reserve the right to modify the design and change the specifications of any material, if in our opinion such Modification constitutes an improvement or is in accordance with revised standards of manufacturing methods. Therefore, specifications, illustrations, dimensions and weights given or agreed to by us in our proposal, catalogues, drawings, Photographs etc. are not binding in detail and are approximate only.

### **Price: -**

The quoted prices are on Ex Pune basis, Transport charges will be Extra at Actual.

### **GST: -**

GST excluded and will be charged extra as applicable at the time of Execution of the Order.

### **Insurance: -**

All equipment and materials to be supplied against customer's risk. If customer desire to opt for transit insurance, it is to be intimated in advance and extra charges to be borne by customer.

### **Delivery Period: -**

4-5 weeks from the receipt of your technically and commercially clear order with advance. The delivery period is indicated in good faith. We will Endeavour to keep the delivery schedule, which is based on current manufacturing program. The above delivery is subject to force Majeure. Delay in delivery will not render the contract void able or reject goods on Account of delay in delivery.

### **Terms of Payment: -**

70% advance along with the purchase order and balance 25% should be released against Delivery note before dispatch & remaining 5% immediately after completion of installation work

### **Warranty: -**

Subject to terms of payment agreed upon being punctually complied With and the equipment being operated properly, the machinery covered by this Contract carries a Warranty against manufacturing defects for 12 months from the date of installation, If any Part of the equipment is put to use earlier for any reason, whatsoever, the warranty Period will commence from the date of such use.

For Samarth Ripening

# Samarth Ripening

Sr No 165, Malwadi, Hadapsar, Pune 411028.  
Mob No: 09822526468, 09673637878  
Email- Samarthripening@gmail.com

Ref.: SR/2021-22/14  
Date: 27/01/2022

We agree to repair / replace such parts which may prove defective and which do not fail from neglect or misuse or faulty operation. Should, However, the services of our qualified men be required outside limits Our Standard charges for such services will apply

**Property Rights and General Lien: -**

As unpaid vendors we shall retain the property rights in the equipment and material Supplied by us under this contract and our rights of lien and resale, until full value thereof as per our bill is paid to us.

During installation & commissioning certain materials deliberately sent in extra quantity to avoid inconvenience. Any such extra material after finishing installation job remains the property of Company and will be taken back suitably. Customer should not claim for such excess material.

**Limitation to Liability: -**

In no event shall we be liable for any consequential loss or damage arising out of or connected with this order in any way whatsoever.

**Cancellation Charges: -**

If any order or part of the order is cancelled, the same shall be subject to cancellation charges including compensation for costs, expenses and losses incurred by us up to the date of cancellation.

**Force Majeure: -**

No liability shall attach to us for non-performance or delayed execution of this order as a result of force majeure.

**Liquidated Damages:-**

Notwithstanding anything to the contrary, we regret our inability to be liable for any Liquidated damages on account of delay of supply / installation for any reason whatsoever.

**Inspection:-**

Inspection of goods shall be arranged at our premises

For Samarth Ripening

# Samarth Ripening

Sr No 165, Malwadi, Hadapsar, Pune 411028.  
Mob No: 09822526468, 09673637878  
Email- Samarthripening@gmail.com

Ref.: SR/2021-22/14  
Date: 27/01/2022

## SCOPE OF WORK

Our scope of work includes installation, testing and commissioning of your Initial Setting up of Cold Storage for your room(s).  
Electrical cables, Copper Tubing & Insulation Upto 10 Meters Only in our scope. Beyond that Will be charge Extra.

## CUSTOMER SCOPE

1. Fabricated Stand with protective canopy for provision for keeping condensing units.
2. Stable Voltage 380-430 Volts Electrical Supply with suitable Breaker ( MCB) and Power Distribution Panel near to units and **lighting work within and outside Rooms**
3. Arrangement of Nitrogen (N2) & Oxygen(O2) if required will be borne by customer.
4. All sort of Civil Work, Kota Flooring, Water Line Plumbing etc. work wherever Required.
5. Providing level base/floor (zero – zero level) for erection of walk-in-Cold room.
6. Provisions of water drain point for condensed water at points specified by you.
7. Water, light, electricity and covered storage space shall be provided to you free of Cost near the work site.
8. You will have to provide the required sunshade water protection truss structure.
9. Support for various equipments will be provided by You.
10. Unloading of all the equipments at site and safe storage of the same Will be Buyer's responsibility.
11. Arrangement for 2 to 3 person during Installation, but food and other expenses will be borne by Our company.