

# LUBNYMASH

SINCE 1888

## COMMERCIAL PROPOSAL

December 11th, 2021



№	Technological equipment	Amount	Price USD, FCA Ukraine	Sum USD, FCA Ukraine
<b>Storage facilities:</b>				
1.	Galvanized metal silo MSVU 092.08.B12 with the kit of ventilation, thermal probe - silo capacity – 660 Cubic meter (528 tons for 0.8 t/m3) - silo diameter – 9200 mm - the amount of layers - 8 - the total height of the silo – 11.964 meter the silo (EU steel S350GD) - body and roof outer ladder with safety rails - service manholes - fasteners: bolts for roof and body assembling with strength class 8.8, with nuts, washers and sealing - the strengthened stiffening ribs (two on each panel) - high limit level probe - the set of ventilation and thermal probes (for measuring the temperature of the grain) - active ventilation - bottom fans - 4 units 7.5 kWt and 1 roof fan 0,25kWt Upper level limit sensor (rotary type) – 1 pc	1	32 885	32 885
<b>AUXILIARY EQUIPMENT:</b>				
1.1.	Screw sweeping conveyor URPK250, L=4.35m	1	2 925	2 925
<b>Total sum on FCA delivery terms</b>				<b>35 810</b>

**Special Discount- 6240 USD**  
**Net Total - 30 435 USD**  
**Approximate delivery cost for one full-set silo unit (CIF Mumbai) – 3 100 USD**

**Sum with delivery included up to Mumbai Port – 32670 USD**

INR CALCULATION FINAL

TOTAL SILO COST- 24,50,250.00

Custom duty @10%- 2,45,025.00

Social welfare fund on custom [duty@10%](#) -24,502.00

Total taxable value - 27,19,777.00

GST @ 18%- 4,89,559.00

Handling charges- 25,000.00

Transport- 84,548.00

**Grand Total INR- 33,18,884.00**

Respectfully  
Director

Yuriy Pleskach