

प्रति,

विषय-मा.बाळासाहेब ठाकरे कृषी व्यवसाय व ग्रामीण परिवर्तन (स्मार्ट) प्रकल्पांतर्गत सन २०२३-२४ मध्ये कार्यालय दुरुस्ती (नुतनीकरण) करणेकरिता खरेदी दरपत्रक मागविण्याबाबत.....

जागतीक बँक अर्थसहाय्यीत मा.बाळासाहेब ठाकरे कृषी व्यवसाय व ग्रामीण परिवर्तन (स्मार्ट) प्रकल्पांतर्गत सन २०२३-२४ मध्ये कार्यालय दुरुस्ती (नुतनीकरण) करणे करिता आपल्याकडून सिलबंद दरपत्रक मागविण्यात येत आहे.

१) खालील वस्तूच्या पुरवठासाठी दरपत्रक मागविण्यात येत आहे.

Sr.	Item Work	Quantity	Unit
१.	Solid Core Flush door Single leaf Providing and fixing factory made solid core flush door in single leaf 35 mm thick, decorative types, of exterior grade, as per detailed drawings, conforming to I.S.:2202 - 1962 (Revised) with approved face veneers on both faces with/without glazing and venetians in the positions shown on the drawings or as directed, all necessary beads, moulding and lipping, holdfasts, mat finish stainless steel fixtures fastenings , finishing with french-polish/ waxing complete. (without door frame).(Sample to be got approved from Ex.Engineer before use) Commercial Hard Wood shutter	3.61	SQM
२.	Medium Height Partition @ 1800/1200HT TILE BASED PARTITION SYSTEM:- Tile based Aluminum partition system of 1800/1200 mm ht. made of 60mm thk aluminum frames having two separate race ways for laying electrical & computer wiring. The wire management shall be through to the race way to be fitted at bottom of partition and other immediately below of work top with hook on type raceway cover for easy access of wires. Frames to be joined by aluminum connectors with M6 x 16 pan-head machin screw and washer with aluminum post cover. Post cover of snap on fashion to be connected on aluminum connectors. All visible aluminium to be in anodized finish. The top/ exposed sides of the frame and posts should be covered with horizontal/ Vertical trim and caps made of	4.85	SQM

	Aluminum in anodized finish in order to enhance its look.Upper tiles of partition to be in Soft Board or Marker tile of 9mm. thk., and prelaminated partial board lower tiles in laminate finish of 9mm. thk. on both the sides.		
3.	Providing and fixing False ceiling of 12 mm thick Laminated board with frame of M.S. angle 40 x 40 x 5 mm and Tee of size 40 x 40 x 6mm at 60 cm c/c including 12 mm dia. hangers, T.W. battens 50 x 25 mm and beading 25 x 15 mm thick scaffolding if necessary, all Iron work etc. complete.	27.50	SQM
4.	Providing and applying priming coat on concrete/ masonry/ Asbestos Cement plastered surfaces including scaffolding if necessary, preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter and sand papering as required etc. complete.	39.24	SQM
5.	Scrapping the old plastered internal surface with sand paper and coating the entire surface with mixture of whiting or glue and linseed oil including scaffolding etc. complete as directed.	39.24	SQM
6.	Providing and applying plastic emulsion paint of approved quality, colour and shade to old surface in three coats including scaffolding, preparing the surface. (excluding primer coat) etc. complete.	39.24	SQM
7.	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete. Bd. L.2 Page One Number 368	9.81	SQM
8.	Providing & Fixing in position, Carpet more than 800+ gsm, made with 100% stain proof fibres of approved make along with 5mm underlay as per Architectural & Acoustical Design & Instructions & Complete in all aspects including all materials labour, finishing etc complete	27.50	SQM

Electrification-

Sr.	Item Work	Quantity	Unit
1.	Switch Point With Wire, Cassing patti, Wages and etc	30	No.
2.	Power Point With Wire, Cassing patti, Wages and etc	03	No.
3.	A C Point With Wire, Cassing patti, Wages and etc	02	No.
4.	Phone point With Wire, Cassing patti, Wages and etc	04	No.
5.	LED Light Point With Wire, Cassing patti, Wages and etc	08	No.
6.	Submeter Point With Wire, Cassing patti, Wages and etc	01	No.
7.	Wire Circuit Point With Wire, Cassing patti, Wages and etc	200	No.
8.	Plugh Point With Wire, Cassing patti, Wages and etc	14	No.
9.	MCB Point With Wire, Cassing patti, Wages and etc	01	No.

२) निविदा दरपत्राचे अटी व शर्ती :-

- वर नमुद केलेल्या मालाच्या संपुर्ण पुरवठ्याचे कंत्राट असेल.
- पुरवठादाराने दरपत्रातील किमती GST वगळून सादर कराव्या.
- कंत्राट संपेपर्यंत बोलीतल्या सर्व किमती अपरिवर्तन असतील. त्यात कोणतीही तडजोड होणार नाही.
- सर्व किमती भारतीय रुपयातच नमुद कराव्यात.

३) दरपत्रक मागणी पत्रातील पात्रतेनुसार आपल्या संस्थेचे दर न्यूनतम आले आणि आपल्याला पुरवठा/कार्यारंभ आदेश देऊनही आपण पुरवठा करण्यास असमर्थता दर्शविल्यास आपले नाव काळ्या यादीत टाकण्यात येईल. तसेच अशी कामे करून घेणाऱ्या इतर यंत्रणांना आपले नाव काळ्या यादीत टाकल्याबाबत कळविण्यात येईल.

४) एक संस्था एकच दरपत्रक सादर करेल.


५) दरपत्रकावर फोन नंबर, संपुर्ण पत्ता, असावा. दर पत्रामध्ये कोणतीही खोडतोड करू नये. खोडतोड झाल्यास त्यावर सही करून दिनांक नमुद करावी.

६) दरपत्रासोबत pan card, shopact किंवा संस्था नोंदणी प्रमाणपत्र, उलाढाल प्रमाणपत्र, GST प्रमाणपत्र, EMD प्रमाणपत्र, काळ्या यादी बाबत प्रमाणपत्र इत्यादी छायांकित कागदपत्रासह बंद लिफाफ्यामध्ये सादर करावे.

७) दरपत्रक वैधता- दरपत्रक सादर करण्याच्या अंतिम मुदतीनंतर किमान एक महिना वैध राहिल.

८) दरपत्राचे मुल्यांकन- सहया केलेल्या सर्व अटींची पूर्तता करणाऱ्या दरपत्रकाचे मुल्यांकन केले जाईल.

- ९) दरपत्रकामध्ये नमुद संख्या मागणीनुसार कमी जास्त होऊ शकते.
- १०) पुरवठा आदेश- सर्वात कमी किमतीचे आणि योग्यरीत्या पुर्ण केलेले दरपत्रक सादर करणाऱ्या पुरवठादारास पुरवठा देण्यात येईल.
- ११) पुरवठा आदेश प्राप्त होताच कार्यालय दुरुस्ती (नूतनीकरण) ७ दिवसांच्या आत पुर्ण करावे.
- १२) तुमच्या कडील दरपत्राचा प्रतिसाद दिनांक 26/06/2023 रोजी वेळ सायंकाळी ५.०० वाजेपर्यंत अपेक्षित आहे.
- १३) कार्यालयाचे नाव व पत्ता- प्रकल्प संचालक आत्मा, अमरावती, विसावा कॉलनी, जुना बायपास रोड, या ठिकाणी दिनांक 27/06/2023 रोजी वेळ सकाळी ११.०० वाजता उघडण्यात येईल.



प्रकल्प संचालक,
आत्मा, अमरावती